

BILL NO 01 PRELIMINARIES

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P1	Preliminary and General Requirements Tender Drawings	Notes	All items will be priced individually. Any item not priced hereunder will be deemed to be included in the Contractors Tender.	Item	0	0.000	0.000
P2	Preliminary and General Requirements Tender Drawings	Tender Drawings	The Tender Drawings are listed in Volume 4 Tender Drawings.	Item	1	0.000	0.000
P3	Preliminary and General Requirements Conditions of Contract	Conditions of Contract	The Conditions of Contract shall be those contained within the Sultanate of Oman Standard Documents for Building and Civil Engineering Works prepared and issued by the Ministry of Finance Muscat.	Item	1	0.000	0.000
P4	Preliminary and General Requirements Conditions of Contract	Conditions of Contract	The Contractor shall allow for complying in all respect with the Conditions of Contract.	Item	1	0.000	0.000
P5	Preliminary and General Requirements Contractors Administration Arrangements	Drawings	The Contractor shall be responsible for checking all drawings and schedule etc. supplied by the Engineer. In the event of any discrepancy being found between such drawings and schedules etc. or if the Contractor considers that additional detail drawings are required then in either case the Contractor shall report such discrepancy to the Engineer for instruction or apply in writing for such detail drawings at least 28 days before the materials and components necessary for the works are to be placed on order by the Contractor.	Item	1	0.000	0.000
P6	Preliminary and General Requirements Contractors Administration Arrangements	Drawings	The Contractor shall ascertain from the drawings or otherwise any holes recesses plugs etc. which may be required in time to form these as the work proceeds. No extra payments will be allowed for cuttings or forming such holes subsequently.	Item	1	0.000	0.000
P7	Preliminary and General Requirements Contractors Administration Arrangements	Drawings	The Contractor will prepare at his own cost detailed working and shop drawings that may require supplementary to the construction drawings furnished by the Engineer.	Item	1	0.000	0.000
P8	Preliminary and General Requirements Contractors Administration Arrangements	Drawings	The detail and working drawing for civil and building works shall be prepared by the contractor supplement the construction drawings furnished by the Engineer will include Reinforcement details and Other drawings.	Item	1	10,500.000	10,500.000
P9	Preliminary and General Requirements Contractors Administration Arrangements	Drawings	The detail and working drawing for civil and building works shall be prepared by the contractor supplement the construction drawings furnished by the Engineer will include the Drawings and details of foundation for equipment machinery and technical installation.	Item	1	10,500.000	10,500.000



BILL NO 01 PRELIMINARIES

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P10	Preliminary and General Requirements Contractors Administration Arrangements	Drawings	Such drawing and detail will depend on the type and make of the equipment offered and will include in particular foundations etc. for the standby power generators chiller and radiators transformers ventilation and airconditioning equipment etc. Construction details as required.	Item	1	0.000	0.000
P11	Preliminary and General Requirements Contractors Administration Arrangements	Drawings	No drawing etc. prepared by the Contractor shall be used in the works before the Engineer has approved it.	Item	1	0.000	0.000
P12	Preliminary and General Requirements Contractors Administration Arrangements	Drawings	The Contractor shall submit to the Engineer for his approval two copies of all his detail working or shop drawings and related documents produced by him for use in construction work. Any changes or modifications considered necessary by the Engineer shall be made at no extra cost to the Employer.	Item	1	0.000	0.000
P13	Preliminary and General Requirements Contractors Administration Arrangements	Drawings	Drawings and other documentation submitted to the Engineer for approval during the construction period should in no case be submitted later than two weeks before the date when the drawings or documents will be required on site for construction purpose.	Item	1	0.000	0.000
P14	Preliminary and General Requirements General Instruction	DESCRIPTION OF THE WORKS	The work under this Contract comprises the provision of all materials plant and labour of whatever kind necessary and the proper performance of every operation required for the complete and proper construction completion commissioning and maintenance of Proposed 20 Nos Housing Units at Halaniyat Island including civil structural mechanical and electrical services and external works. The exact scope of work is indicated in the Tender Drawings.	Item	1	0.000	0.000
P15	Preliminary and General Requirements General Instruction	GENERAL INSTRUCTIONS	The Tenderer shall insert a lumpsum or rate to each individual item Clause or SubClause in this Bill which he considers has a financial implication or is of financial value. Where the Contractor considers that an item Clause or SubClause has no financial value he shall insert the word Nil. Lump Sums shall not be inserted covering more than one item Clause or SubClause.	Item	1	0.000	0.000
P16	Preliminary and General Requirements General Instruction	GENERAL INSTRUCTIONS	The value of services and obligations involved in all the items Clauses and SubClauses in this Bill shall not be included in rates or prices in other Bills of Quantities but shall be priced in their totality in this Bill.	Item	1	0.000	0.000
P17	Preliminary and General Requirements Contractors Administration Arrangements	Contractors Administrative Arrangements	No examination or approval by the Engineer of any drawing or order documents submitted by the Contractor shall relieve the Contractor of any of his responsibilities under the Contract.	Item	1	0.000	0.000



BILL NO 01 PRELIMINARIES

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P18	Preliminary and General Requirements Contractors Administration Arrangements	Site Administration	The Contractor shall allow for providing all that is required for the proper administration of the Contract at site level and in particular for complying in all respects with the relevant Clauses in the Standard Conditions of Contract.	Item	1	0.000	0.000
P19	Preliminary and General Requirements Contractors Administration Arrangements	Site Inspection	The Contractor is advised to visit and inspect the site during tendering at his own cost and hire own boat and to satisfy himself as to the accessibility and full extent and character of the site and of all local conditions and restrictions including the provision of and any matter referred to in Clause 11 of the Conditions of Contract..	Item	1	0.000	0.000
P20	Preliminary and General Requirements Contractors Administration Arrangements	Access to the site	Access to the site will be from existing roads adjacent to the site. Access to the site may be obtained by prior arrangement with Engineer. During the construction and maintenance stages the Contractor will be responsible for complying with all of the Employers security and safety requirements.	Item	1	0.000	0.000
P21	Preliminary and General Requirements Contractors Administration Arrangements	Access to the site	During construction the Contractor will afford access to the site to any persons or Company employed directly by the Employer for the purpose of carrying out work at the site and will liaise with that person or company to agree a work procedure to ensure a mutually beneficial programme of work and to provide such services as are required in accordance with Clause 31 of the Conditions of Contract.	Item	1	0.000	0.000
P22	Preliminary and General Requirements Contractors Administration Arrangements	Access for Plant	The Contractor should allow for all costs involved in making access arrangements for any items of plant etc. without risk of damage to roads leading to the site and such like and for reinstatement thereto.	Item	1	0.000	0.000
P23	Preliminary and General Requirements Contractors Administration Arrangements	Limitations of Working Space	The Contractor shall confine his apparatus the storage of materials and the operations of the workman to the site and shall not be unreasonably encumber the area with his materials.	Item	1	0.000	0.000
P24	Preliminary and General Requirements Contractors Administration Arrangements	Limitations of Working Space	The Contractor shall be entirely responsible for complying with municipality regulations regarding fencing the site storage of materials and spoil heaps unloading of materials temporary building sanitary arrangements etc. No claims for delay or costs will be entertained in the event of work being stopped for breach of regulations.	Item	1	0.000	0.000
P25	Preliminary and General Requirements Contractors Administration Arrangements	Limitation of Working Hours	Any work which in accordance with Clause 45 of the Conditions of Contract or by agreement with the Engineer executed outside of normal working hours or on Fridays or Public Holidays shall be carried out in such a way as to cause the absolute minimum of disturbance or inconvenience to the Residents or users of the buildings near or adjacent to the works.	Item	1	0.000	0.000



BILL NO 01 PRELIMINARIES

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P26	Preliminary and General Requirements Contractors Administration Arrangements	Limitation of Working Hours	The Contractors specific attention is drawn to the clauses in the specification relating to restriction of placement of certain items of work in certain weather/temperature conditions and he is to allow for complying with these requirements.	Item	1	0.000	0.000
P27	Preliminary and General Requirements Contractors Administration Arrangements	Restrictions	The site shall not be used for any purpose other than the execution of the Contract.	Item	1	0.000	0.000
P28	Preliminary and General Requirements Contractors Administration Arrangements	Restrictions	The Contractor will be required to make good any damage to the surrounding properties caused during the execution of the work and to restore to their original condition after the completion of the works.	Item	1	0.000	0.000
P29	Preliminary and General Requirements Contractors Administration Arrangements	Restrictions	Vegetation and trees are not to be cut down or in any way interfered with even if shown on the drawings to be removed or breached until the Engineers permission has been obtained.	Item	1	0.000	0.000
P30	Preliminary and General Requirements Contractors Administration Arrangements	Vegetation and Trees	Prevent damage to vegetation and trees and provide protection for them in accordance with the Specification. Pay all costs and charges incurred in complying with statutes and regulations regarding trees	Item	1	0.000	0.000
P31	Preliminary and General Requirements Contractors Administration Arrangements	Vegetation and Trees	The Contractor shall ascertain for himself the location of existing services on under or over the site. He shall take precautions to protect all such services within the confines of the site temporarily divert as required reinstate on completion and immediately make good any damage at his own expense all to the satisfaction of the Engineer.	Item	1	0.000	0.000
P32	Preliminary and General Requirements Contractors Administration Arrangements	Existing Services	The Contractor shall ascertain for himself the location of existing services on under or over the site. He shall take precautions to protect all such services within the confines of the site temporarily divert as required reinstate on completion and immediately make good any damage at his own expense all to the satisfaction of the Engineer.	Item	1	1,575.000	1,575.000
P33	Preliminary and General Requirements Contractors Administration Arrangements	Existing Services	Allow for locate protect uphold temporarily divert if necessary and maintain all pipes ducts drains sewers service mains overhead or underground electrical telephone cables etc. during execution of the Works. The Contractor shall make good any damage to existing services and/or property however caused at his own expense or pay any costs or charges in connection. Approval shall be obtained a minimum of two weeks in advance of any planned interruption of services.	Item	1	1,575.000	1,575.000
P34	Preliminary and General Requirements Contractors Administration Arrangements	Existing Services	Existing services and their locations may not be fully shown on the drawings and the Contractor shall liaise with the relevant authorities to determine the exact nature and full extent of such services which require protection and maintenance.	Item	1	0.000	0.000



BILL NO 01 PRELIMINARIES

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P35	Preliminary and General Requirements Contractors Administration Arrangements	Supervision	Detailed Curriculum Vitae of the Contractors Supervisory staff together with those of his SubContractors Supervisors must be submitted for the Engineers approval prior to commencement of the Works.	Item	1	0.000	0.000
P36	Preliminary and General Requirements Contractors Administration Arrangements	Supervision	The Project Manager Project Engineer shall not be changed without one months written notice to the Engineer.	Item	1	0.000	0.000
P37	Preliminary and General Requirements Contractors Administration Arrangements	Security	Allow for providing security to the site. Only those staff and workpeople directly employed on this project will be allowed on site.	Item	1	0.000	0.000
P38	Preliminary and General Requirements Contractors Administration Arrangements	Safety Health and Welfare of Workpeople	Provide for all costs and charges incurred by complying with all safety health and welfare regulations appertaining to staff and workpeople employed on the site including those employed by all SubContractors.	Item	1	0.000	0.000
P39	Preliminary and General Requirements Contractors Administration Arrangements	Safety Health and Welfare of Workpeople	The Contractor shall be responsible for and shall allow for providing medical facilities including emergency medical facilities for his staff and shall make these available to the Engineers staff.	Item	1	0.000	0.000
P40	Preliminary and General Requirements Contractors Administration Arrangements	Safety Health and Welfare of Workpeople	Allow for all costs for providing protective clothing and accessories for all workmen and supervisory staff on site.	Item	1	0.000	0.000
P41	Preliminary and General Requirements Contractors Administration Arrangements	Safety Health and Welfare of Workpeople	Contractors and Subcontractors operatives will not be allowed to eat and sleep on site at any time. Proper shaded areas are to be provided within the site establishment for Contractors and Subcontractors operatives to ensure they do not move outside the site premises.	Item	1	0.000	0.000
P42	Preliminary and General Requirements Contractors Administration Arrangements	Transport of Workpeople	Allow for the cost of all transport to and from site of the workpeople engaged on the site in approved vehicles.	Item	1	0.000	0.000
P43	Preliminary and General Requirements Contractors Administration Arrangements	Constructional PlantSmall Plant and Tools	Provide for all necessary small plant and tools for the proper execution and completion of the Contract.	Item	1	0.000	0.000
P44	Preliminary and General Requirements Contractors Administration Arrangements	Constructional PlantScaffoldingw orking platforms	Provide all necessary temporary scaffolding and working platforms for the proper execution and completion of the Contract. Alter relocate and adapt from time to time as necessary. The Contractor is to ascertain whether any scaffolding or platform is required by any SubContractor before striking. If the Contractor should strike any of his scaffolding or working platform and it is so required it shall be reerected at his own expenses.	Item	1	0.000	0.000
P45	Preliminary and General Requirements Contractors Administration Arrangements	Constructional PlantPlant required for Specific Trades	Provide all necessary plant required for specific trades for the proper execution and completion of the Contract.	Item	1	0.000	0.000



BILL NO 01 PRELIMINARIES

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P46	Preliminary and General Requirements Contractors Administration Arrangements	Constructional PlantCranes and Lifting Plant	Allow for all cranes and lifting plant necessary for the safe and efficient execution of the works to the satisfaction of the Engineer.	Item	1	0.000	0.000
P47	Preliminary and General Requirements Contractors Administration Arrangements	Constructional PlantPlant generally	Allow for all other plant necessary for the safe and efficient execution of the Works.	Item	1	0.000	0.000
P48	Preliminary and General Requirements Contractors Administration Arrangements	Transport for Work People	The Contractor is to allow for obtaining an adequate labour force for the Works and is to include for transport men to and from the Site as is necessary.	Item	1	0.000	0.000
P49	Preliminary and General Requirements Contractors Administration Arrangements	Site Transportation	Provide all necessary vehicles and other site transport etc. with all consumables store etc. as described for small plant and tools etc.	Item	1	0.000	0.000
P50	Preliminary and General Requirements Employer Facilities	Temporary Office	Provide erect furnish equip maintain and remove three month after completion of the Contract fully serviced furnished and equipped airconditioned offices and a conference room for the exclusive use of the Engineer all as described in General Requirement of the Architectural Specification.	Item	1	0.000	0.000
P51	Preliminary and General Requirements Employer Facilities	Temporary Office	The offices shall be provided and maintained throughout the period of the Contract.	Item	1	0.000	0.000
P52	Preliminary and General Requirements Employer Facilities	Temporary Office	The Contractor shall be responsible for providing security power water drainage safety helmets safety boots daily cleaning car parking and other facilities to the Engineers offices.	Item	1	0.000	0.000
P53	Preliminary and General Requirements Employer Facilities	Temporary Office	The Contractor shall be responsible during the continuance of the Contract for satisfactorily maintain and security of the offices and for all plans documents and paper and other articles contained there in.	Item	1	0.000	0.000
P54	Preliminary and General Requirements Employer Facilities	Telephone for the Engineer and Employer	Allow for providing the Engineers site office with an independent telephone service until removal of office and for paying all charges incurred by the Engineers staff for business calls concerning the project within the Sultanate of Oman.	Item	1	1,050.000	1,050.000
P55	Preliminary and General Requirements Employer Facilities	Attendance on the Engineer	Provide attendance and assistance to the Engineer all as described in the Specification.	Item	1	0.000	0.000
P56	Preliminary and General Requirements Employer Facilities	Surveying and other equipment	The Contractor shall provide to the Engineer for his exclusive use all survey equipment and electrical test equipment as described in the Specification.	Item	1	1,575.000	1,575.000



BILL NO 01 PRELIMINARIES

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P57	Preliminary and General Requirements Employer Facilities	Mobilisation	The Engineer may issue the notice to proceed at any time within the period of validity of the tender. After the date of the notice to proceed the Contractor shall have a period of 120 days to complete mobilisation and to be completely prepared for the work. After the mobilisation is complete the work shall be carried out in accordance with the requirements of this Contract.	Item	1	0.000	0.000
P58	Preliminary and General Requirements Employer Facilities	Programme and Order of Works	Within 14 days of receipt of an order to commence the Works the Contractor shall submit to the Engineer a detailed programme in respect of all works contained in the scope of works including temporary works and services.	Item	1	0.000	0.000
P59	Preliminary and General Requirements Employer Facilities	Programme and Order of Works	Within 21 days of receipt of an order to commence the Works the Contractor shall submit to the Engineer a detailed programme in respect of all trades separately for each building section and external works and services together with the target dates for receipt of information required to enable the Contractor to comply with this programme.	Item	1	0.000	0.000
P60	Preliminary and General Requirements Employer Facilities	Programme and Order of Works	In addition the Contractor shall at the same time submit to the Engineer a detailed schedule of items and information that he requires instruction upon for early ordering schedules.	Item	1	0.000	0.000
P61	Preliminary and General Requirements Employer Facilities	Coordination	The Contractors attention is drawn to the fact that he shall be entirely responsible for the coordination of all works carried out by both his own workmen and the workmen of SubContractors and shall be responsible for ensuring that all SubContractors shop and/or working drawings are submitted to the Engineer for approval in such time as not to prejudice the expeditious execution of the Works in accordance with the Contractors programme.	Item	1	0.000	0.000
P62	Preliminary and General Requirements Employer Facilities	Reports	Provide and maintain daily reports and delivery records for inspection by the Engineer. Such reports must give details of number and category of labour force list of plant list of material deliveries work planned and work carried out climatic conditions high and low temperature and any other information required by the Engineer.	Item	1	0.000	0.000
P63	Preliminary and General Requirements Employer Facilities	Progress Reports	Provide progress reports at intervals and in a format as required by the Engineer.	Item	1	0.000	0.000



BILL NO 01 PRELIMINARIES

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P64	Preliminary and General Requirements Employer Facilities	Progress Reports	Provide a camera on site for use by the Engineer and arrange each month to print in duplicate colour progress photographs of the works taken by the Engineer. All photographs shall be subject to the Employers security precautions and shall not be used for promotional commercial purposes without written permission of the Employer. The Contractor shall provide suitable albums for the correct storage of the above photographs. The copy rights of all photographs rests with the Employer.	Item	1	0.000	0.000
P65	Preliminary and General Requirements Employer Facilities	Site Sign Boards	The Contractor shall allow for the provision erection and maintenance of two site sign board to display the project name the names of all Consultants associated with the Works and the Contractors name all as specified and to the approval of the Engineer. The sign board shall be complete with all necessary foundations supports framing painting and sign writing in Arabic and English denoting the title of the Project name of the Employer and names of Consultants and Contractor with their respective addresses and logos. The Contractor shall provide all details of the sign board to the Engineer for his approval before any work is put in hand and to enable erection to commence in the early stages of the Contract. The Contractor shall at the completion of the Contract remove the sign board supports and foundations.	Item	1	0.000	0.000
P66	Preliminary and General Requirements Employer Facilities	Site Offices Stores and Other Facilities	The Contractor shall provide erect maintain and remove on completion all necessary site offices stores messrooms sanitary accommodation and other facilities as may be required by the Contractor for his own and his SubContractors use together with all associated water drainage electrical lighting and power airconditioning telephoneradio facilities furniture equipment and attendance.	Item	1	15,750.000	15,750.000
P67	Preliminary and General Requirements Employer Facilities	Site Offices Stores and Other Facilities	The position of all site offices stores etc. shall be to the approval of the Engineer and the Contractor must allow for all other facilities he may require to fulfil his contractual obligations additional to the area allocated to him.	Item	1	7,560.000	7,560.000
P68	Preliminary and General Requirements Contractor Facilities	Accommodation for Workmen	The Contractor will not be allowed to accommodate workpeople on the site and arrangements must be made for such accommodation elsewhere at the Contractors expense and for transporting the workforce to the site.	Item	1	15,120.000	15,120.000
P69	Preliminary and General Requirements Contractor Facilities	Communications	Provide a telephone for both his own and his SubContractors use including paying all charges in connection therewith. Radio telephone will only be permitted at the discretion of the Engineer if in his opinion it is not feasible to obtain a conventional telephone connection.	Item	1	0.000	0.000



BILL NO 01 PRELIMINARIES

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P70	Preliminary and General Requirements	Temporary worksTemporary Fencing	Allow for all temporary fencing hoardings screens gantries etc. necessary for the execution of the Works. The Contractors particular attention is drawn to the neatness and approval of the hoardings by the Authorities and the Engineer.	Item	1	1,575.000	1,575.000
P71	Preliminary and General Requirements	Temporary worksTemporary Roads	Provide maintain and alter as necessary temporary roads paths hardstandings pavement crossings and the like to and within the site. Remove and reinstate all ground and work disturbed when required.	Item	1	0.000	0.000
P72	Preliminary and General Requirements	Temporary worksWater for the Works	Provide all water required for the Works and provide and remove on completion all requisite temporary pipework pumps storage tanks etc. The Contractor must include for obtaining water from an independent source.	Item	1	525.000	525.000
P73	Preliminary and General Requirements	Temporary worksElectricity for the Works	Provide all electric light and power required for the Works including all temporary installations maintaining altering and adapting as necessary and remove all temporary installations on completion.	Item	1	525.000	525.000
P74	Preliminary and General Requirements	Temporary worksTraffic Diversions	The Contractor is to maintain at all times the flow of traffic on the existing roads and is to provide suitable signs lights and flag men at all times during the currency of the Contract all to the approval of the Authorities and the Engineer.	Item	1	0.000	0.000
P75	Preliminary and General Requirements	Temporary worksPumping and Dewatering	Provide here for all equipment and labour necessary to comply with the requirements for keeping the excavations and area of site free from surface underground running or standing water to the complete satisfaction of the Engineer to cover all such work wherever such work is not specifically measured in the relevant sections of the Bills of Quantities.	Item	1	0.000	0.000
P76	Preliminary and General Requirements	Temporary worksTemporary Lighting	Allow for installation maintenance and operation during hours of darkness a system of sufficient artificial lighting of roads paths access routes working platforms and areas where the works are in operation on site and that may be used or approached by any persons authorised to be on site and final removal from site on completion of the works.	Item	1	0.000	0.000
P77	Preliminary and General Requirements	Sundry ItemsTesting of Materials and the Works	Allow for all tests required by the Specification to be carried out including providing all necessary equipment materials and samples	Item	1	0.000	0.000
P78	Preliminary and General Requirements	Sundry ItemsSingle Sources of Supply	Where a choice of manufacturer or source of supply is allowed for any particular product of material the whole quantity required to complete the work must be of the same type manufacturer andor source. Changes will not be allowed without prior approval of the Engineer and at no cost to the Client. Written evidence of sources of supply must be produced when requested by Engineer.	Item	1	0.000	0.000



BILL NO 01 PRELIMINARIES

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P79	Preliminary and General Requirements	Sundry ItemsSamples; generally	Allow for providing and submitting to the Engineer as he may require samples of all materials and goods which the Contractor proposes to incorporate in the Works.	Item	1	0.000	0.000
P80	Preliminary and General Requirements	Sundry ItemsSamples; generally	Allow for providing sample panels of materials workmanship and mockups as required by the Specification.	Item	1	0.000	0.000
P81	Preliminary and General Requirements	Sundry ItemsSamples Marble	The contractor shall submit three samples 300 x 300 mm of each marble specified layout of slabs and detailed shop drawings showing dimensions to the Engineer and obtain his approval prior to placing order. One of the samples should be the type of marble proposed to be incorporated in the works.	Item	1	0.000	0.000
P82	Preliminary and General Requirements	Sundry ItemsSamples Marble	The other two shall indicate the closest natural variation in colour and grain of the proposed marble. All marble slabs shall be delivered on site polished and ready for installation.	Item	1	0.000	0.000
P83	Preliminary and General Requirements	Sundry ItemsSource of Marble	Tenderers are required to name the proposed suppliers of marble to be incorporated in the works this information is to be submitted with the Tender.	Item	1	0.000	0.000
P84	Preliminary and General Requirements	Sundry ItemsProtection of the Works	Allow for protecting the Works from damage from any source including inclement weather.	Item	1	0.000	0.000
P85	Preliminary and General Requirements	Sundry ItemsDisposal of refuse	Keep the site free from debris arising from the Works during the construction period and leave the site free from debris and large loose stones on completion to the satisfaction of the Engineer.	Item	1	0.000	0.000
P86	Preliminary and General Requirements	Sundry ItemsSite Clearance	Clear the site of all scrub debris rubbish etc. in accordance with the Specification.	Item	1	0.000	0.000
P87	Preliminary and General Requirements	Sundry ItemsReports	Provide and maintain all Records Site Books and Daily Reports for inspection by the Engineer.	Item	1	0.000	0.000
P88	Preliminary and General Requirements	Sundry ItemsProgress Report	Provide Progress Reports at monthly intervals in a format as required by the Engineer.	Item	1	0.000	0.000
P89	Preliminary and General Requirements	Sundry ItemsCleaning the Works	Remove protective casings and coverings and thoroughly clean the Works at completion to the entire satisfaction of the Engineer.	Item	1	0.000	0.000
P90	Preliminary and General Requirements	Sundry ItemsTraffic Regulations	Allow for complying with all traffic regulations.	Item	1	0.000	0.000



BILL NO 01 PRELIMINARIES

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P91	Preliminary and General Requirements	Sundry ItemsMaintenance of Public and Private Roads	Allow for making good any damage to public or private roads paths paved or landscaped areas. Contractors SubContractors and Suppliers vehicles must be kept in a clean condition and must not be allowed to soil public or private areas.	Item	1	0.000	0.000
P92	Preliminary and General Requirements	Sundry ItemsFire Fighting Facilities	Provide fire fighting facilities on site to the approval of the Authorities and the Engineer.	Item	1	0.000	0.000
P93	Preliminary and General Requirements	Sundry ItemsMaintenance of existing property access.	The Contractor is to maintain access to existing properties at all times with the use of steel plates ramps ducts etc. all to the approval of the Engineer.	Item	1	0.000	0.000
P94	Preliminary and General Requirements	Sundry ItemsDrying the Works	Allow for drying the works in accordance with the Specification and to the satisfaction of the Engineer.	Item	1	0.000	0.000
P95	Preliminary and General Requirements	Sundry ItemsControl of noise and pollution	Allow for keeping noise and pollution to an absolute minimum.Take all necessary precautions to reduce noise from plant by means of mufflers silencers screens and the like.Work entailing excessive noise is to be carried out during suitable hours as directed by the Engineer.	Item	1	0.000	0.000
P96	Preliminary and General Requirements	Sundry ItemsAntipollution Measures	The Contractor shall take precautions to minimize the pollution of and disturbance to lands roads and other places on and around the site.	Item	1	0.000	0.000
P97	Preliminary and General Requirements	Sundry ItemsStatutory Obligations	Allow for complying with all Statutory Obligations and for obtaining all permissions licences etc. and paying all fees as required by Statutory Authorities in connection with the carrying out of the Works.Allow for arranging inspection and the obtaining of all no objection certificates.The Contractor shall allow for complying with all building regulations.	Item	1	0.000	0.000



BILL NO 01 PRELIMINARIES

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P98	Preliminary and General Requirements	Sundry ItemsPublic Authority for Electricity and Water PAEW and Oman Telecommunications Company OMANTEL Regulations and Requirements	Public Authority for Electricity and Water PAEW and OMANTEL regulations require certain works to be carried out by specialist Contractors approved by them and it is the responsibility of Tenderers to establish the extent of such work. Tenderers will be deemed to have allowed in their rates against the various items of work for complying with Public Authority for Electricity and Water and OMANTEL regulations and where necessary for employing Public Authority for Electricity and Water and OMANTEL approved Contractors for such specialist works.	Item	1	1,050.000	1,050.000
P99	Preliminary and General Requirements	Sundry ItemsSite Survey and Grid of Levels	Before commencing excavation or site levelling operations the Contractor shall conduct a coordinated site survey witnessed by the Engineer related to a bench mark referred to in the Contract document and shall prepare a site plan showing a grid of levels at 5 m centres to the proposed site the Contractor shall provide the Engineer with one transparency and two copies of the site survey plan.	Item	1	0.000	0.000
P100	Preliminary and General Requirements	Sundry ItemsSite Survey and Grid of Levels	The Contractor shall conduct similar site survey after site levelling operations and external works have been completed and provide drawings as above.	Item	1	0.000	0.000
P101	Preliminary and General Requirements	Sundry ItemsCopies of Orders	Provide the Engineers Representative with a copy of all orders for the supply of such materials or goods required in connection with the Works as the Engineers Representative may specify.	Item	1	0.000	0.000
P102	Preliminary and General Requirements	Sundry ItemsWorking Drawings	Allow for preparing and submission to the Engineer of all working drawings and operation and maintenance instructions as detailed in the specification if these costs are not specifically measured elsewhere in the relevant sections of this document.	Item	1	0.000	0.000
P103	Preliminary and General Requirements	Sundry ItemsWorking Drawings	Upon completion of the works submit two sets of diskettes Autocad R12 later two transparencies and four copies of all drawings duly marked AsBuilt clearly defining all locations depths shapes and dimensions of all permanent works executed.	Item	1	0.000	0.000
P104	Preliminary and General Requirements	Sundry ItemsTraining of Employers Personnel	During the execution of the Works the Contractor shall provide such assistance as may be necessary for the instruction and training of personnel appointed by the Employer.	Item	1	0.000	0.000



BILL NO 01 PRELIMINARIES

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P105	Preliminary and General Requirements	Sundry Items Training of Employers Personnel	The Contractor shall provide all necessary instruction material for this purpose such as manuals booklets pamphlets drawings sketches models pictures photos colour slides films etc. This instruction material shall become the property of the Employer.	Item	1	0.000	0.000
P106	Preliminary and General Requirements	Sundry Items Direct Contractors	The Tenderers attention is drawn to the fact that the Employer may appoint other Contractors to carry out certain items of Specialist Works in accordance with Clause 31 of the Conditions of Contract.	Item	1	0.000	0.000
P107	Preliminary and General Requirements Performance Bond Advance Payment Bond and Insurance Certificate	Performance Bond	The Contractor will be required to provide Performance Bond all in accordance with Clause 4.2 of the Conditions of Contract.	Item	1	0.000	0.000
P108	Preliminary and General Requirements Performance Bond Advance Payment Bond and Insurance Certificate	Insurance	The Contractor will be required to provide all Insurances in accordance with the Conditions of Contract.	Item	1	0.000	0.000
P109	Preliminary and General Requirements Performance Bond Advance Payment Bond and Insurance Certificate	Insurance Declaration	On signing the Contract the Contractor shall obtain from his Insurance Company and lodge with the Engineer a declaration that the insurance provided is strictly in accordance with all relevant Clause in the Conditions of Contract. This shall also include insurance against damage of any kind to existing buildings which may arise as a result of the building operations.	Item	1	0.000	0.000
P110	Preliminary and General Requirements Performance Bond Advance Payment Bond and Insurance Certificate	Advance Payment Bond	The Contractor will be required to provide an Advance Payment Bond all in accordance with Clause 14.2 of Conditions of Contract.	Item	1	0.000	0.000



BILL NO 01 PRELIMINARIES

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P111	Preliminary and General Requirements Temporary Facilities.	Refer Provisional Sum Temporary Houses	The Contractor will be required to provide temporary houses Caravan for the resident while working in the Construction and also during Maintenance Works and refix inside houses after work finish as outside extra rooms for them. Every caravan will be around 65m2 and will include and not be limited to 2 rooms a hall a kitchen and two toilets The structure to use steel structure painted with anticorrosion paint with isolated walls and roof aluminum sandwich panels 50 mm thickness from 2 sheets 0.7 mm thickness and foam of 45 kgm3 density internal ceramic floor and walls for toilets and kitchen to be ceramic all sanitary fixture for toilet and kitchen sink and cabinet sewage electrical and water connection to be done in the temporary place and will be finally done again after move to internal new and maintained houses foundation for caravan and 3 steps omani marble in final place fixing also 4 AC are included design of caravan to be done by the contractor approved by client consultant before delivery the caravans will be under project defects notification period for one year.	item	1	124,800.000	124,800.000
P112	Preliminary and General Requirements CCTV Control.	CCTV	The Contractor will be required to provide CCTV to monitor and maintain the work activity at site while working in the Construction Works also during Maintenance Works.	Item	1	0.000	0.000
P113	Preliminary and General Requirements Temporary Facilities.	External Temporary Building	The Contractor should follow maintenance works for the External Building for the Existing 32 Housing while working in the Construction Works also during Maintenance Works.	Item	1	0.000	0.000
P114	Preliminary and General Requirements Engineer Employer Facilities	Facilities for Engineers Employers	The Contractor shall provide erect maintain and remove on completion all necessary Engineers accommodation Employers accommodation common kitchen with dining hall including food for all time to the Engineers Employers sanitary accommodation and other facilities all by the Contractor expenses and link together with all associated water drainage electrical lighting and power air conditioning telephone mobile phones 4nos with recharge cards 30rial new furniture washing equipment and maintenance the same until the Completion of Project as per details in prim documents.	Item	1	25,200.000	25,200.000
P115	Preliminary and General Requirements Contractors Administration Arrangements	Site Transportation for Engineers Employers	Provide necessary 4x4 vehicles 2nos in excellent condition for consultant client staff transportation and pickup vehicle 2nos for site transport etc. with all consumables fuel etc. as described for small plant and tools for regular maintenance etc as per details in prim documents.	Item	1	8,700.000	8,700.000
TOTAL PRELIMINARIES						227,580.000	



BILL NO 2 DAYWORKS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
D1	Daywork Schedule	Day Work	The Contractor may be required to execute certain works on the basis of day works.	Item	1	0.000	0.000
D2	Daywork Schedule	Day Work	The Contractor shall keep an accurate record of time spent and materials and plant and used on each separate instruction given. Day work sheets are to be numbered and are to describe fully the instructions to which they refer and they are to be fully summarized fully priced and submitted to the Engineer for signature. The submission of such day work sheets does not necessarily mean that the work will be valued under Clause 13.5 of the Conditions of Contract or that any payment is in fact due.	Item	1	0.000	0.000
D3	Daywork Schedule	Labour 1. The Tenderer shall give the rates herein required for labourers and craftsmen against each item stated. 2.The rates are to be comprehensive and include	Wages and all costs payments and charges including pensions annual and public holidays traveling time expenses fares and transport guaranteed time nonproductive time and other expenses in connection with overtime incentive and bonus payments dirty money and danger money and other disbursements arising from employment of labour including redundancy payment reduced working hours during Ramadhan all associated costs if labourers imported from other countries and workmens compensation insurance gratuity and all terminal benefits as per Oman labour Laws.	Item	1	0.000	0.000
D4	Daywork Schedule	Labour 1. The Tenderer shall give the rates herein required for labourers and craftsmen against each item stated. 2.The rates are to be comprehensive and include	Charges incurred in respect of site and office supervision including foreman's time and extra emoluments paid to foreman and leading craftsmen and gangers.	Item	1	0.000	0.000



BILL NO 2 DAYWORKS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
D5	Daywork Schedule	Labour 1. The Tenderer shall give the rates herein required for labourers and craftsmen against each item stated. 2.The rates are to be comprehensive and include	Site and Head Office overhead charges such as rent rates insurances electricity fuel water printing stationery postage telephone charges motor car expenses renewals maintenance and depreciation of premises machinery plant and the like.	Item	1	0.000	0.000
D6	Daywork Schedule	Labour 1. The Tenderer shall give the rates herein required for labourers and craftsmen against each item stated. 2.The rates are to be comprehensive and include	Profit	Item	1	0.000	0.000
D7	Daywork Schedule	Materials	Materials used in day works to be charged at invoice cost. All discounts are to be allowed to the Ministry of Health. Invoices are to be made available to the Engineer at the time the relevant day work sheets are submitted.	Item	1	0.000	0.000
D8	Daywork Schedule	Materials	The Contractor is to allow for additional percentage he requires to be added to the invoice cost of materials to cover for ordering taking delivery paying all insurances in transit landing charges dues custom duties Municipality tax and all other charges loading and transporting to the site taking into store storing as may be required and all other charges and profit.	Item	1	0.000	0.000
D9	Daywork Schedule	Plant 1. The Contractor shall give here the rates he requires for plant and machinery 2. The rates are to be comprehensive and include	Mobilization and demobilization costs	Item	1	0.000	0.000



BILL NO 2 DAYWORKS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
D10	Daywork Schedule	Plant 1. The Contractor shall give here the rates he requires for plant and machinery 2. The rates are to be comprehensive and include	Fuel oil lubricants and all other consumable stores.	Item	1	0.000	0.000
D11	Daywork Schedule	Plant 1. The Contractor shall give here the rates he requires for plant and machinery 2. The rates are to be comprehensive and include	Servicing repairs and replacements.	Item	1	0.000	0.000
D12	Daywork Schedule	Plant 1. The Contractor shall give here the rates he requires for plant and machinery 2. The rates are to be comprehensive and include	Site and Head Office overhead charges as previously defined.	Item	1	0.000	0.000
D13	Daywork Schedule	Plant 1. The Contractor shall give here the rates he requires for plant and machinery 2. The rates are to be comprehensive and include	Profit	Item	1	0.000	0.000
D14	Daywork Schedule	Plant	The rates are to include for haulage to and from site and all other charges relating to plant and shall be exclusive of attendants and drivers who shall be charged at labour rates as set out above.	Item	1	0.000	0.000
D15	Daywork Schedule	Plant	If the Contractor is unable to price the particular type of plant listed he should price for the nearest equivalent item available to him and state what has been included in his tender.	Item	1	0.000	0.000
D16	Daywork Schedule	Labour	Labourers	Hr	200	0.000	0.000
D17	Daywork Schedule	Labour	Gangers	Hr	25	0.000	0.000
D18	Daywork Schedule	Labour	Steelfixers	Hr	50	0.000	0.000



BILL NO 2 DAYWORKS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
D19	Daywork Schedule	Labour	Carpenters and Joiners	Hr	50	0.000	0.000
D20	Daywork Schedule	Labour	Tile Layers	Hr	50	0.000	0.000
D21	Daywork Schedule	Labour	Masons	Hr	50	10.500	525.000
D22	Daywork Schedule	Labour	Painters	Hr	50	10.500	525.000
D23	Daywork Schedule	Labour	Scaffolders	Hr	50	10.500	525.000
D24	Daywork Schedule	Labour	Drainlayers	Hr	50	10.500	525.000
D25	Daywork Schedule	Labour	Plumbers	Hr	50	10.500	525.000
D26	Daywork Schedule	Labour	ElectriciansA.C. Mechanics	Hr	50	10.500	525.000
D27	Daywork Schedule	Labour	Welders	Hr	50	10.500	525.000
D28	Daywork Schedule	Labour	FabricatorsFitters	Hr	50	10.500	525.000
D29	Daywork Schedule	Labour	Plant and Machinery Operators and Drivers	Hr	80	10.500	840.000
D30	Daywork Schedule	Materials	Include the Provisional Sum of Rials Omani Ten Thousand RO. 10000.000 for the cost of Local Materials expended on Dayworks. These costs shall be charged at the nett price paid by the Contractor for the materials exsupplier as substantiated by the suppliers invoices.	Item	1	0.000	0.000
D31	Daywork Schedule	Materials	Include the Provisional Sum of Rials Omani Ten Thousand R.O. 10000.000 for the cost of Imported Materials expended on daywork. These costs shall be charged at the nett price paid by the Contractor for the materials delivered C.I.F. Oman as substantiated by the suppliers invoices.	Item	1	0.000	0.000
D32	Daywork Schedule	Materials	Contractors percentage on net cost of material 5 percent	Item	1	0.000	0.000
D33	Daywork Schedule	Plant	Portable compressors Complete with hoses Delivery of free air Up to 4.6 Cumper minute	Hr	50	52.500	2,625.000



BILL NO 2 DAYWORKS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
D34	Daywork Schedule	Plant	Pneumatic hammer including steels	Hr	20	31.500	630.000
D35	Daywork Schedule	Plant	Concrete Mixers	Hr	50	21.000	1,050.000
D36	Daywork Schedule	Plant	Dumper up to 0.5 Cum bucket capacity	Hr	30	21.000	630.000
D37	Daywork Schedule	Plant	Concrete vibrator poker 50mm diameter	Hr	30	10.500	315.000
D38	Daywork Schedule	Plant	Excavators up to 0.5 Cum bucket capacity	Hr	30	10.500	315.000
D39	Daywork Schedule	Plant	Generator sets 50 KVA	Hr	50	31.500	1,575.000
D40	Daywork Schedule	Plant	Tipper truck 10 tonne	Hr	40	52.500	2,100.000
D41	Daywork Schedule	Plant	Van or utility vehicle	Hr	40	21.000	840.000
D42	Daywork Schedule	Plant	Three tonne pickup	Hr	40	31.500	1,260.000
D43	Daywork Schedule	Plant	Water tanker 2000 gallon	Hr	20	31.500	630.000
D44	Daywork Schedule	Plant	Excavator hydraulic full circle slew 1m3	Hr	20	42.000	840.000
D45	Daywork Schedule	Plant	Mobile Crane 10 tonne	Hr	25	52.500	1,312.500
D46	Daywork Schedule	Plant	Bulldozer 430hp	Hr	25	42.000	1,050.000
D47	Daywork Schedule	Plant	Loader1.5m3	Hr	25	52.500	1,312.500
D48	Daywork Schedule	Plant	Grader 200 hp	Hr	25	52.500	1,312.500
D49	Daywork Schedule	Plant	Roller 4 tonne	Hr	25	42.000	1,050.000
D50	Daywork Schedule	Plant	Welding set 300 A including electrodes	Hr	25	31.500	787.500
D51	Daywork Schedule	Plant	Oxy acetylene cutting set including electrodes	Hr	25	31.500	787.500
D52	Daywork Schedule	Plant	2 inch Water pump 5 hp	Hr	30	26.250	787.500



BILL NO 2 DAYWORKS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
D53	Daywork Schedule	Plant	4 inch Water pump 10 hp	Hr	30	36.750	1,102.500
D54	Daywork Schedule	Employee Staff	Project Manager	Hr	200	42.000	8,400.000
D55	Daywork Schedule	Employee Staff	Resident Project Engineer	Hr	200	26.250	5,250.000
D56	Daywork Schedule	Employee Staff	Resident Civil Material Engineer	Hr	200	26.250	5,250.000
D57	Daywork Schedule	Employee Staff	Resident Electrical Engineer	Hr	200	26.250	5,250.000
D58	Daywork Schedule	Employee Staff	Resident Mechanical Engineer	Hr	200	26.250	5,250.000
D59	Daywork Schedule	Employee Staff	Resident Architecture Engineer Omani	Hr	200	26.250	5,250.000
D60	Daywork Schedule	Employee Staff	Resident Quantity Surveyor	Hr	200	26.250	5,250.000
D61	Daywork Schedule	Employee Staff	Resident Draftsman Omani	Hr	200	26.250	5,250.000
D62	Daywork Schedule	Employee Staff	Resident QA QC	Hr	200	26.250	5,250.000
D63	Daywork Schedule	Employee Staff	Resident HSE Omani	Hr	200	26.250	5,250.000
D64	Daywork Schedule	Employee Staff	Cook	Hr	200	15.750	3,150.000
D65	Daywork Schedule	Employee Staff	Assistant to Cook	Hr	200	10.500	2,100.000
P66	Preliminary and General Requirements Employer Facilities	Site Offices Stores and Other Facilities	The Contractor shall provide erect maintain and remove on completion all necessary site offices stores messrooms sanitary accommodation and other facilities as may be required by the Contractor for his own and his SubContractors use together with all associated water drainage electrical lighting and power airconditioning telephoneradio facilities furniture equipment and attendance.	Item	1	0.000	0.000



BILL NO 2 DAYWORKS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P67	Preliminary and General Requirements Employer Facilities	Site Offices Stores and Other Facilities	The position of all site offices stores etc. shall be to the approval of the Engineer and the Contractor must allow for all other facilities he may require to fulfil his contractual obligations additional to the area allocated to him.	Item	1	0.000	0.000
P68	Preliminary and General Requirements Contractor Facilities	Accommodation for Workmen	The Contractor will not be allowed to accommodate workpeople on the site and arrangements must be made for such accommodation elsewhere at the Contractors expense and for transporting the workforce to the site.	Item	1	0.000	0.000
P69	Preliminary and General Requirements Contractor Facilities	Communications	Provide a telephone for both his own and his SubContractors use including paying all charges in connection therewith. Radio telephone will only be permitted at the discretion of the Engineer if in his opinion it is not feasible to obtain a conventional telephone connection.	Item	1	0.000	0.000
P70	Preliminary and General Requirements	Temporary worksTemporary Fencing	Allow for all temporary fencing hoardings screens gantries etc. necessary for the execution of the Works. The Contractors particular attention is drawn to the neatness and approval of the hoardings by the Authorities and the Engineer.	Item	1	0.000	0.000
P71	Preliminary and General Requirements	Temporary worksTemporary Roads	Provide maintain and alter as necessary temporary roads paths hardstandings pavement crossings and the like to and within the site. Remove and reinstate all ground and work disturbed when required.	Item	1	0.000	0.000
P72	Preliminary and General Requirements	Temporary worksWater for the Works	Provide all water required for the Works and provide and remove on completion all requisite temporary pipework pumps storage tanks etc. The Contractor must include for obtaining water from an independent source.	Item	1	0.000	0.000
P73	Preliminary and General Requirements	Temporary worksElectricity for the Works	Provide all electric light and power required for the Works including all temporary installations maintaining altering and adapting as necessary and remove all temporary installations on completion.	Item	1	0.000	0.000
P74	Preliminary and General Requirements	Temporary worksTraffic Diversions	The Contractor is to maintain at all times the flow of traffic on the existing roads and is to provide suitable signs lights and flag men at all times during the currency of the Contract all to the approval of the Authorities and the Engineer.	Item	1	0.000	0.000



BILL NO 2 DAYWORKS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P75	Preliminary and General Requirements	Temporary worksPumping and Dewatering	Provide here for all equipment and labour necessary to comply with the requirements for keeping the excavations and area of site free from surface underground running or standing water to the complete satisfaction of the Engineer to cover all such work wherever such work is not specifically measured in the relevant sections of the Bills of Quantities.	Item	1	0.000	0.000
P76	Preliminary and General Requirements	Temporary worksTemporary Lighting	Allow for installation maintenance and operation during hours of darkness a system of sufficient artificial lighting of roads paths access routes working platforms and areas where the works are in operation on site and that may be used or approached by any persons authorised to be on site and final removal from site on completion of the works.	Item	1	0.000	0.000
P77	Preliminary and General Requirements	Sundry ItemsTesting of Materials and the Works	Allow for all tests required by the Specification to be carried out including providing all necessary equipment materials and samples	Item	1	0.000	0.000
P78	Preliminary and General Requirements	Sundry ItemsSingle Sources of Supply	Where a choice of manufacturer or source of supply is allowed for any particular product of material the whole quantity required to complete the work must be of the same type manufacturer andor source. Changes will not be allowed without prior approval of the Engineer and at no cost to the Client. Written evidence of sources of supply must be produced when requested by Engineer.	Item	1	0.000	0.000
P79	Preliminary and General Requirements	Sundry ItemsSamples; generally	Allow for providing and submitting to the Engineer as he may require samples of all materials and goods which the Contractor proposes to incorporate in the Works.	Item	1	0.000	0.000
P80	Preliminary and General Requirements	Sundry ItemsSamples; generally	Allow for providing sample panels of materials workmanship and mockups as required by the Specification.	Item	1	0.000	0.000
P81	Preliminary and General Requirements	Sundry ItemsSamples Marble	The contractor shall submit three samples 300 x 300 mm of each marble specified layout of slabs and detailed shop drawings showing dimensions to the Engineer and obtain his approval prior to placing order. One of the samples should be the type of marble proposed to be incorporated in the works.	Item	1	0.000	0.000



BILL NO 2 DAYWORKS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P82	Preliminary and General Requirements	Sundry ItemsSamples Marble	The other two shall indicate the closest natural variation in colour and grain of the proposed marble. All marble slabs shall be delivered on site polished and ready for installation.	Item	1	0.000	0.000
P83	Preliminary and General Requirements	Sundry ItemsSource of Marble	Tenderers are required to name the proposed suppliers of marble to be incorporated in the works this information is to be submitted with the Tender.	Item	1	0.000	0.000
P84	Preliminary and General Requirements	Sundry ItemsProtection of the Works	Allow for protecting the Works from damage from any source including inclement weather.	Item	1	0.000	0.000
P85	Preliminary and General Requirements	Sundry ItemsDisposal of refuse	Keep the site free from debris arising from the Works during the construction period and leave the site free from debris and large loose stones on completion to the satisfaction of the Engineer.	Item	1	0.000	0.000
P86	Preliminary and General Requirements	Sundry ItemsSite Clearance	Clear the site of all scrub debris rubbish etc. in accordance with the Specification.	Item	1	0.000	0.000
P87	Preliminary and General Requirements	Sundry ItemsReports	Provide and maintain all Records Site Books and Daily Reports for inspection by the Engineer.	Item	1	0.000	0.000
P88	Preliminary and General Requirements	Sundry ItemsProgress Report	Provide Progress Reports at monthly intervals in a format as required by the Engineer.	Item	1	0.000	0.000
P89	Preliminary and General Requirements	Sundry ItemsCleaning the Works	Remove protective casings and coverings and thoroughly clean the Works at completion to the entire satisfaction of the Engineer.	Item	1	0.000	0.000
P90	Preliminary and General Requirements	Sundry ItemsTraffic Regulations	Allow for complying with all traffic regulations.	Item	1	0.000	0.000
P91	Preliminary and General Requirements	Sundry ItemsMaintenance of Public and Private Roads	Allow for making good any damage to public or private roads paths paved or landscaped areas. Contractors SubContractors and Suppliers vehicles must be kept in a clean condition and must not be allowed to soil public or private areas.	Item	1	0.000	0.000
P92	Preliminary and General Requirements	Sundry ItemsFire Fighting Facilities	Provide fire fighting facilities on site to the approval of the Authorities and the Engineer.	Item	1	0.000	0.000



BILL NO 2 DAYWORKS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P93	Preliminary and General Requirements	Sundry ItemsMaintenance of existing property access.	The Contractor is to maintain access to existing properties at all times with the use of steel plates ramps ducts etc. all to the approval of the Engineer.	Item	1	0.000	0.000
P94	Preliminary and General Requirements	Sundry ItemsDrying the Works	Allow for drying the works in accordance with the Specification and to the satisfaction of the Engineer.	Item	1	0.000	0.000
P95	Preliminary and General Requirements	Sundry ItemsControl of noise and pollution	Allow for keeping noise and pollution to an absolute minimum.Take all necessary precautions to reduce noise from plant by means of mufflers silencers screens and the like.Work entailing excessive noise is to be carried out during suitable hours as directed by the Engineer.	Item	1	0.000	0.000
P96	Preliminary and General Requirements	Sundry ItemsAntipollution Measures	The Contractor shall take precautions to minimize the pollution of and disturbance to lands roads and other places on and around the site.	Item	1	0.000	0.000
P97	Preliminary and General Requirements	Sundry ItemsStatutory Obligations	Allow for complying with all Statutory Obligations and for obtaining all permissions licences etc. and paying all fees as required by Statutory Authorities in connection with the carrying out of the Works.Allow for arranging inspection and the obtaining of all no objection certificates.The Contractor shall allow for complying with all building regulations.	Item	1	0.000	0.000
P98	Preliminary and General Requirements	Sundry ItemsPublic Authority for Electricity and Water PAEW and Oman Telecommunications Company OMANTEL Regulations and Requirements	Public Authority for Electricity and Water PAEW and OMANTEL regulations require certain works to be carried out by specialist Contractors approved by them and it is the responsibility of Tenderers to establish the extent of such work. Tenderers will be deemed to have allowed in their rates against the various items of work for complying with Public Authority for Electricity and Water and OMANTEL regulations and where necessary for employing Public Authority for Electricity and Water and OMANTEL approved Contractors for such specialist works.	Item	1	0.000	0.000



BILL NO 2 DAYWORKS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P99	Preliminary and General Requirements	Sundry ItemsSite Survey and Grid of Levels	Before commencing excavation or site levelling operations the Contractor shall conduct a coordinated site survey witnessed by the Engineer related to a bench mark referred to in the Contract document and shall prepare a site plan showing a grid of levels at 5 m centres to the proposed site the Contractor shall provide the Engineer with one transparency and two copies of the site survey plan.	Item	1	0.000	0.000
P100	Preliminary and General Requirements	Sundry ItemsSite Survey and Grid of Levels	The Contractor shall conduct similar site survey after site levelling operations and external works have been completed and provide drawings as above.	Item	1	0.000	0.000
P101	Preliminary and General Requirements	Sundry ItemsCopies of Orders	Provide the Engineers Representative with a copy of all orders for the supply of such materials or goods required in connection with the Works as the Engineers Representative may specify.	Item	1	0.000	0.000
P102	Preliminary and General Requirements	Sundry ItemsWorking Drawings	Allow for preparing and submission to the Engineer of all working drawings and operation and maintenance instructions as detailed in the specification if these costs are not specifically measured elsewhere in the relevant sections of this document.	Item	1	0.000	0.000
P103	Preliminary and General Requirements	Sundry ItemsWorking Drawings	Upon completion of the works submit two sets of diskettes Autocad R12 later two transparencies and four copies of all drawings duly marked AsBuilt clearly defining all locations depths shapes and dimensions of all permanent works executed.	Item	1	0.000	0.000
P104	Preliminary and General Requirements	Sundry ItemsTraining of Employers Personnel	During the execution of the Works the Contractor shall provide such assistance as may be necessary for the instruction and training of personnel appointed by the Employer.	Item	1	0.000	0.000
P105	Preliminary and General Requirements	Sundry ItemsTraining of Employers Personnel	The Contractor shall provide all necessary instruction material for this purpose such as manuals booklets pamphlets drawings sketches models pictures photoscolour slides films etc. This instruction material shall become the property of the Employer.	Item	1	0.000	0.000
P106	Preliminary and General Requirements	Sundry ItemsDirect Contractors	The Tenderers attention is drawn to the fact that the Employer may appoint other Contractors to carry out certain items of Specialist Works in accordance with Clause 31 of the Conditions of Contract.	Item	1	0.000	0.000



BILL NO 2 DAYWORKS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P107	Preliminary and General Requirements Performance Bond Advance Payment Bond and Insurance Certificate	Performance Bond	The Contractor will be required to provide Performance Bond all in accordance with Clause 4.2 of the Conditions of Contract.	Item	1	0.000	0.000
P108	Preliminary and General Requirements Performance Bond Advance Payment Bond and Insurance Certificate	Insurance	The Contractor will be required to provide all Insurances in accordance with the Conditions of Contract.	Item	1	0.000	0.000
P109	Preliminary and General Requirements Performance Bond Advance Payment Bond and Insurance Certificate	Insurance Declaration	On signing the Contract the Contractor shall obtain from his Insurance Company and lodge with the Engineer a declaration that the insurance provided is strictly in accordance with all relevant Clause in the Conditions of Contract. This shall also include insurance against damage of any kind to existing buildings which may arise as a result of the building operations.	Item	1	0.000	0.000
P110	Preliminary and General Requirements Performance Bond Advance Payment Bond and Insurance Certificate	Advance Payment Bond	The Contractor will be required to provide an Advance Payment Bond all in accordance with Clause 14.2 of Conditions of Contract.	Item	1	0.000	0.000



BILL NO 2 DAYWORKS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P111	Preliminary and General Requirements Temporary Facilities.	Refer Provisional Sum Temporary Houses	The Contractor will be required to provide temporary houses Caravan for the resident while working in the Construction and also during Maintenance Works and refix inside houses after work finish as outside extra rooms for them. Every caravan will be around 65m2 and will include and not be limited to 2 rooms a hall a kitchen and two toilets The structure to use steel structure painted with anticorrosion paint with isolated walls and roof aluminum sandwich panels 50 mm thickness from 2 sheets 0.7 mm thickness and foam of 45 kgm3 density internal ceramic floor and walls for toilets and kitchen to be ceramic all sanitary fixture for toilet and kitchen sink and cabinet sewage electrical and water connection to be done in the temporary place and will be finally done again after move to internal new and maintained houses foundation for caravan and 3 steps omani marble in final place fixing also 4 AC are included design of caravan to be done by the contractor approved by client consultant before delivery the caravans will be under project defects notification period for one year.	item	0	0.000	0.000
P112	Preliminary and General Requirements CCTV Control.	CCTV	The Contractor will be required to provide CCTV to monitor and maintain the work activity at site while working in the Construction Works also during Maintenance Works.	Item	1	0.000	0.000
P113	Preliminary and General Requirements Temporary Facilities.	External Temporary Building	The Contractor should follow maintenance works for the External Building for the Existing 32 Housing while working in the Construction Works also during Maintenance Works.	Item	1	0.000	0.000



BILL NO 2 DAYWORKS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P114	Preliminary and General Requirements EngineerEmployer Facilities	Facilities for EngineersEmployers	The Contractor shall provide erect maintain and remove on completion all necessary Engineers accommodation Employers accommodation common kitchen with dining hall including food for all time to the EngineersEmployers sanitary accommodation and other facilities all by the Contractor expenses and link together with all associated water drainage electrical lighting and power airconditioning telephone mobile phones 4nos with recharge cards 30rial new furniture washing equipment and maintenance the same until the Completion of Project as per details in prim documents.	Item	1	0.000	0.000
P115	Preliminary and General Requirements Contractors Administration Arrangements	Site Transportation for EngineersEmployers	Provide necessary 4x4 vehicles 2nos in excellent condition for consultantclient staff transportation and pickup vehicle 2nos for site transport etc. with all consumables fuel etc. as described for small plant and tools for regular maintenance etc as per details in prim documents.	Item	1	0.000	0.000
TOTAL DAYWORKS						88,252.500	



BILL NO: 00 PROVISIONAL SUM

Item Code	Item Name	Item Details	Additional Information	UOM	Qty	Rate	Amount
PV1	Allow for the provisional sums to be expended as directed by the Engineer or deducted in whole or in part if not required - Soft landscaping and Irrigation System	1	Item	Item	1	20000.000	20000.000
PV2	Allow for the provisional sums to be expended as directed by the Engineer or deducted in whole or in part if not - 2000 KVA Sub Station	1	Item	Item	1	40000.000	40000.000
PV3	Allow for the provisional sums to be expended as directed by the Engineer or deducted in whole or in part if not - 11 KV extension & tapping	1	Item	Item	1	60000.000	60000.000
PV4	Allow for the provisional sums to be expended as directed by the Engineer or deducted in whole or in part if not - Water and Power Main Connection from the Authority for Electricity line and Water line.	1	Item	Item	1	40000.000	40000.000
PV5	Allow for the provisional sums to be expended as directed by the Engineer or deducted in whole or in part if not - Relocation of Halaniyat Resident to the Temporary Houses in Salalah, Two Bed Room, Two Toilet, One Kitchen for 28 months.	1	Item	Item	1		Covered In Preliminaies P111
PV6	Allow for the provisional sums to be expended as directed by the Engineer or deducted in whole or in part if not - Add for overhead and profit (7.5 percent)	1	Item	Item	1	40000.000	40000.000
TOTAL PROVISIONAL SUM							200,000.00



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C1	General Works	Demolishing and Clearing the Construction Area	Demolishing the complete building and removing the debris from the Construction Site as per EngineerEmployer Instruction including cart away from the Project Site up to OGL	NO	20	2,520.000	50,400.000
C2	Substructure Works	Site Clearance	This shall include removing vegetation undergrowth bushes hedges trees other temporary buildings structures or the like all complete to clean the full plot.	NO	20	52.500	1,050.000
C3	Substructure Works	Earth work and Excavation	Bulk Excavation to receive foundations in any kind of soil including hard soil and rock earth sport underground surface or running water from whatever source if any for the new foundation building area including removal of old buildings foundations cleaning the site and removing all debris not suitable for backfilling from the project area to the damp yard contractor to prepare all areas to receive new foundation safely as per drawings and soil report.	M3	15000	0.770	11,550.000
C4	Substructure Works	Filling	Approved imported granular fill material compacted in layers in making up levels under floors	M3	4000	0.525	2,100.000
C5	Substructure Works	Filling	Approved imported fill material compacted in layers to raise the levels	M3	15000	0.525	7,875.000
C6	Substructure Works	Filling	Approved selected excavated material backfilled into excavations	M3	6000	0.525	3,150.000
C7	Substructure Works	Filling	200 mm thick well compacted hardcore filling under floors	M3	1040	0.455	473.200
C8	Substructure Works	Anti termite treatment	Anti termite treatment to surfaces of ground or filling applied strictly in accordance with the manufacturers printed instructions including digging trenches backfilling etc. as required by the manufacturer and the provision of guarantee valid for 10 years	M2	6200	1.524	9,448.800



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C9	Substructure Works	Poured Concrete Plain insitu concrete poured Ordinary Portland Cement OPC Concrete Grade C15 all in accordance with Drawings and Specifications and including Formwork to give as struck finish. Providing and erecting formwork including all necessary staging centering shuttering supports cross bracing deshuttering carefully making good the damaged surfaces wherever necessary all complete as specified and as directed by the Engineer all in accordance with the Drawings and Specifications	Blinding upto 100 mm thickness	M3	300	63.000	18,900.000
C10	Substructure Works	Reinforced insitu concrete poured vibrated Sulphate Resistent Cement OPC Concrete Grade C30 all in accordance with Drawings and Specifications and including Reinforcement High yield strength deformed bars conforming to BS 4449 Grade 460 including cutting bending binding binding wire cover blocks tests and all necessary fixing accessories all in accordance with the Drawings and Specifications and including Formwork to give as struck finish. Providing and erecting formwork including all necessary staging centering shuttering supports cross bracing deshuttering carefully making good the damaged surfaces wherever necessary all complete as specified and as directed by the Engineer all in accordance with the Drawings and Specifications	Footings	M3	800	94.500	75,600.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C11	Substructure Works	Reinforced insitu concrete poured vibrated Sulphate Resistent Cement OPC Concrete Grade C30 all in accordance with Drawings and Specifications and including Reinforcement High yield strength deformed bars conforming to BS 4449 Grade 460 including cutting bending binding binding wire cover blocks tests and all necessary fixing accessories all in accordance with the Drawings and Specifications and including Formwork to give as struck finish. Providing and erecting formwork including all necessary staging centering shuttering supports cross bracing deshuttering carefully making good the damaged surfaces wherever necessary all complete as specified and as directed by the Engineer all in accordance with the Drawings and Specifications	Plinth beams	M3	600	94.500	56,700.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C12	Substructure Works	Reinforced insitu concrete poured vibrated Sulphate Resistent Cement OPC Concrete Grade C30 all in accordance with Drawings and Specifications and including Reinforcement High yield strength deformed bars conforming to BS 4449 Grade 460 including cutting bending binding binding wire cover blocks tests and all necessary fixing accessories all in accordance with the Drawings and Specifications and including Steel fabric reinforcement A 393 BRC mesh in two layers. All complete in accordance with the Drawings and Specifications and including Formwork to give as struck finish. Providing and erecting formwork including all necessary staging centering shuttering supports cross bracing deshuttering carefully making good the damaged surfaces wherever necessary all complete as specified and as directed by the Engineer all in accordance with the Drawings and Specifications	Beds Slabs Grade slabs upto 120 mm thickness	M3	800	94.500	75,600.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C13	Substructure Works	Reinforced insitu concrete poured vibrated ordinary Portland Cement OPC Concrete Grade C40 all in accordance with Drawings and Specifications and including Reinforcement High yield strength deformed bars conforming to BS 4449 Grade 460 including cutting bending binding wire cover blocks tests and all necessary fixing accessories all in accordance with the Drawings and Specifications and including Formwork to give as struck finish. Providing and erecting formwork including all necessary staging centering shuttering supports cross bracing deshuttering carefully making good the damaged surfaces wherever necessary all complete as specified and as directed by the Engineer all in accordance with the Drawings and Specifications	Substructure columns	M3	200	94.500	18,900.000
C14	Substructure Works	Sundries Concrete and Block work Protection	Polythene sheet gauge 1200 all in accordance with Drawings and Specifications to surfaces of structural members in contact with soil	M2	8400	2.000	16,800.000
C15	Substructure Works	Sundries Bitumenous Paint	Bitumenous Paint 3 coat to the surfaces of concrete	M2	10000	0.546	5,460.000
C16	Substructure Works	Sundries Bitumenous Sheet	Bitumenous Sheet to the surfaces of concrete	M2	5200	5.250	27,300.000
C17	Substructure Works	Sundries Block work Protection including Bitumenous Paint and Bitumenous Sheet	Protection to concrete masonry block work in contact with soil 3 coats of approved bituminous paint bituminous sheet and including flexible board all in accordance with Drawings and Specifications to surfaces of block work in contact with soil.	M2	22000	21.000	462,000.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C18	Substructure Works	Concrete solid block work 10.5N per mm ² compressive strength cement and sand mortar 1to3 with and including stiffener columns and stiffener beams as required all in accordance with Drawings and Specifications	200mm thick walls	M2	11000	9.450	103,950.000
C19	Substructure Works	The Contractor should read and quote as per the supply laying and all works are included and required approval and commissioning as per contract standards should be under the Contractor scope of work including required charges also including DNP scope and guarantees for material.	Important Note	Item	0	0.000	0.000
C20	Substructure Works	The Contractor is advised to complete the project as per the drawing boq and specification also need to complete if anything missing in the drawing but mentioned in the boq and specification and viceversa. Should the Tenderer fail to insert any item here it will be deemed that this lump sum price for the tender includes all items and no subsequent claim for any additional items will be entertained	Important Note	Item	0	0.000	0.000
C21	Substructure Works	The Contractor is to detail below any additional items with quantities and rates not previously included to complete the build up of the lump sum tender price for this section of the works. Should the Tenderer fail to insert any item here it will be deemed that this lump sum price for the tender includes all items and no subsequent claim for any additional items will be entertained	Important Note	Item	0	0.000	0.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C22	Superstructure Works Concrete Works	Poured Concrete Reinforced insitu concrete poured vibrated Ordinary Portland Cement OPC concrete grade C30 all in accordance with the Drawings and Specifications and including Reinforcement High yield strength deformed bars conforming to BS 4449 Grade 460 including cutting bending binding binding wire cover blocks tests and all necessary fixing accessories all in accordance with the Drawings and Specifications and including Formwork to give as struck finish. Providing and erecting formwork including all necessary staging centering shuttering supports cross bracing deshuttering carefully making good the damaged surfaces wherever necessary all complete as specified and as directed by the Engineer all in accordance with the Drawings and Specifications	Suspended slabs waist slabs landingsstair etc. not exceeding 200 mm thickness	M3	1400	10.080	14,112.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C23	Superstructure Works Concrete Works	Poured Concrete Reinforced insitu concrete poured vibrated Ordinary Portland Cement OPC Concrete Grade C30 all in accordance with the Drawings and Specifications and including Reinforcement High yield strength deformed bars conforming to BS 4449 Grade 460 including cutting bending binding binding wire cover blocks tests and all necessary fixing accessories all in accordance with the Drawings and Specifications and including Formwork to give as struck finish. Providing and erecting formwork including all necessary staging centering shuttering supports cross bracing deshuttering carefully making good the damaged surfaces wherever necessary all complete as specified and as directed by the Engineer all in accordance with the Drawings and Specifications	Columns	M3	380	13.153	4,998.140



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C24	Superstructure Works Concrete Works	Poured Concrete Reinforced insitu concrete poured vibrated Ordinary Portland Cement OPC Concrete Grade C30 all in accordance with the Drawings and Specifications and including Reinforcement High yield strength deformed bars conforming to BS 4449 Grade 460 including cutting bending binding binding wire cover blocks tests and all necessary fixing accessories all in accordance with the Drawings and Specifications and including Formwork to give as struck finish. Providing and erecting formwork including all necessary staging centering shuttering supports cross bracing deshuttering carefully making good the damaged surfaces wherever necessary all complete as specified and as directed by the Engineer all in accordance with the Drawings and Specifications	Beams	M3	650	8.530	5,544.500



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C25	Superstructure Works Concrete Works	Poured Concrete Reinforced insitu concrete poured vibrated Ordinary Portland Cement OPC Concrete Grade C30 all in accordance with the Drawings and Specifications and including Reinforcement High yield strength deformed bars conforming to BS 4449 Grade 460 including cutting bending binding binding wire cover blocks tests and all necessary fixing accessories all in accordance with the Drawings and Specifications and including Formwork to give as struck finish. Providing and erecting formwork including all necessary staging centering shuttering supports cross bracing deshuttering carefully making good the damaged surfaces wherever necessary all complete as specified and as directed by the Engineer all in accordance with the Drawings and Specifications	Ramp	M3	200	1.260	252.000
C26	Superstructure Works Concrete Works	Sundries	GRC Mesh in the Duct 300 X 400 refer to the Architectural Drawing.	NO	20	21.000	420.000
C27	Superstructure Works Concrete Works	Sundries	GRC Mesh in the Duct 300 X 500 refer to the Architectural Drawing.	NO	20	21.000	420.000
C28	Superstructure Works Concrete Works	Sundries	GRC Mesh in the Duct 300 X 1000 refer to the Architectural Drawing.	NO	20	21.000	420.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C29	Superstructure Works Concrete Works	Sundries	Planter box including excavation backfilling disposals blinding solid blockwork waterproofing plaster all complete of various size	No	100	47.250	4,725.000
C30	Superstructure Works Masonry	Internal Walls Ordinary Portland cement concrete blocks 7.5N per mm2 compressive strength cement and sand mortar 1to3 with and including stiffener columns and stiffener beams as required all in accordance with the Drawings and Specifications	200mm thick walls	M2	17400	15.000	261,000.000
C31	Superstructure Works Masonry	Sunken Slab Waterproofing	Providing and applying Sunken Slab Waterproof course with bituminous paint and bituminous membrane conforming to BSto6398 in horizontal joints laid strictly in compliance with approved manufacturers printed instructions and as directed by Engineer.	M2	700	3.600	2,520.000
C32	Superstructure Works Masonry	Roof Slab Waterproofing THERMAL AND MOISTURE PROTECTION COVERINGS AND LININGS	Combo roof treatment for thermal and moisture protection for open terraces by an approved expert agency complete with thermal and moisture resistant layers UV protection layer leveling course separation layers top finishes skirting with 250mm high etc. ensuring smooth runoff and with minimum 25 years of warranty.	Item	1	15,750.000	15,750.000
C33	Superstructure Works Thermal and Moisture Protection	Backgrounds and Finishes Roof screed light weight concrete screed 1000 kg per m3 minimum 50 mm thick to a maximum of 125 mm thick	50 mm minimum bed laid on concrete to falls and cross falls	M2	5600	1.050	5,880.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C34	Superstructure Works Thermal and Moisture Protection	4 mm thick torch applied acrylic polypropylene modified bitumen membrane with non woven polyester reinforcement and polyethylene film waterproof membrane including primer to roofs as per the manufacturer printed instructions complete as specified. Contractor to allow for 10 years guarantee and 24 hours flood test.	To roof decks 4mm thick on flat surface laid to falls and cross falls	M2	5600	1.050	5,880.000
C35	Superstructure Works Thermal and Moisture Protection	Skirting 300 mm girth including turning into groove	In up stands drops and around plinths minimum 300 mm high including dressing over fillet grooves sealant tantalized batten etc. complete to roof deck	M	1900	1.050	1,995.000
C36	Superstructure Works Thermal and Moisture Protection	Insulation Extruded high density polystyrene foam board insulation with rigid closed cell structure all in accordance with the specifications and drawings in external	to roof decks 50 mm thick laid on concrete spot bonded to waterproofing	M2	5600	1.050	5,880.000
C37	Superstructure Works Thermal and Moisture Protection	Roof Finishes	300 x 300 x 30 mm white cement tiles bedded on and including cement mortar screed to falls and cross falls jointed in cement mortar movements joints etc. complete to roof	M2	5600	4.200	23,520.000
C38	Superstructure Works Thermal and Moisture Protection	Roof Finishes	100 x 30 mm white cement skirting to upstands	M	1900	3.150	5,985.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C39	Superstructure Works Thermal and Moisture Protection	Roof Sundries	Allow for Providing dressing around 110mm 83mm UPVC rainwater outlets roof duct gargyle extract fan soil and vent pipe	NO	20	78.750	1,575.000
C40	Superstructure Works Thermal and Moisture Protection	Roof Sundries	Allow for gun applied sealant to seal the joints and groove as applicable and as specified.	NO	20	26.250	525.000
C41	Superstructure Works Metal Works	WPC Pergola	Supply fabricate and install of WPC Pergola as per the approved Construction Drawing and refer to the Architectural Drawing for a highquality WPC Pergola waterproof and antimoisture. The Contractor should submit a detailed drawing of pergola approval 10 years guarantee..	NO	19	210.000	3,990.000
C42	Superstructure Works Metal Works	Staircase hand rail	Stainless steel handrail as shown in the Architectural drawing shop drawings with full sections details to be approved before supply. Note to all stainless steel material shall be of 304 grade.	M	200	26.250	5,250.000
C43	Superstructure Works Metal Works	CAT Ladder	Supply and install a 3800mm high CAT steel Ladder as specified and detailed on the drawing with anticorrelation epoxy pain.	No	20	152.250	3,045.000
C44	Superstructure Works Doors and Windows	Wood Doors Note	1 All timber and veneers shall be well conditioned seasoned dried vacuum treated and preservative treated all as specified	Item	1	0.000	0.000
C45	Superstructure Works Doors and Windows	Wood Doors Note	2 Prepare the surface prime and apply two under coats and two finishing coats of high gloss enamel paint of approved quality make and shade for shutter and frame	Item	1	0.000	0.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C46	Superstructure Works Doors and Windows	Wood Doors Note	3 All hardwood timber shall be best quality Meranti	Item	0	0.000	0.000
C47	Superstructure Works Doors and Windows	Wood Doors Note	4 Sizes stated are structural opening sizes	Item	0	0.000	0.000
C48	Superstructure Works Doors and Windows	Wood Doors Door comprising profiled heads jambs frames subframes architraves beadings mouldings plinth block ply linings infill panels mastic and other pointing fixings neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved fixed to hardwood including paint All locks shall be under master key system as detailed on drawing Note All stainless steel fittings shall be of 304 grade	Type D1 double leaf overall size 1800x2400mm high	No	20	892.500	17,850.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C49	Superstructure Works Doors and Windows	Wood Doors Door comprising profiled heads jambs frames subframes architraves beadings mouldings plinth block ply linings infill panels mastic and other pointing fixings neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved fixed to hardwood including paint All locks shall be under master key system as detailed on drawing Note All stainless steel fittings shall be of 304 grade	Type D2 single leaf overall size 1000x2400mm high	No	20	262.500	5,250.000
C50	Superstructure Works Doors and Windows	Wood Doors Door comprising profiled heads jambs frames subframes architraves beadings mouldings plinth block ply linings infill panels mastic and other pointing fixings neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved fixed to hardwood including paint All locks shall be under master key system as detailed on drawing Note All stainless steel fittings shall be of 304 grade	Type D3 single leaf overall size 1000x2100mm high	No	160	229.700	36,752.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C51	Superstructure Works Doors and Windows	Wood Doors Door comprising profiled heads jambs frames subframes architraves beadings mouldings plinth block ply linings infill panels mastic and other pointing fixings neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved fixed to hardwood including paint All locks shall be under master key system as detailed on drawing Note All stainless steel fittings shall be of 304 grade	Type D4 single leaf overall size 800x2100mm high	No	100	220.500	22,050.000
C52	Superstructure Works Doors and Windows	Wood Doors Door comprising profiled heads jambs frames subframes architraves beadings mouldings plinth block ply linings infill panels mastic and other pointing fixings neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved fixed to hardwood including paint All locks shall be under master key system as detailed on drawing Note All stainless steel fittings shall be of 304 grade	Type D5 single leaf overall size 1000x2100mm high	No	40	262.500	10,500.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C53	Superstructure Works Doors and Windows	Wood Doors Door comprising profiled heads jambs frames subframes architraves beadings mouldings plinth block ply linings infill panels mastic and other pointing fixings neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved fixed to hardwood including paint All locks shall be under master key system as detailed on drawing Note All stainless steel fittings shall be of 304 grade	Type D6 single leaf overall size 1000x2400mm high	No	40	131.250	5,250.000
C54	Superstructure Works Doors and Windows	WPC Solid Core Doors Door comprising profiled heads jambs frames subframes architraves beadings mouldings plinth block ply linings infill panels mastic and other pointing fixings neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved fixed to hardwood including paint All locks shall be under master key system as detailed on drawing Note All stainless steel fittings shall be of 304 grade.	Type D1 double leaf overall size 1800x2400mm high	Item	1	9,135.000	9,135.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C55	Superstructure Works Doors and Windows	WPC Solid Core Doors Door comprising profiled heads jambs frames subframes architraves beadings mouldings plinth block ply linings infill panels mastic and other pointing fixings neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved fixed to hardwood including paint All locks shall be under master key system as detailed on drawing Note All stainless steel fittings shall be of 304 grade.	Type D2 single leaf overall size 1000x2400mm high	Item	1	4,410.000	4,410.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C56	Superstructure Works Doors and Windows	WPC Solid Core Doors Door comprising profiled heads jambs frames subframes architraves beadings mouldings plinth block ply linings infill panels mastic and other pointing fixings neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved fixed to hardwood including paint All locks shall be under master key system as detailed on drawing Note All stainless steel fittings shall be of 304 grade.	Type D3 single leaf overall size 1000x2100mm high	Item	1	26,460.000	26,460.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C57	Superstructure Works Doors and Windows	WPC Solid Core Doors Door comprising profiled heads jambs frames subframes architraves beadings mouldings plinth block ply linings infill panels mastic and other pointing fixings neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved fixed to hardwood including paint All locks shall be under master key system as detailed on drawing Note All stainless steel fittings shall be of 304 grade.	Type D4 single leaf overall size 800x2100mm high	Item	1	15,750.000	15,750.000
C58	Superstructure Works Doors and Windows	WPC Solid Core Doors Door comprising profiled heads jambs frames subframes architraves beadings mouldings plinth block ply linings infill panels mastic and other pointing fixings neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved fixed to hardwood including paint All locks shall be under master key system as detailed on drawing Note All stainless steel fittings shall be of 304 grade.	Type D5 single leaf overall size 1000x2100mm high	Item	1	8,400.000	8,400.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C59	Superstructure Works Doors and Windows	WPC Solid Core Doors Door comprising profiled heads jambs frames subframes architraves beadings mouldings plinth block ply linings infill panels mastic and other pointing fixings neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved fixed to hardwood including paint All locks shall be under master key system as detailed on drawing Note All stainless steel fittings shall be of 304 grade.	Type D6 single leaf overall size 1000x2400mm high	Item	1	4,410.000	4,410.000
C60	Superstructure Works Doors and Windows	Ironmongery Supply and fix of ironmongery with and including all necessary fixing accessories and screws to match all in accordance with the specifications and drawings to wood doors	Allow for grand master key and master key system	No	20	31.500	630.000
C61	Superstructure Works Doors and Windows	UPVC windows window sets complete with all necessary ironmongery as specified including fixing to blockwork or concrete and mastic pointing all around all as specified and detailed on drawing and including required reinforcement cement concrete lintels	Type W1 overall size 2000 x 1300mm high	No	160	68.906	11,024.960



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C62	Superstructure Works Doors and Windows	UPVC windows window sets complete with all necessary ironmongery as specified including fixing to blockwork or concrete and mastic pointing all around all as specified and detailed on drawing and including required reinforcement cement concrete lintels	Type W2 overall size 1200 x 900mm high	No	20	47.250	945.000
C63	Superstructure Works Doors and Windows	UPVC windows window sets complete with all necessary ironmongery as specified including fixing to blockwork or concrete and mastic pointing all around all as specified and detailed on drawing and including required reinforcement cement concrete lintels	Type W3 overall size 600 x 1300mm high	No	60	78.750	4,725.000
C64	Superstructure Works Doors and Windows	UPVC windows window sets complete with all necessary ironmongery as specified including fixing to blockwork or concrete and mastic pointing all around all as specified and detailed on drawing and including required reinforcement cement concrete lintels	Type W4 overall size 1000 x 3700mm high	No	20	94.500	1,890.000
C65	Superstructure Works Doors and Windows	UPVC ventilator ventilator sets complete with all necessary ironmongery as specified including fixing to blockwork or concrete and mastic pointing all around all as specified and detailed on drawing and including required reinforcement cement concrete lintels	Type V overall size 600 x 600mm high	No	100	94.500	9,450.000
C66	Superstructure Works Finishes	Backgrounds Plaster cement and sand 1to3 internal To walls and columns on concrete block base internal including stainsteel mesh butterfly angle between the concrete column and block work.	to receive internal painting	M2	16200	2.385	38,637.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C67	Superstructure Works Finishes	Backgrounds Plaster cement and sand 1to4 external To walls and columns on concrete block base external including stainsteel mesh butterfly angle between the concrete column and block work.	to receive external painting	M2	14000	2.070	28,980.000
C68	Superstructure Works Finishes	Allow for laying of Marble Threshold as per the specifications drawings and to approval of the Engineer.	Internal Floor Tile	No	20	945.000	18,900.000
C69	Superstructure Works Finishes	Floor Tilesto FF1 Ceramic floor tiles laid on screed grouted with waterproof coloured compatible mortar to manufacturers specificationinstruction; internally	600 x 600 x 8 mm AntiSlip tiling to floor	M2	3700	4.086	15,118.200
C70	Superstructure Works Finishes	Floor Tilesto FF2 Ceramic floor tiles laid on screed grouted with waterproof coloured compatible mortar to manufacturers specificationinstruction; internally	600 x 600 x 8 mm AntiSlip tiling to floor	M2	550	4.582	2,520.100
C71	Superstructure Works Finishes	Floor Tilesto FF3 Ceramic floor tiles laid on screed grouted with waterproof coloured compatible mortar to manufacturers specificationinstruction; internally	600 x 600 x 8 mm AntiSlip tiling to floor	M2	600	6.300	3,780.000
C72	Superstructure Works Finishes	Floor Tilesto FF4 30mm tk. Granite laid on screed grouted with waterproof coloured compatible mortar to manufacturers specificationinstruction; internally	30mm thick Granite for Staircase and Steps	M2	600	5.600	3,360.000
C73	Superstructure Works Finishes	Floor Tilesto FF5 20mm tk. Granite laid on screed grouted with waterproof coloured compatible mortar to manufacturers specificationinstruction; internally	20mm tk. Granite Tiles alternative bands of rough smooth coping both sides	M2	500	2.520	1,260.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C74	Superstructure Works Finishes	Floor Tilesto FF6 80mm tk. Interlock tiles laid on screed grouted with waterproof coloured compatible mortar to manufacturers specificationinstruction; internally	80mm tk. Heavy Duty Interlock Tile	M2	4000	1.470	5,880.000
C75	Superstructure Works Finishes	Floor Tilesto FF7 Porcelain tiles laid on screed grouted with waterproof coloured compatible mortar to manufacturers specificationinstruction; internally	Porcelain Tiles 600 X 600 X 20	M2	800	16.275	13,020.000
C76	Superstructure Works Finishes	Floor Tilesto FF9 Granite tiles laid on screed grouted with waterproof coloured compatible mortar to manufacturers specificationinstruction; internally	30mm thick Granite for Entrance floor and Staircase and Steps	M2	200	14.000	2,800.000
C77	Superstructure Works Finishes	Skirting Tilesto FF1 Ceramic tiles laid on screed grouted with waterproof coloured compatible mortar to manufacturers specificationinstruction; internally	Ceramic Tiles 600 X 150 X 8 Anti Slip	M	3800	1.658	6,300.400
C78	Superstructure Works Finishes	Skirting Tilesto FF4 30mm tk. Granite laid on screed grouted with waterproof coloured compatible mortar to manufacturers specificationinstruction; internally	30mm thick Granite for Staircase and Steps	M	200	4.725	945.000
C79	Superstructure Works Finishes	Allow for construction of Decorative projection weather coat stoneshield with 10 years guarantee as per the specifications drawings and to approval of the Engineer	External Elevation	No	20	47.250	945.000
C80	Superstructure Works Finishes	Allow for construction of Decorative projection weather coat stoneshield with 10 years guarantee as per the specifications drawings and to approval of the Engineer	F1F2 External Elevation	M2	11600	1.720	19,952.000
C81	Superstructure Works Finishes	Allow for construction of Decorative projection as per the specifications drawings and to approval of the Engineer	F3 External Elevation	Item	2400	0.525	1,260.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C82	Superstructure Works Finishes	Wall Finishes FF1 Painting and decorating Elegance marble paint finish internal	Smooth Plaster Painting Anti Fungal and Water Resistance	M2	12200	2.479	30,243.800
C83	Superstructure Works Finishes	Wall Finishes FF2 Ceramic Tiles 600 X 200 X 8 Anti Slip	Ceramic Tiles 600 X 200 X 20 Anti Slip	M2	1700	4.941	8,399.700
C84	Superstructure Works Finishes	Wall Finishes FF3 Ceramic Tiles 600 X 200 X 8 Anti Slip	Ceramic Tiles 600 X 200 X 20 Anti Slip	M2	3600	7.000	25,200.000
C85	Superstructure Works Finishes	Ceilings Finishes FF1 Painting and decorating Elegance marble paint finish internal	Smooth Plaster Painting Anti Fungal and Water Resistance	M2	3700	7.150	26,455.000
C86	Superstructure Works Finishes	Ceilings Finishes FF2 Smooth Plaster Painting Elegance marble paint finish Anti Fungal and Water Resistance	Smooth Plaster Painting Anti Fungal and Water Resistance	M2	550	7.636	4,199.800
C87	Superstructure Works Finishes	Ceilings Finishes FF3 Smooth Plaster Painting Elegance marble paint finish Anti Fungal and Water Resistance	Smooth Plaster Painting Anti Fungal and Water Resistance	M2	600	8.400	5,040.000
C88	Superstructure Works Finishes	Ceilings Finishes FF4 Smooth Plaster Painting Elegance marble paint finish Anti Fungal and Water Resistance	Smooth Plaster Painting Anti Fungal and Water Resistance	M2	600	7.880	4,728.000
C89	Superstructure Works Finishes	Allow for supply fabricate and installation of Gas Cylinder Stage as per the specifications drawings and to approval of the Engineer.	Gas Cylinder Stage	No	20	36.750	735.000
C90	Superstructure Works Finishes	Allow for corecut remove and smooth finish as per the specifications drawings and to approval of the Engineer.	Drain Open to connect Sewage Tanker to the Holding Tank size 550 X 400mm	No	20	42.000	840.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C91	Superstructure Works Finishes	Allow for supply fabricate and installation of water point protection as per the specifications drawings and to approval of the Engineer.	Water point protection	No	20	47.250	945.000
C92	Superstructure Works Finishes	Allow for supply fabricate and installation of Meter Panel protection as per the specifications drawings and to approval of the Engineer.	Meter Panel protection	No	20	47.250	945.000
C93	Superstructure Works Finishes	Allow for supply fabricate and installation of Kitchen Stage including Stage Concrete Stage Korean Top and Stage Area Ceramic Wall Tile as per the specifications drawings and to approval of the Engineer.	Kitchen Stage Concrete Korean Top Ceramic Wall Tiles	No	20	178.500	3,570.000
C94	Superstructure Works Finishes	Allow for supply fabricate and installation of Kitchen Hood Range including Aluminum Kitchen Cabinet above and Aluminum Kitchen Cabinet below all as per the specifications drawings and to approval of the Engineer.	Kitchen Hood Range Cabinet above and below Cabinet.	No	20	189.000	3,780.000
C95	Superstructure Works Finishes	The Contractor should read and quote as per the supply laying and all works are included and required approval commissioning as per contract standards should be under the Contractor scope of work including required charges also including DNP scope and guarantees for material.	Important Note	Item	0	0.000	0.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
C96	Superstructure Works Finishes	The Contractor is advised to complete the project as per the drawing boq and specification also need to complete if anything missing in the drawing but mentioned in the boq specification and viceversa. Should the Tenderer fail to insert any item here it will be deemed that this lump sum price for the tender includes all items and no subsequent claim for any additional items will be entertained	Important Note	Item	0	0.000	0.000
C97	Superstructure Works Finishes	The Contractor is to detail below any additional items with quantities and rates not previously included to complete the build up of the lump sum tender price for this section of the works. Should the Tenderer fail to insert any item here it will be deemed that this lump sum price for the tender includes all items and no subsequent claim for any additional items will be entertained	Important Note	Item	0	0.000	0.000
P1	Sanitary Installation	UPVC pipes to BS 4514 1983 and BS 4660 1973 including all joints and accessories and brackets	UPVC drain pipes to BS 4514 1983 and BS 4660 1973 including all joints with ring seals fittings and accessories in the running length.	Item	0	0.000	0.000
P2	Sanitary Installation	UPVC pipes to BS 4514 1983 and BS 4660 1973 including all joints and accessories and brackets	160mm diameter	M	1120	6.975	7,812.000
P3	Sanitary Installation	UPVC pipes to BS 4514 1983 and BS 4660 1973 including all joints and accessories and brackets	110mm diameter	M	320	4.725	1,512.000
P4	Sanitary Installation	UPVC pipes to BS 4514 1983 and BS 4660 1973 including all joints and accessories and brackets	82mm diameter	M	600	4.410	2,646.000
P5	Sanitary Installation	UPVC pipes to BS 4514 1983 and BS 4660 1973 including all joints and accessories and brackets	50mm diameter	M	580	4.780	2,772.400



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P6	Sanitary Installation	UPVC pipes to BS 4514 1983 and BS 4660 1973 including all joints and accessories and brackets	42mm diameter	M	200	10.500	2,100.000
P7	Sanitary Installation	vent cowl	Vent cowl with weathering apron 50mm diameter	No	80	2.100	168.000
P8	Sanitary Installation	Floor Drain trap	Floor Trap with 150 X 150 mm SS grating Cover	No	160	2.625	420.000
P9	Sanitary Installation	Gully Trap	300 mm and 300 mm gully trap of approximate 300 mm depth set in concrete Grade 30 Nmm joints to drain pipes complete with 300 mm and 300 mm medium duty cast iron cover and frame.	No	100	58.800	5,880.000
P10	Sanitary Installation	Inspection Chambers	Manhole size 600 and 600 mm internally upto 1.30m deep to invert	No	185	45.400	8,399.000
P11	Sanitary Installation	Manhole Cover	600 and 600 mm medium duty double seal cast iron manhole cover and frame.	No	185	55.620	10,289.700
P12	Sanitary Installation	Holding tank with soak pit	Reinforced concrete grade 30 N mm2 holding tank size 4000 and 2000 and 2500 mm deep internally with concrete grade 15 N mm2 and 100mm thick blinding and 250mm thick concrete base slab and 200mm thick concrete wall and roof slab and including reinforcement and formwork and rendering and step irons and 3 coats of bitumen paint and 2 layer of 1000 gauge polythene sheet and excavation and dewatering backfilling and disposal of surplus excavated materials and 600 and 600 mm heavy duty double seal ductile iron cover and frame and Precast concrete soak pit size 2000 mm diameter and 2500 mm deep internally including reinforcement and excavation and dewatering and backfilling and disposal of surplus excavated materials 600 and 600 mm heavy duty ductile iron cover and frame et as detailed on drawing.	No	20	945.000	18,900.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P13	Sanitary Wares and Fittings	Semi pedestal wash basin	650 mm and 475 mm vitreous china white wash basin with semi pedestal and center tap hole and overflow and bottle trap including required complete Civil Works.	No	100	15.750	1,575.000
P14	Sanitary Wares and Fittings	Counter top wash basin	630 mm and 510 mm vitreous china white counter top wash basin and center tap hole and overflow and bottle trap including required complete Civil Works.	No	80	15.750	1,260.000
P15	Sanitary Wares and Fittings	Stainless Steel Sink	1000 mm ² and 550 mm stainless steel sink single bowl single drainer with drainboard to BS 1244 complete with 2 piece tubular P trap chain and plug and waste and brackets including required complete Civil Works.	No	20	2.100	42.000
P16	Sanitary Wares and Fittings	European Water Closet	400 mm and 685 mm vitreous china white concealed tank wall hung mounted EWC squatting pan built in wall toilet dual flush 3L or 6L concealed cistern and heavy duty auto closed seat and cover including required complete Civil Works.	No	100	1.050	105.000
P17	Sanitary Wares and Fittings	Faucet spray	Chromium plated approved ablution faucet with angle valve and hose and spray unit.	No	100	1.050	105.000
P18	Sanitary Wares and Fittings	Wash Basin Mixer	Single lever chrome plated wash basin mixer including pop up waste.	No	180	1.050	189.000
P19	Sanitary Wares and Fittings	Sink Mixer	Single lever chrome plated Sink mixer.	No	20	2.100	42.000
P20	Sanitary Wares and Fittings	Toilet tissue holder	Recessed type stainless steel Toilet tissue dispenser or holder with stainless steel hood.	No	100	1.050	105.000
P21	Sanitary Wares and Fittings	Towel rail	610 and 75 and 75 mm towel rail	No	140	1.050	147.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P22	Sanitary Wares and Fittings	Mirror	450 and 600 mm mirror 6 mm thick and bevel edged and plywood backing fixed with chromium plated dome headed screws	No	180	1.050	189.000
P23	Sanitary Wares and Fittings	Bath shower	Single lever dual control bath shower mixer	No	100	1.050	105.000
P24	Sanitary Wares and Fittings	Bip tap	For internal and external.	No	140	0.600	84.000
P25	Sanitary Installation AC DRAIN SYSTEM	NOTE	HPUPVC pipes and fittings to BS 3505 Class E including all joints and connections and fittings.	Item	0	0.000	0.000
P26	Sanitary Installation AC DRAIN SYSTEM	Hpupvc pipe	25 mm diameter pipe for air conditioner drainage pipe to ac drain pit.	M	1230	0.512	629.760
P27	Water Supply installation	Polypropylene random copolymer pipe NOTE	Polypropylene random copolymer pipes and fittings and cold and hot water connections to international standard ISO EN ISO 15874 2003 and DIN 80777 8078 including up stand and brackets exposed insulation as per Specification in running length and 25mm thick rigid performed sectional fiber glass insulation with aluminum foil and fiber glass reinforced adhesive and canvas Cora cloth with 2 coats of foster paint one coat of water proof emulsion glossy white paint and vapour barrier coating as described.	Item	0	0.000	0.000
P28	Water Supply installation	Cold and Hot water PPR C pipes with insulation	15 mm diameter	M	1400	0.900	1,260.000
P29	Water Supply installation	Cold and Hot water PPR C pipes with insulation	20 mm diameter	M	2200	0.460	1,012.000
P30	Water Supply installation	Cold and Hot water PPR C pipes with insulation	25 mm diameter	M	550	2.520	1,386.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P31	Water Supply installation	Cold and Hot water PPR C pipes with insulation	32 mm diameter	M	1600	1.050	1,680.000
P32	Water Supply installation	Cold and Hot water PPR C pipes with insulation	40 mm diameter	M	1000	0.840	840.000
P33	Water Supply installation	Cold and Hot water PPR C pipes with insulation	50 mm diameter	M	50	2.100	105.000
P34	Water Supply installation	Cold and Hot water Valves	Supply and install the following Isolating valves to BS 5154 series B bronze and wedge gate pattern and screwed joints with adaptor to pipes etc wherever shown in drawings and or specified and as approved by the Engineer.	Item	0	0.000	0.000
P35	Water Supply installation	Cold and Hot water Valves	15 mm diameter	No	700	0.810	567.000
P36	Water Supply installation	Cold and Hot water Valves	20 mm diameter	No	400	0.945	378.000
P37	Water Supply installation	Cold and Hot water Valves	25 mm diameter	No	40	2.100	84.000
P38	Water Supply installation	Cold and Hot water Valves	32 mm diameter isolating value	No	120	1.925	231.000
P39	Water Supply installation	Cold and Hot water Valves	40 mm diameter	No	40	1.575	63.000
P40	Water Supply installation	Cold and Hot water Valves	50 mm diameter	No	20	5.250	105.000
P41	Water Supply installation	Equipment and Accessories Note	Equipment and accessories as specified including all connections and fittings	Item	0	0.000	0.000
P42	Water Supply installation	Water Tank	600 US gallon capacity GRP type water storage tank with foundation epoxy coated frame ball valve overflows etc to approval	No	20	21.000	420.000
P43	Water Supply installation	Water Heater	50 liter capacity horizontal type copper tank high level wall mounted electrical water heater including all connections and fixing.	No	120	68.250	8,190.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P44	Water Supply installation	Booster pump	Cold water pressurised booster pump set 1No Working pump and 1No standby pump for domestic water supply delivering 2 l per sec at 2.5 bar with Gate valve and Non return valve and float switch and pressure gauge and pressure vessel 30 to 50 lit PN10 and water low level cut off relay etc with pump room all complete as detailed in the drawing to approval.	No	20	99.750	1,995.000
P45	RAIN WATER SYSTEM Rain Water Installation	Rain Water UPVC Pipes	UPVC pipes to BS 4514 or 1983 including all joints and fittings and accessories and connections and brackets	Item	0	0.000	0.000
P46	RAIN WATER SYSTEM Rain Water Installation	Rain Water UPVC Pipes	110mm diameter	m	700	1.800	1,260.000
P47	RAIN WATER SYSTEM Rain Water Installation	Rain water Outlet	110 mm diameter root terminal socket tail rain water outlet.	No	80	3.675	294.000
P48	Plumbing and Drainage System	Sundries	Allow for working drawings and asbuilt drawings.	Item	1	0.000	0.000
P49	Plumbing and Drainage System	Sundries	Allow for all supports plinths and dog houses and necessary builder s work after obtaining approval through shop drawings including setting out and marking holes and chases cut outs etc and making good.	Item	1	10.500	10.500
P50	Plumbing and Drainage System	Sundries	Allow for all protective and decorative painting.	Item	1	315.000	315.000
P51	Plumbing and Drainage System	Sundries	Allow for providing Test Certificates	Item	1	315.000	315.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
P52	Plumbing and Drainage System	Sundries	Allow for co ordination with other Engineering Installations.	Item	1	840.000	840.000
P53	Plumbing and Drainage System	Sundries	Allow for testing and commissioning of underground cable prior to and after backfilling.	Item	1	945.000	945.000
P54	Plumbing and Drainage System	Sundries	Allow for OandM Manual	Item	1	945.000	945.000
P55	Plumbing and Drainage System	Sundries	Allow for sterilization of all pipes and over head tanks etc.	Item	1	945.000	945.000
P56	Plumbing and Drainage System	Sundries	Allow for spare parts for three years as per manufacturers recommendation.	Item	1	1,785.000	1,785.000
P57	Plumbing and Drainage System	Sundries	Allow for training OandM staff.	Item	1	1,680.000	1,680.000
P58	Plumbing and Drainage System	Sundries	Allow for any other activity not listed above.	Item	1	63.000	63.000
F1	Fire Fighting Installation	Fire Fighting Installation	Supply and install a complete fire fighting system to the approval of the Civil Defence Authorities and complete with association and fitting as shown in drawings or specified in accordance with BS 530 Part 1 1976 and Part 3 1985 and to approval of the Engineer.	Item	1	0.000	0.000
F2	Fire Fighting Installation	Fire hose reel	1.5 mm thick Electro static powder coated painted stainless steel recessed type fire hose reel cabinet with 25 mm diameter hose reel and 45 meter long including 1 No. 9 litter foam type fire extinguisher and 1 No 5Kg carbon dioxide type fire extinguisher with civil defence final approval certificate.	No	3	0.000	0.000
F3	Fire Fighting Installation	outlet	Wet riser outlet with valve assembly	NO	3	80.000	240.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
F4	Fire Fighting Installation	valve	Zonal control valve assembly	NO	1	120.000	120.000
F5	Fire Fighting Installation	inlet	Breaching inlet	NO	1	200.000	200.000
F6	Fire Fighting Installation	Fire Extinguisher	2 Kg carbon dioxide fire extinguisher	No	20	2.100	42.000
F7	Fire Fighting Installation	Fire Extinguisher	180 and 180 mm fire blanket	No	20	1.050	21.000
F8	Fire Fighting Installation	Fire alarm cable and conduits and panel and accessories installation	Automatic Multi detector point	No	20	130.000	2,600.000
G1	Gas supply line	Gas line	Supply and fix 18 mm diameter MS schedule 40 gas pipeline including pickup points and connection to Gas Stove	M	100	10.500	1,050.000
M1	Air Conditioning and Ventilation Installation	High level Wall mounted Split AC with DX unit	18000 BTU HR capacity high level wall mounted split type air conditioner including connection to electrical outlet and concrete base foundation.	No	120	240.000	28,800.000
M2	Air Conditioning and Ventilation Installation	High level Wall mounted Split AC with DX unit	30000 BTU HR capacity high level wall mounted split type air conditioner including connection to electrical outlet and concrete base foundation.	No	20	320.000	6,400.000
M3	Air Conditioning and Ventilation Installation	High level Wall mounted Split AC with DX unit	36000 BTU HR capacity high level wall mounted split type air conditioner including connection to electrical outlet and concrete base foundation.	No	20	420.000	8,400.000
M4	Mechanical installation	Sundries	Allow for builders works in connection with sanitary and water services including holes and chases and sleeves and pipe brackets painted casing to exposed pipes and access panels and weather proof flashing to vent pipes passing through roof etc.	Item	1	0.000	0.000
M5	Mechanical installation	Sundries	Allow for incidental works such as co ordination with other engineering installations	Item	1	0.000	0.000
M6	Mechanical installation	Sundries	Allow for protective covering and painting to all exposed water supply and ventilation pipe work	Item	1	0.000	0.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
M7	Mechanical installation	Sundries	Allow for identification labels and color coding etc.	Item	1	0.000	0.000
M8	Mechanical installation	Sundries	Allow for testing and commissioning.	Item	1	0.000	0.000
M9	Mechanical installation	Sundries	Allow for chlorination of water storage tanks and pipe work	Item	1	0.000	0.000
M10	Mechanical installation	Sundries	Allow for document As installed drawings and Operation ad Maintenance Manuals	Item	1	0.000	0.000
E1	Electrical Engineering Installation	Note	Supply and install 11 KV underground line including intermediate pole tapping arrangement from existing O H linea and stays and pit excavation and cable trench and backfilling and all accessories and connections as per Public Authority for Electricity and Water rules and regulation and to approval.	Item	1	0.000	0.000
E2	Electrical Engineering Installation	Cable	3C and 240 mm2 11 KV UG cable including termination	M	100	0.000	0.000
E3	Electrical Engineering Installation	Excavation	Excavation of HV cable trench and pit and backfilling as per Public Authority for Electricity and Water rules and regulation and to approval.	M	100	0.000	0.000
E4	Electrical Engineering Installation	Testing and commissioning	Testing and commissioning including liaison with Public Authority for Electricity and Water	Item	1	0.000	0.000
E5	Electrical Engineering Installation	Substation Equipments Note	Supply and install electrical substation equipments including foundation all as per Public Authority for Electricity and Water requirement and to approval.	Item	1	0.000	0.000
E6	Electrical Engineering Installation	Transformer	1600 KVA 11KV 415V transformer including cable termination	No	1	0.000	0.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
E7	Electrical Engineering Installation	Feeder Pillar	2500 A incomer feeder pillar with 2Nos 600A three Phase Strip fuse isolator 4 Nos 400A three phase Strip Fuse isolator and 1Nos spare 100A single phase Strip fuse isolator and 1 Nos spare 200A three phase strip fuse isolator in weatherproof enclosure IP 54 with seperate CT meter weatherproof encolsure including cable termination.	No	1	0.000	0.000
E8	Electrical Engineering Installation	RMU	Substation Ring Main Unit RMU from 2OLU and 1HFU to 2OLU and 2HFU including excavation and reaarangement of RMU and cable termination as per MEDC Public Authority for Electricity and Water requirement and to approval.	No	1	0.000	0.000
E9	Electrical Engineering Installation	Cable	3C and 120 mm2 11 KV UG cable from RMU to transformers	M	10	0.000	0.000
E10	Electrical Engineering Installation	Cable	7 Runs of 1C and 630 mm2 XLPE PVC SWA PVC Cu. Cable from transformer to Feeder pillar And Main Feeder Pillar to SubFeeder Pillar including all termination	M	20	0.000	0.000
E11	Electrical Engineering Installation	Manhole	2500 and 1500 and 700 mm deep internal size electrical manhole RCC wall and rendering internally 75 mm PCC at bottom with 800 and 800 mm double seal heavy duty cast iron cover and frame	No	1	0.000	0.000
E12	Electrical Engineering Installation	Electrical Engineering Installation	Electricity and water connection to be charged local Public Authority for Electricity and Water	Item	1	0.000	0.000
E13	Electrical Engineering Installation	caution tape	Cable caution tape marked in Arabic and English for cable.	M	1250	0.000	0.000
E14	Electrical Engineering Installation	PVC tile	PVC tile	M	1250	0.000	0.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
E15	Electrical Engineering Installation	Earth pit	Earthing with earth pit	Item	1	0.000	0.000
E16	Electrical Engineering Installation	Testing and commissioning	Testing and commissioning including liaison with Public Authority for Electricity and Water	Item	1	0.000	0.000
E17	Electrical Engineering Installation	Cable duct note	UPVC cable duct with socket joint and laid in trench and encased in plain cement concrete with a minimum encasement thickness of 100 mm on all sides in running length with excavate trench in any materials and minimum 700 mm deep and including bedding and backfilling with excavated materials and disposal of surplus materials.	Item	1	0.000	0.000
E18	Electrical Engineering Installation	Cable duct	160 mm diameter UPVC duct	M	550	0.000	0.000
E19	Electrical Engineering Installation	Cable duct	110 mm diameter UPVC duct	M	850	0.000	0.000
E20	Electrical Engineering Installation	Sundries	Allow for builders work in connection with electrical installation including holes and chases and sleeves ducts and cable tray trucking panel backboards or formwork and supports and access panels and cover plates etc.	Item	1	0.000	0.000
E21	Electrical Engineering Installation	Sundries	Allow for incidental works such as co ordination with other engineering installations.	Item	1	0.000	0.000
E22	Electrical Engineering Installation	Sundries	Allow to identification labels and charts etc.	Item	1	0.000	0.000
E23	Electrical Engineering Installation	Sundries	Allow for testing and commissioning of complete electrical installation.	Item	1	0.000	0.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
E24	Electrical Engineering Installation	Sundries	Allow for documents As Installed drawings and Operation and Maintenance manuals.	Item	1	0.000	0.000
E25	MAIN DISTRIBUTION BOARD Electrical Engineering Installation	Main Distribution Board	Main Distribution panel board in weather proof GRP enclosure IP 65 including 2 nos 600A and 4 nos 400A and 1NOS spare 100 A and 1 NOS spare 200A Incoming MCCB Breaker and 4nos 200A and 2nos spare 100 A Outgoing MCCB Breakers and supports and Busbar and earthing and cable glands and Ammeters and Voltmeters and internal wiring interconnection 1PH 3PH KWH series meters and labels as per approved MHEW drawings	NO	6	14.000	84.000
E26	MAIN DISTRIBUTION BOARD Electrical Engineering Installation	Cable	4C and 240 mm ² UG cable from Feeder Pillar to MDB Panels	M	500	0.000	0.000
E27	MAIN DISTRIBUTION BOARD Electrical Engineering Installation	Manholes	1000 and 1000 and 700 mm deep internal size electrical manhole RCC wall and rendering internally 75 mm PCC at bottom with 800 and 800 mm double seal heavy duty cast Ductile Iron EN 124 B400 cover and frame	No	16	0.000	0.000
E28	MAIN DISTRIBUTION BOARD Electrical Engineering Installation	Manholes	600 and 600 and 700 mm deep internal size electrical manhole and RCC wall and rendering internally 75 mm PCC at bottom with 600 and 600 mm double seal heavy duty cast iron cover and frame.	No	40	0.000	0.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
E29	SUB MAIN DISTRIBUTION BOARD	Sub Main Distribution Board	Sub Main Distribution panel board in weather proof GRP enclosure IP 65 including 1nos 200A MCCB and 2 NOS 100A MCCB Outgoing Breakers and supports and Busbar and earthing and cable glands and Ammeters and Voltmeters and internal wiring interconnection 1PH 3PH KWH series meters and labels as per approved MHEW drawings	No	20	0.000	0.000
E30	SUB MAIN DISTRIBUTION BOARD	Note	XLPE PVC SWA PVC copper cable with PVC copper earth continuity conductor including necessary conduit and trunking and cable tray and termination	Item	1	0.000	0.000
E31	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB1	M	40	0.000	0.000
E32	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB2	M	20	0.000	0.000
E33	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB3	M	25	0.000	0.000
E34	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB4	M	35	0.000	0.000
E35	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB5	M	20	0.000	0.000
E36	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB6	M	25	0.000	0.000
E37	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB7	M	40	0.000	0.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
E38	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB8	M	20	0.000	0.000
E39	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB9	M	20	0.000	0.000
E40	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB10	M	40	0.000	0.000
E41	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB11	M	10	0.000	0.000
E42	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB12	M	30	0.000	0.000
E43	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB13	M	40	0.000	0.000
E44	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB14	M	20	0.000	0.000
E45	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB15	M	20	0.000	0.000
E46	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB16	M	40	0.000	0.000
E47	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB17	M	40	0.000	0.000
E48	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB18	M	20	0.000	0.000
E49	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB19	M	25	0.000	0.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
E50	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB20	M	45	0.000	0.000
E51	Electrical Engineering Installation	Distribution Board	Distribution board including isolator and ELCB in separate enclosure and MCB RCD MCB as specified along with necessary supports earthing cable glands and internal wiring and interconnection and labels	Item	1	0.000	0.000
E52	Electrical Engineering Installation	Distribution Board	100A TPN 12 way DBs	No	20	3.150	63.000
E53	Electrical Engineering Installation	Distribution Board	100A TPN 6 way DBs	No	20	4.200	84.000
E54	Electrical Engineering Installation	Cable	XLPE PVC SWA PVC copper cable with PVC and copper earth continuity conductor including necessary conduit and trunking and cable tray and termination	Item	1	0.000	0.000
E55	Electrical Engineering Installation	Cable	4C and 25 mm ² + 1C and 16 mm ² ECC from SMDBs to DB1 GF for 20 villas	M	500	0.840	420.000
E56	Electrical Engineering Installation	Cable	4C and 25 mm ² + 1C and 16 mm ² ECC from SMDBs to DB1 GF for 21 villas	M	500	0.840	420.000
E57	Electrical Engineering Installation	Earthing Installation	Earthing system including 16 mm dia. high conductivity solid copper rod electrodes with drive head assemblies and Earthing clamps for earth pits Earthing of exposed pipe work sanitary fittings and equipment all as required including 300 and 300 and 400 mm deep internally earth pit and earth wires as per specification and drawings complete with 300 mm and 300 mm medium duty double seal cast iron cover and frame.	No	30	140.000	4,200.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
E58	Electrical Engineering Installation	Sundries	Allow for builders work in connection with electrical installation including holes chases sleeves ducts cable tray trucking panel backboards or formwork supports access panels cover plates etc.	Item	1	1,260.000	1,260.000
E59	Electrical Engineering Installation	Sundries	Allow for incidental works such as co ordination with other engineering installations.	Item	1	945.000	945.000
E60	Electrical Engineering Installation	Sundries	Allow to identification labels and charts etc.	Item	1	1,029.000	1,029.000
E61	Electrical Engineering Installation	Sundries	Allow for testing and commissioning of complete electrical installation.	Item	1	2,100.000	2,100.000
E62	Electrical Engineering Installation	Sundries	Allow for documents As installed drawings Operation and Maintenance manuals.	Item	1	945.000	945.000
E63	Electrical Engineering Installation	Small Power Accessories and cable and Conduits Installation Note	Supply and installd and connect test and commissioning of the following wiring devices including SS cover plate connect test of the conduits and cables and back box and junction box form distribution board from the following as required as shown on drawing and specification	Item	1	0.000	0.000
E64	Electrical Engineering Installation	Small Power Accessories and cable and Conduits Installation	13A DP single switched socket outlet	No	720	0.146	105.120
E65	Electrical Engineering Installation	Small Power Accessories and cable and Conduits Installation	13A DP twin switched socket outlet	No	260	3.000	780.000
E66	Electrical Engineering Installation	Small Power Accessories and cable and Conduits Installation	13A DP single gang weatherproof switch socket outlet	No	280	0.975	273.000
E67	Electrical Engineering Installation	Small Power Accessories and cable and Conduits Installation	30A cooker socket	No	20	1.050	21.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
E68	Electrical Engineering Installation	Small Power Accessories and cable and Conduits Installation	20A DP flux outlet for AC 1.5 ton	No	120	0.875	105.000
E69	Electrical Engineering Installation	Small Power Accessories and cable and Conduits Installation	20A weatherproof DP flux outlet for WH	No	120	1.050	126.000
E70	Electrical Engineering Installation	Small Power Accessories and cable and Conduits Installation	13 A unswitched fused spur unit outlet for EF	No	120	1.050	126.000
E71	Electrical Engineering Installation	Small Power Accessories and cable and Conduits Installation	30A DP flux outlet for AC 2.5 and 3 ton	No	40	1.050	42.000
E72	Electrical Engineering Installation	Small Power Accessories and cable and Conduits Installation	20A Dp switch for WH and AC	No	220	1.050	231.000
E73	Electrical Engineering Installation	Small Power Accessories and cable and Conduits Installation	30A Dp switch for AC	No	40	1.050	42.000
E74	Electrical Engineering Installation	Small Power Accessories and cable and Conduits Installation	20A weatherproof TPN isolator for Booster pump	No	20	0.000	0.000
E75	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	Supply and install and connect test of the conduits and cables form distribution board from the following .Supply and install connect test and commissioning of the following wiring devices including SS cover plate connect test of the conduits and cables and back box and junction box form distribution board from the following as required as shown on drawing and specification.	Item	1	0.000	0.000
E76	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	Lighting switch 10A Double pole one way one gang	No	220	0.370	81.400
E77	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	Lighting switch 10A Double pole one way one gang whether proof	No	20	0.000	0.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
E78	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	Ditto one way two gang	No	420	0.250	105.000
E79	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	Ditto one way three gang	No	220	0.115	25.300
E80	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	Ditto two way one gang	No	60	0.210	12.600
E81	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	Ditto two way two gang	No	40	0.000	0.000
E82	Electrical Engineering Installation	Lighting Fixture Note	Supply and install and connect test and commissioning of the following lighting fixtures and including lamps and electronic ballasts and control gear and wires and cables and all necessary accessories complete as specified and as shown on the drawings.	Item	0	0.000	0.000
E83	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	40w led downlight	No	720	1.750	1,260.000
E84	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	40w led downlight with whether proof IP 65	No	200	2.310	462.000
E85	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	40w led downlight with integral emergency conversion kit	No	180	3.267	588.060
E86	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	25w led wall mounted light fixture	No	120	0.000	0.000
E87	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	26w led wall mounted light fixture with whether proof	No	200	0.000	0.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
E88	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	7w led mirror light	No	180	0.000	0.000
E89	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	20w compound wall light with whether proof IP65	No	220	0.000	0.000
E90	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	40w fluorescent light fixture for car parking area	No	20	0.000	0.000
E91	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	Ceiling fan	No	180	2.100	378.000
E92	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	Chandelier	No	40	4.200	168.000
E93	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	Wall mounted exhaust fan	No	120	2.100	252.000
GN1	TV System Installation	Cable	Cable and conduit to TV point in concealed installation from satellite	No	120	2.100	252.000
GN2	TV System Installation	Outlet	Flush mounted TV Satellite outlet	No	120	2.100	252.000
GN3	TV System Installation	TV System Installation	Allow for co axial cable in concealed conduit from dish antenna to satellite switcher with all necessary accessories and trunking and conduits and trays and supports etc.	Item	1	0.000	0.000
GN4	Telephone System	Cable	Cable and conduits to telephone outlet points in concealed installation from telephone junction box to IP phone expansion module for reception	No	120	2.450	294.000
GN5	Telephone System	Outlet	Cat 6E telephone outlet	No	120	2.450	294.000
GN6	Telephone System	Junction box	Telephone junction box	No	20	2.100	42.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
GN7	Telephone System	Excavation	Supply and laying 80 pair telephone cable including trench excavation and backfilling and ducts and bedding caution tape etc all as per site conditions	Item	1	0.000	0.000
GN8	Telephone System	Cables	80 pair external grade telephone cable from mantel terminal box to main telephone junction box at main building Electrical room.	Item	1	0.000	0.000
GN9	Telephone System	Draw Pits	450 and 450 and 500 mm deep internal size telephone draw pit RCC wall and rendering internally and 75 mm PCC at bottom with 450 and 450 mm medium duty ductile iron cover and frame.	Item	1	0.000	0.000
GN10	DATA SYSTEM	DATA SYSTEM	Supply and install and connect and test and commissioning of the following for the WiFi system including cables and trunking and accessories and as shown on specifications.	item	1	0.000	0.000
GN11	Structured Cabling system	Accessories	Wi Fi access units including all accessories and fittings	item	1	472.500	472.500
GN12	Structured Cabling system	Accessories	Any other works not specifically enumerated under the works above with implementation cost	Item	1	1,155.000	1,155.000
GN13	Structured Cabling system	Cable	Cableconduits and accessories to RJ 45 Category 6A dual socket outlet	No	120	11.025	1,323.000
GN14	Structured Cabling system	Cable	Drop lead 3m long Category 6A	No	160	8.400	1,344.000
GN15	Structured Cabling system	Cable	Drop lead 6m long Category 6A	No	160	8.400	1,344.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
GN16	Structured Cabling system	patch panel	16 Port Cat 6A Patch panel	No	20	8.400	168.000
GN17	Structured Cabling system	Structured Cabling system	500mm single mode fiber LC SC Patch cords	No	20	9.450	189.000
GN18	Structured Cabling system	Accessories	Accessories and stacking kits and cable management and cable organizer and cable channels and supports all types of cords and pig tail connectors including termination etc complete	Item	1	1,050.000	1,050.000
GN19	CCTV System	PTZ Camera	PTZ Vandal proof with weather proof Bullet type Day and Night vision CCTV IP camera Outdoor as specified.	No	40	26.250	1,050.000
GN20	CCTV System	pulling box	Allow for cable pulling boxes	Item	1	1,575.000	1,575.000
GN21	CCTV System	cable	Cables and Trunking and Accessories	Item	1	0.000	0.000
GN22	Telephone and Structured Cabling and CCTV System	Sundries	Allow for builders work in connection with electrical installation including holes and chases and sleeves and ducts and cable tray trucking and panel backboards or formwork support and access panels and cover plates etc.	Item	1	945.000	945.000
GN23	Telephone and Structured Cabling and CCTV System	Sundries	Allow for incidental works such as co ordination with other engineering installations.	Item	1	1,260.000	1,260.000
GN24	Telephone and Structured Cabling and CCTV System	Sundries	Allow to identification labels charts etc.	Item	1	0.000	0.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
GN25	Telephone and Structured Cabling and CCTV System	Sundries	Allow for testing and commissioning of complete electrical installation.	Item	1	0.000	0.000
GN26	Telephone and Structured Cabling and CCTV System	Sundries	Allow for documents As Installed drawings Operation and Maintenance manuals.	Item	1	0.000	0.000
MEP 1	MEP Works	The Contractor should read and quote as per the supply laying and all works are included and required approval commissioning as per contract standards should be under the Contractor scope of work including required charges also including DNP scope and guarantees for material.	Important Note	Item	1	0.000	0.000
MEP 2	MEP Works	The Contractor is advised to complete the project as per the drawing boq and specification also need to complete if anything missing in the drawing but mentioned in the boqspecification and viceversa. Should the Tenderer fail to insert any item here it will be deemed that this lump sum price for the tender includes all items and no subsequent claim for any additional items will be entertained	Important Note	Item	1	0.000	0.000



BILL NO 4 NEW HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price	Total Price In Figure
MEP 3	MEP Works	The Contractor is to detail below any additional items with quantities and rates not previously included to complete the build up of the lump sum tender price for this section of the works. Should the Tenderer fail to insert any item here it will be deemed that this lump sum price for the tender includes all items and no subsequent claim for any additional items will be entertained	Important Note	Item	1	0.000	0.000
TOTAL NEW HOUSING UNITS						1,965,370.940	



BILL NO 04 EXTERNAL WORKS AND EXTERNAL SERVICES

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
EW1	External Works General Site Works	Site Preparation	Allow for setting out grading trimming including clearing loose boulders vegetation stones and the like all trees bushes shrubs and undergrowth grub up all roots and burn or remove from site as directed by the Engineer.	Item	1	0.000	0.000
EW2	External Works General Site Works	Boundary wall	Allow for the Contractor to prepare RCC foundation column block work plastering and painting as per the Architectural Drawing and as per Engineer Employer Instruction to complete the Boundary Wall.	M	1775	2.100	3,727.500
EW3	External Works General Site Works	Wicket Gate	Allow for the Contractor to supply fabricate and installation of single leaf Wicket Gate as per the Architectural Drawing and follow as per Engineer Employer Instructions including anti corrosion epoxy paint.	no	20	105.000	2,100.000
EW4	External Works General Site Works	Car Entrance Gate	Allow for the Contractor to supply fabricate and installation of single leaf Car Entrance Gate as per the Architectural Drawing and follow as per Engineer Employer Instructions including anti corrosion epoxy paint	no	20	141.750	2,835.000
EW5	External Works General Site Works	Entrance Gate ont only	Allow for the Contractor to supply fabricate and installation of Wicket Gate solid WPC with 10 years guarantee as per the Architectural Drawing and follow as per Engineer Employer Instructions including anti corrosion epoxy paint.	Item	0	0.000	0.000
EW6	External Works General Site Works	Wicket Gate	Single leaf Wicket Gate solid WPC	Item	1	0.000	0.000
EW7	External Works General Site Works	Car Entrance Gate	Single leaf Car Entrance Gate soild WPC	Item	1	0.000	0.000
EW8	External Works General Site Works	Entrance Concrete Paver	Allow for the Contractor to prepare Concrete Paver as per the Architectural Drawing and place at the House Main Entrance.	No	100	5.250	525.000



BILL NO 04 EXTERNAL WORKS AND EXTERNAL SERVICES

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
EW9	External Works General Site Works	Interlock Tile	Allow for connection Asphalt road to the site from the main drawing as per approval	M2	13550	1.050	14,227.500
EW10	External Works General Site Works	Curb Stone	Allow for connection Asphalt road to the site from the main drawing as per approval	M	1400	2.100	2,940.000
EW11	External Works General Site Works	Design and Build Shaded Car Parking of 20 numbers with Solar Panel Canopy	Allow for the Contractor to design and build the Shaded Car Park for houses with Solar Panel Canopy as per Engineer Employer Instruction.	no	20	105.000	2,100.000
TOTAL EXTERNAL WORKS AND EXTERNAL SERVICES						28,455.000	



BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
EX1	External Works Lump sum	Site Clearance	Which shall include removing vegetation undergrowth bushes hedges trees or the like all complete item also Removal and disposal of surplus excavated material including providing suitable tip to the dumping yard or as specified and directed by the Engineer or local authorities..	Item	29	304.500	8,830.500
EX2	External Works Lump sum	Demolishing	demolishing all the structures and stores inside the boundary wall by preparing a sketch for each house and submitting to clients engineer and getting the written approval for demolishing and shifting the disposal material to damp yard including foundations of structres.	Item	29	514.500	14,920.500
EX3	External Works Lump sum	Demolishing Rebuild	demolishing and rebuilding as per the Same Specifications the gates columns damaged boundary wall damaged manholes damaged Holding Tanks damaged Sock Pits and change the cover to be GRP type Heavy duty and any other elements must be demolished to modified or rebuilt as per main scope all of this including and not limited to Excavation in any type of soil Disposal of surplus material filling by imported fill material compacted in layers waterproof concrete reinforcements joints block works polythene sheets anti termite manholes cover plastering PVC Pipes and any necessary work to finish the work in functional condition.	Item	29	619.500	17,965.500



BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
EX4	External Works Lump sum	boundary wall	the contractor has to remove and demolish any damaged or unsafe parts of the wall and rebuild it with the same height after filling any cracks space between concrete and blockwork with non shirenkage filler with SS mesh between concrete and blocks and to remove all the paint or cladding and re paint again with external paint weather coat stoneshield with prime coat with 10 years guarantee .all of this including and not limited to to 200mm thick walls Polythene sheet gauge 1000 Waterproofing with two bitumen coats and membrane 4mm to surfaces of concreteProtection to concretemasonryblock work in contact with soil 3 coats approved bituminous paintExpansion joint	Item	29	619.500	17,965.500
EX5	External Works Lump sum	GI gates	remove the existing gates and supply and fix new gates GI and painted with marine paint as per the site conditions with warranty for the paint and gates for 10 years	Item	29	724.500	21,010.500
EX6	External Works Lump sum	Pea Gravel around the house and inside the boundary wall	the contractor has fill the full area with pea gravel with size between 20mm to 50mm max with depth 100 mm around the house detecting from it the manholes and holding tanks and sock pit only but it must be under the new caravans	Item	29	829.500	24,055.500
EX7	External Works Lump sum	Dewatering	Allow for keeping excavations free from underground surface or running water from whatever source	Item	29	252.000	7,308.000
EX8	External Works Lump sum	Gas Cylinder Room	Contractor has to built a Gas Cylinder Room with RCC base and block work with height 1.5 m with concrete top slab with suitable foundation and safety gate that powder coated and painted with marine paint with warranty 10 years.	Item	29	241.500	7,003.500



BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C1	Super Structure Works Lump sum	Demolishing the Existing staircase slab and reconstruct it with Poured Concrete Reinforced insitu concrete poured vibrated Ordinary Portland Cement OPC concrete grade C35 all in accordance with the Drawings and Specifications including but not limited formwork reinforcement additives movement joints construction joints joint filler curing compounds surface finishes water stop wherever necessary concrete tests and any other accessories and ancillary work required to complete the work.	RCC slabs RCC beams RCC Columns landingsstair etc. not exceeding 200 mm thickness at staircase head rooms.	Item	29	262.500	7,612.500




BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C2	Superstructure Works Thermal and Moisture Protection	Removing Roof tiles and screed and waterproofing with cleaning the surfaces closing any cracks with chemical sealants and making the surface ready for receiving the new waterproofing.	Demolishing the existing roof finish with waterproof and disposal the material and make the surface ready for receiving the new waterproofing	Item	29	1,995.000	57,855.000



BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	#VALUE!	Total Price In Figure
C3	Superstructure Works Thermal and Moisture Protection	Roof screed lightweight concrete screed 1000 kgm3 minimum 50 mm thick to a maximum of 125 mm thick and Waterproofing with two bitumen coats and 4 mm thick torch applied acrylic polypropylene modified bitumen membrane with nonwoven polyester reinforcement and polyethylene film waterproof membrane including primer to roofs as per the manufacturer printed instructions complete as specified. Contractor to allow for 10 years guarantee and 24 hours flood test	To roof decksRoof screed lightweight concrete screed 1000 kgm3 minimum 50 mm thick to a maximum of 125 mm thick and Waterproofing with two bitumen coats and 4mm thick membrane on flat surface laid to falls and cross falls	Item	29	3,150.000	91,350.000



BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C4	Superstructure Works Thermal and Moisture Protection	Skirting 300 mm girth including turning into groove	In up standsdrops and around parapet minimum 300 mm high including dressing over fillet grooves sealant tantalized batten etc. complete to roof deck	Item	29	1,890.000	54,810.000
C5	Superstructure Works Thermal and Moisture Protection	Insulation Extruded high density polystyrene foam board insulation with rigid closed cell structure all in accordance with the specifications and drawings external	to roof decks 50 mm thick laid on concrete spot bonded to waterproofing	Item	29	514.500	14,920.500
C6	Superstructure Works Thermal and Moisture Protection	Roof Finishes	Supply and fix 300 x 300 x 25 mm terrazzo tiles bedded on and including cement mortar screed to falls and cross falls jointed in cement mortar movements joints etc. complete to roof	Item	29	1,995.000	57,855.000
C7	Superstructure Works Thermal and Moisture Protection	Roof Finishes	Supply and fix 100x20 mm terrazzo skirting to upstands	Item	29	892.500	25,882.500
C8	Superstructure Works Thermal and Moisture Protection	Roof Sundries	Allow for Providing dressing around 110mm83mm UPVC rainwater outlets roof duct gargoyle extract fan soil and vent pipe	Item	29	481.950	13,976.550
C9	Superstructure Works Thermal and Moisture Protection	Roof Sundries	For parapet Allow for gun applied sealant to seal the joints and groove as applicable and as specified.	Item	29	304.500	8,830.500
C10	Superstructure Works Metal Works	Staircase handrail	Removing the old handrails and replacing them with 316 St.st handrails including supply and fix as per existing desin hand rail in new houses drawings.	Item	29	1,575.000	45,675.000
C11	Superstructure Works Metal Works	galvanized steel cat Ladder	Supply and install galvanized steel cat Ladder as specified and detailed on the drawingas per existing desin hand rail in new houses drawings.	Item	29	262.500	7,612.500



BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C12	Superstructure Works Doors and Windows	Wood Doors All Types and Size of doors including the main entrance door comprising profiled heads jambs frames subframes architraves beadings moldings plinth block ply linings infill panels mastic and other pointing fixings neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation ironmongery as specified in schedule and approved; fixed to hardwood All locks shall be 3 sets of keys Note to all stainless steel fittings shall be of 304 grade	1remove the Old doors and maintain the frame if possible and supply and fix wooden door with the same existing size and specification and new accessories.item include and not limited to maintain the existing frame and paint.	Item	29	9,975.000	289,275.000



BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C13	Superstructure Works Doors	UPVC Doors	The contractor to Replace all Wooden Doors for Toilets and Roof to be UPVC and to respect the following to 1 Door sizes stated are structural opening size 2 Tenderers shall strictly follow the door size as per site conditions prior to pricing this section. No additional payments will be entertained due to failure or and misunderstanding by the tenderer. 3 Rate shall include for supply and fixing of new all necessary ironmongery as specified 4 Roof doors shall be airtight rubbersealed and weather resistant 5 Rate shall include final finishing and final decoration as per the specification drawings and schedule and to the approval of the Engineer	Item	29	3,675.000	106,575.000
C14	Superstructure Works for Windows	Aluminium windows	The contractor is to Maintain the existing Aluminum Windows for and to respect the following to 1 Windows sizes stated are structural opening size 2 Contractor shall strictly follow the Windows size as per site conditions prior to pricing this section. No additional payments will be entertained due to failure or and misunderstanding by the contractor. 3 Rate shall include for supply and fixing of new all necessary ironmongery as specified 4 Windows shall be airtight rubbersealed and weather resistant. 5 Rate shall include final finishing and final decoration as per the specification drawings and schedule and to the approval of the Engineer 6 The exterior glass is to be replaced with new 6 mm Reflected Glass and 6 mm smokey glass for toilets complete systems including all stiffeners fasteners sealants jointing and material thickness as required to form high quality systems in accordance with specifications. 7 Contractor to replace the Insect mesh to be aluminum type not metal. 8 the contractor is to replace any Aluminum section that could be totally damaged and can not be rectified.	Item	29	8,400.000	243,600.000



BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C15	Superstructure Works Finishes	Entrance Flooring	Demolishing entrance flooring preparing the surface to receive marble tiles and supplying and fixing marble tiles for landing and stairs Tread and raiser for steps also skirting included with the same material.with supplying and fixing	Item	29	430.500	12,484.500
C16	Superstructure Works Finishes	Salah and Majles flooring	Demolishing salah and Majles flooring preparing the surface to receive porcelain tiles and supplying and fixing porcelain tiles matching with existing floors also skirting included with the same material.with supplying and fixing	Item	29	472.500	13,702.500
C17	Superstructure Works Finishes	Kitchen and toilets flooring	Demolishing Kitchen and toilets flooring preparing the surface to receive antislip ceramic tiles and supplying and fixing antislip ceramic tiles matching with existing floors.with supplying and fixing	Item	29	367.500	10,657.500
C18	Superstructure Works Finishes	Stairs Landing and steps	Demolishing Stairs flooring preparing the surface to receive marble tiles and supplying and fixing marble tiles for landing and stairs Tread and raiser for steps also skirting included with the same material.with supplying and fixing	Item	29	682.500	19,792.500



BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C19	Superstructure Works Finishes	Internal wall Finishes Scrap the existing paint repair the cracks fill the cracks and put SS mesh between concrete and block work and over the MEP pipes including PVC corner beads and expanded metal lath angle beads and plaster stops as specified. including decorative around the windows with internal Backgrounds Plaster cement and sand 1to3 internal To walls and columns on concrete block base internal for the damaged areas to receive INTERNAL Paint to walls of approved color over a coat of waterbased primer including preparation of	Prepare prime and apply one coat of primer and 2 coats of approved quality and color Painting and decoratingEligance marble paint with 10 years garantee all as specifiedto internally	Item	29	1,260.000	36,540.000



BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C20	Superstructure Works Finishes	External wall Finishes Scrap the existing paint repair the cracks fill the cracks and put SS mesh between concrete and block work and over the MEP pipes including PVC corner beads and expanded metal lath angle beads and plaster stops as specified. including decorative around the windows with internal Backgrounds Plaster cement and sand 1to3 External To walls and columns on concrete block base External for the damaged areas to receive three coats of heavy texture EXTERNAL walls and columns design and windows concrete frame and all	Prepare prime and apply 3 coats of approved quality and color Decorative projection weather coat stoneshield with 10 years guarantee as per the specificationsto Externally	Item	29	787.500	22,837.500
C21	Superstructure Works Finishes	Toilets and Kitchen wall Ceramic tiles	Demolishing Kitchen and toilets walls tiles preparing the surface to receive glossy ceramic tiles with supplying and fixing	Item	29	735.000	21,315.000



BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C22	Superstructure Works Finishes	Ceilings Finishes Scrap the existing paint repair the cracks fill the cracks Painting and decorating internal Paint to walls of approved color over a coat of waterbased primer including preparation of surface by thorough cleaning and wetting and applying POP Gypsum powder putty as per manufacturer's specification fully to give an even shade before painting and curing as per manufacturers specifications and as directed the paint should be antifungal growth and weather resistance.	One coat Primertwo coats putty Three coats of Fenomastic Silk paint or equivalent on cement sand plaster. Colour as per Approval of Engineer	Item	29	945.000	27,405.000



BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C23	Superstructure Works Finishes	External Wall Finishes supply and fix Crazy Natural Stone with height 1.5 meter from external FFL	Supply and fix Crazy Natural Stone or marble with a height 1.5 meters from External FFL	Item	29	1,522.500	44,152.500
C24	Superstructure Works Finishes	Remove the Existing and Allow for supply fabricate and installation of Kitchen Stage including Stage Concrete Stage Korean Top and Stage Area Ceramic Wall Tile as per the specifications drawings and to approval of the Engineer.	Kitchen Stage Concrete Korean Top Ceramic Wall Tiles	Item	29	84.000	2,436.000
C25	Superstructure Works Finishes	Remove the Existing and Allow for supply fabricate and installation of Kitchen Hood Range including Aluminum Kitchen Cabinet above and Aluminum Kitchen Cabinet below all as per the specifications drawings and to approval of the Engineer.	Kitchen Hood Range Cabinet above and below Cabinet.	Item	29	84.000	2,436.000



BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
P1	Sanitary Installation	The Contractor must remove all sanitary that were fixed	The Contractor must remove all sanitary that were fixed at toilets and kitchens including but not limited to Wash basins EWC Mixers toilet accessories st st sink floor trap covers towel rails tissue holder .. Etc and store it to handover to the client in clients storages.	Item	29	95.550	2,770.950
P2	Sanitary Installation	UPVC pipes to BS 45141983 and BS 4660 1973 including all joints accessories and brackets	Supply and install Vent cowl with weathering apron 75 mm diameter	Item	29	12.600	365.400
P3	Sanitary Installation	Floor Drain trap	Supply and install 110 mm diameter Floor Trap with 150 X 150 mm SS grating Cover including all UPVC and PVC pipes for water supply and drain with fittings and flexible pipes	Item	29	11.550	334.950
P4	Sanitary Installation	Gully Trap	Supply and install 300 mm x 300 mm gully trap of approx. 300 mm depth set in concrete Grade 30 Nmm joints to drain pipes complete with 300 mm x 300 mm medium duty cast iron cover and frame. including all UPVC and PVC pipes for water supply and drain with fittings and flexible pipes	Item	29	12.600	365.400
P5	Sanitary Wares and Fittings	Semi pedestal wash basin	Supply and install 650 mm x 475 mm vitreous china white wash basin with semi pedestal center tap hole overflow and bottle trap. including all UPVC and PVC pipes for water supply and drain with fittings and flexible pipes including all UPVC and PVC pipes for water supply and drain with fittings and flexible pipes	Item	29	12.600	365.400
P6	Sanitary Wares and Fittings	Stainless Steel Sink	Supply and install 1000 mm x 550 mm stainless steel sink single bowl single drainer with drainboard to BS 1244 complete with 2 piece tubular P trap chain plug waste brackets. including all UPVC and PVC pipes for water supply and drain with fittings and flexible pipes	Item	29	23.100	669.900



BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
P7	Sanitary Wares and Fittings	European Water Closet	Supply and install 400 mm x 685 mm vitreous china white concealed tank wall hung mounted EWC squatting pan built in wall toilet dual flush 3L6L concealed cistern and heavy duty auto closed seat and cover including all UPVC and PVC pipes for water supply and drain with fittings and flexible pipes	Item	29	13.650	395.850
P8	Sanitary Wares and Fittings	shower tray	Supply and install white glazed shower tray size 70x70 with the necessary fittings and plumbing darins including all UPVC and PVC pipes for water supply and drain with fittings and flexible pipes	Item	29	12.600	365.400
P9	Sanitary Wares and Fittings	Ablution Faucet	Chromium plated approved ablution faucet with angle valve hose and spray unit. including all UPVC and PVC pipes for water supply and drain with fittings and flexible pipes	Item	29	13.650	395.850
P10	Sanitary Wares and Fittings	shower Mixer	Single lever chrome plated shower mixer including Rainshower rail set with its hand shower. including all UPVC and PVC pipes for water supply and drain with fittings and flexible pipes	Item	29	12.600	365.400
P11	Sanitary Wares and Fittings	Wash Basin Mixer	Single lever chrome plated wash basin mixer including pop up waste. including all UPVC and PVC pipes for water supply and drain with fittings and flexible pipes	Item	29	9.450	274.050
P12	Sanitary Wares and Fittings	Sink Mixer	Single lever chrome plated Sink mixer. including all UPVC and PVC pipes for water supply and drain with fittings and flexible pipes	Item	29	9.450	274.050
P13	Sanitary Wares and Fittings	Toilet tissue holder	Recessed type stainless steel Toilet tissue dispenser holder with stainless steel hood.	Item	29	9.450	274.050
P14	Sanitary Wares and Fittings	Towel rail	610 x 75 x 75 mm towel rail	Item	29	8.400	243.600
P15	Sanitary Wares and Fittings	Mirror	450 x 600 mm mirror 6 mm thick bevel edged plywood backing fixed with chromium plated dome headed screws	Item	29	12.600	365.400



BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
P16	Water Supply	Polypropylene random copolymer pipe	contractor to check the pressure of the cold and hot water at each house and to replace the damaged or leaked pipes after removing the tiles floor wall and refix the tiles again with similar or with new the Polypropylene random copolymer pipes and fittings cold and hot water connections to international standard ISO to EN ISO 15874 to 2003 and DIN 80777 8078 including up stand and brackets exposed insulation as per Specification all the pipes as per the original sizes.	Item	29	8.400	243.600
P17	Water Supply	Cold and Hot water Valves	Supply and install the following Isolating valves to BS 5154 series B bronze wedge gate pattern screwed joints with adaptor to pipes etc. wherever shown in drawings and or specified and as approved by the Engineer. all the Valves as per the original sizes.	Item	29	9.450	274.050
P18	Water Supply	The Contractor must remove all Equipment and Accessories that were fixed	The Contractor must remove all Equipment and accessories that were fixed at houses including but not limited to GRP Water Tanks water Heater etc. and store it to hand over to the client in the clients storage.	Item	29	9.269	268.800
P19	Water Supply	Water Tank	Supply and install 400US gallon capacity GRP type water storage tank with foundation epoxy coated frame ball valve overflows etc. to approval	Item	29	52.138	1,512.000
P20	Water Supply	Water Heater	Supply and install 50 liter capacity horizontal type copper tank high level wall mounted electrical water heater including all connections and fixing.	Item	29	30.124	873.600
P21	Rain Water Installation	Rain Water UPVC Pipes with outlet	remove the existing and Supply and install UPVC pipes to BS 4514 1983 including all joints fittings accessories connections and brackets	Item	29	32.441	940.800
P22	Rain Water Installation	TAP AND ABLUTION FAUCET	Construct a 60x120x40 Ablution base by Solid Block with RCC base and finished from all side with anti slip ceramic including the mixer subject to the engineers and client approval	Item	29	28.966	840.000



BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
M1	Air Conditioning and Ventilation Installation	The Contractor must remove all Equipment and Accessories that were fixed	The Contractor must remove all Equipment and accessories that were fixed at houses including but not limited to AC units indoor outdoor... Etc and store it to hand over to the client in the clients storage.	Item	29	25.490	739.200
M2	Air Conditioning and Ventilation Installation	High level Wall mounted Split AC with DX unit replacing the box type at walls	Contractor to remove the existing AC at walls and to close the walls and make plaster with st st mesh and painting after that to fix 18000 BTUHR capacity highlevel wall mounted split type air conditioner including connection to electrical outlet and concrete base foundation and AC drain pipes to gully trap.	Item	29	23.172	672.000
M3	Air Conditioning and Ventilation Installation	High level Wall mounted Split AC with DX unit for Kitchen	18000 BTUHR capacity highlevel wall mounted split type air conditioner including connection to electrical outlet and concrete base foundation and AC drain pipes to gully trap.	Item	29	243.310	7,056.000
M4	Air Conditioning and Ventilation Installation	High level Wall mounted Split AC with DX unit for salah and majles	30000 BTUHR capacity highlevel wall mounted split type air conditioner including connection to electrical outlet and concrete base foundation and AC drain pipes to gully trap.	Item	29	278.069	8,064.000
M5	Air Conditioning and Ventilation Installation	Ventilating Fans	remove the existing and Supply and install test and commission ventilating fan 6 and 8 with electrically operated louvers as specified on the drawings complete with all mounting requirements flexible connections electrical connections support backdraft dampers auto changeover controller all in accordance with the specification	Item	29	46.345	1,344.000
E1	Electrical Engineering Installation	Distribution Board	the Contractor must check the Power supply distribution copper cable with earth continuity cable Rate should cover related accessories jointing glanding earthing tag termination legs PVA shrowds and cable tag for interconnecting cables cable trays cable identification cable route marker from substation to the switches and sockets and in between subboards and distribution panels and change any defected item to have the system working in functional conditions	Item	29	46.345	1,344.000



BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
E2	Electrical Engineering Installation	Contractor to provide full Solar system	The contractor to Design and Provide the solar system including all materials and supply and fix it to be compatible with the MCCP and DBs at the houses and get the approvals from the ClientEngineer before executing any work	Item	29	0.000	0.000
E3	Electrical Engineering Installation	Sub Main Distribution Board	the Contractor to replace the existing with new weatherproof GRP IP 65 Main or Sub Main Distribution panel board including MCCBs supports earthing cable glands Ammeters Voltmeters internal wiring interconnection and labels as per drawings and specification	Item	29	53.297	1,545.600
E4	Electrical Engineering Installation	Sub Main Distribution Board	The contractor to replace the existing DBs with new weatherproof GRP IP 65 for all the DBs at the houses.	Item	29	63.724	1,848.000
E5	Electrical Engineering Installation	Sub Main Distribution Board	The contractor to add a new DB for the New Caravans to be weatherproof GRP IP 65 .	Item	29	62.566	1,814.400
E6	Electrical Engineering Installation	Small Power Accessories removing	the Contractor to replace the existing with new switches and sockets and the existing to be handover to client at his storage at end of the project.	Item	29	6.952	201.600
E7	Electrical Engineering Installation	Small Power Accessories Installation	the Contractor to replace the existing with new 13A DP single switched socket outlet	Item	29	52.138	1,512.000
E8	Electrical Engineering Installation	Small Power Accessories Installation	the Contractor to replace the existing with new 13A DP twin switched socket outlet	Item	29	11.586	336.000
E9	Electrical Engineering Installation	Small Power Accessories Installation	the Contractor to replace the existing with new 13A DP single gang weatherproof switch socket outlet	Item	29	12.745	369.600
E10	Electrical Engineering Installation	Small Power Accessories Installation	the Contractor to replace the existing with new 20A Dp switch outlet	Item	29	637.241	18,480.000
E11	Electrical Engineering Installation	Small Power Accessories Installation	the Contractor to replace the existing with new two way two gang	Item	29	27.807	806.400



BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
E12	Electrical Engineering Installation	Small Power Accessories Installation	the Contractor to replace the existing regulator for the ceiling fans	Item	29	30.124	873.600
E13	Electrical Engineering Installation	Small Power Lighting Fixture removing	the Contractor to replace the existing with new Lighting Fixture inside and out side and celing fans such as including lamps electronic ballasts control gearwirescables and all necessary accessories and the existing to be handover to client at his storage at end of the project.	Item	29	28.966	840.000
E14	Electrical Engineering Installation	Lighting Fixture	Supply install connect test and commissioning of the following lighting fixtures including lamps electronic ballasts control gearwirescables and all necessary accessories complete as specified and as shown on the drawingsto	Item	29	173.793	5,040.000
E15	Electrical Engineering Installation	Lighting Fixture	Supply install connect test and commissioning of the following lighting fixtures at all Bed Rooms	Item	29	24.331	705.600
E16	Electrical Engineering Installation	Lighting Fixture	Supply install connect test and commissioning of the following lighting fixtures at all Salah	Item	29	24.331	705.600
E17	Electrical Engineering Installation	Lighting Fixture	Supply install connect test and commissioning of the following lighting fixtures at all Majles	Item	29	28.966	840.000
E18	Electrical Engineering Installation	Lighting Fixture	Supply install connect test and commissioning of the following lighting fixtures at all Kitchen	Item	29	28.966	840.000
E19	Electrical Engineering Installation	Lighting Fixture	Supply install connect test and commissioning of the following lighting fixtures at all toilets	Item	29	28.966	840.000
E20	Electrical Engineering Installation	Lighting Fixture	Supply install connect test and commissioning of the following lighting fixtures at all corridors	Item	29	11.586	336.000
E21	Electrical Engineering Installation	Lighting Fixture	Supply install connect test and commissioning of the following lighting fixtures at staircase	Item	29	11.586	336.000



BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
E22	Electrical Engineering Installation	Lighting Fixture	Supply install connect test and commissioning of the following lighting fixtures at entrance	Item	29	11.586	336.000
E23	Electrical Engineering Installation	Lighting Fixture	Supply install connect test and commissioning of the following lighting fixtures at boundary wall	Item	29	11.586	336.000
E24	Electrical Engineering Installation	Lighting Fixture	Supply install connect test and commission of the following lighting fixtures at roof 4 corners and above the stair head room 4 corners	Item	29	5.793	168.000
E25	Electrical Engineering Installation	Lighting Fixture	Supply install connect test and commission of the following lighting fixtures Emergency light	Item	29	17.379	504.000
E26	Electrical Engineering Installation	Ceiling Fan	Supply install connect test and commission of celing fans	Item	29	23.172	672.000
E27	Electrical Engineering Installation	Earthing Installation	Supply install NEW Earthing system including 16 mm dia. high conductivity solid copper rod electrodes with drive head assemblies and Earthing clamps for earth pits Earthing of exposed pipe work sanitary fittings and equipment all as required including 300 x 300 x 400 mm deep internally earth pit earth wires as per specification and drawings complete with 300 mm x 300 mm medium duty double seal cast iron cover and frame.	Item	29	28.966	840.000
E28	Electrical Engineering Installation	TV Points and Dish Installation	Supply install NEW TV Satellite system all Data Cable with the dish above the roof and the concrete base and to connect it to the existing TV points all in functional conditions.	Item	29	52.138	1,512.000
G1	Sundrie	Sundrie Items	Any other works not specifically enumerated under the works in this bill but indicated in the drawings or required to complete the work in manner of respect to handover the project in working and safe conditions to the residents specification or needed to complete the work.	Item	29	52.138	1,512.000



BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
G2	Sundrie	Sundrie Items	if any works was miss matching with any part of this tender documents the contractor must raise his queries during tender period and by submitting the offer the contractor confirming that every points was clear for him and confirming that is included at his price and no variation will be accepted	Item	29	52.138	1,512.000
TOTAL EXISTING HOUSING UNITS 29 NOS						1,436,308.650	



BILL NO 06 PROTECTION AND STORM WATER DRAINAGE

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
PSW1	1 Conditions of Contract	Flood Protection and Storm Water Drainage Systems. Note	The contractor is deemed to have carefully studied and understood and taken into account the provisions and requirements of the General Conditions of Contract. The rates and prices stated in the Bill of Quantities shall include for all costs of compliance with the conditions. Reconstruct the new flood protection system as per the specification and drawing and not allowed to remove or demolish the existing system before constructing the new system.	Item	0	0.000	0.000
PSW2	Conditions of Contract	Flood Protection and Storm Water Drainage Systems.Note	The contractor must refer to Oman Highway Design Standards 2017 for Specifications and Details.	Item	0	0.000	0.000
PSW2	2 Earthwork	Earthwork Excavation .Note	All the Levels taken from Architecture Zero Level and the Contractor must submit the Quantities based on approved topographical survey.	Item	0	0.000	0.000
PSW3	Earthwork	Earthwork Excavation .Note	Rate to include for excavation for all leads & lift loading unloading & double handling where required necessary equipments tools & plants dressing the excavation to proper level and grade as required dumping the soil in the designated area approved by the Authorities taking necessary precautions to prevent any spillages or spoiling of the premises public roads during removal & transporting the soil all consumables including protecting the sides of excavation as per the the nature of site soil condition and safety of excavation etc complete as directed.	Item	0	0.000	0.000
PSW4	Earthwork	Excavation for Structures Trenches	Unclassified structural excavation Depth 0 to required depth as per drawings Excavation by mechanical means using excavators JCB Porcelains etc. in soil any type to the required level for foundation excavation. Including soft rock and hard rock and any remaining material or elements for the existing building. Dispose of excavated material offsite by mechanical means as directed to the approval of the Client and consultant. Disposal is not measured separately mass excavation must be done.	m3	111780	1.050	117369.000



BILL NO 06 PROTECTION AND STORM WATER DRAINAGE

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
PSW5	Earthwork	Backfilling for Structures trenches . Note	Rate shall include for loading unloading transportation hire and fuel charges for tools and plants employed and other incidental charges etc. complete and as directed.	Item	0	0.000	0.000
PSW6	Earthwork	Backfilling for Structures trenches.Note	Supplying and filling in foundations and the area wherever required below ground level with the approved by Consultant material brought from outside other approved filling materials like river sand in layers not exceeding 150 mm thickness including mixing spreading levelling watering and consolidating each layer with power hand roller of required capacity to obtain required proctor density as per specification etc. all complete and as directed.	Item	0	0.000	0.000
PSW7	Earthwork	Backfilling for Structures trenches.Note	Approved imported fill material in making up level compacted in layers planting and execute pit including but not limited to:	Item	0	0.000	0.000
PSW8	Earthwork	Backfilling for Structures trenches	Backfilling	m3	38975	0.525	20461.875
PSW9	Earthwork	Earthwork for Pipe Trenches	Trench excavation and backfilling Depth 0 to 2m	m3	9180	0.700	6426.000
PSW10	Earthwork	Earthwork for Pipe Trenches	Trench excavation and backfilling 2m to 3m	m3	12615	1.575	19868.625
PSW11	Earthwork	Earthwork for Pipe Trenches	Trench excavation and backfilling 3m to 4m	m3	3090	2.100	6489.000
PSW12	Earthwork	Earthwork for Pipe Trenches	Trench excavation and backfilling Depth more than 4m	m3	4080	4.200	17136.000



BILL NO 06 PROTECTION AND STORM WATER DRAINAGE

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
PSW13	3 Granular Subbase Aggregate Base Course and Stabilized Base Courses.	Redesign and Construction of Asphalt Road to be suitable for Erection of Culvert with all necessary drawings details...	Aggregate Base Course Class B	m3	1500	2.100	3150.000
PSW14	4 Bituminous Pavement	Redesign and Construction of Asphalt Road to be suitable for Erection of Culvert with all necessary drawings details...	Bituminous Prime Coat Application rate 1.5 KgSq.m	m3	4050	2.100	8505.000
PSW15	Asphalt Road	Redesign and Construction of Asphalt Road to be suitable for Erection of Culvert with all necessary drawings details...	Bituminous Wearing Course Class B	m3	280	12.600	3528.000
PSW16	5 Concrete and Concrete Structures	Construction of Box culvert N2 Size 2x1.5m concrete class 30 with reinforcement as per HDS 2017 including wing wall foundations bituminous paint excavation backfilling and as directed by Engineer	Concrete Materials and Mixes Note	Item	0	0.000	0.000



BILL NO 06 PROTECTION AND STORM WATER DRAINAGE

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
PSW17	Concrete and Concrete Structures	Construction of Box culvert N2 Size 2x1.5m concrete class 30 with reinforcement as per HDS 2017 including wing wall foundations bituminous paint excavation backfilling and as directed by Engineer	Concrete Class 15 in foundations.	m3	130	13.650	1774.500
PSW18	Concrete and Concrete Structures	Construction of Box culvert N2 Size 2x1.5m concrete class 30 with reinforcement as per HDS 2017 including wing wall foundations bituminous paint excavation backfilling and as directed by Engineer	Concrete Class 35 in box culverts wing walls apron slab retaining walls and debris foundations.	m3	375	12.600	4725.000
PSW19	Concrete and Concrete Structures	Construction of Box culvert N2 Size 2x1.5m concrete class 30 with reinforcement as per HDS 2017 including wing wall foundations bituminous paint excavation backfilling and as directed by Engineer	Reinforcing Steel Note	Item	0	0.000	0.000



BILL NO 06 PROTECTION AND STORM WATER DRAINAGE

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
PSW20	Concrete and Concrete Structures	Construction of Box culvert N2 Size 2x1.5m concrete class 30 with reinforcement as per HDS 2017 including wing wall foundations bituminous paint excavation backfilling and as directed by Engineer	High tensile steel bar factory epoxy coated reinforcement of any diameter	Ton	55	94.500	5197.500
PSW21	Concrete and Concrete Structures	Construction of Box culvert N2 Size 2x1.5m concrete class 30 with reinforcement as per HDS 2017 including wing wall foundations bituminous paint excavation backfilling and as directed by Engineer	Waterproofing for Structures Note	Item	0	0.000	0.000
PSW22	Concrete and Concrete Structures	Construction of Box culvert N2 Size 2x1.5m concrete class 30 with reinforcement as per HDS 2017 including wing wall foundations bituminous paint excavation backfilling and as directed by Engineer	Tar or bituminous paint Type II 2 coats for surfaces in contact with earth in all structures	m2	1420	1.050	1491.000



BILL NO 06 PROTECTION AND STORM WATER DRAINAGE

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
PSW23	Concrete and Concrete Structures	Construction of Box culvert N2 Size 2x1.5m concrete class 30 with reinforcement as per HDS 2017 including wing wall foundations bituminous paint excavation backfilling and as directed by Engineer	Membrane Waterproofing Geotextile 4mm thickness	m2	15500	1.050	16275.000
PSW24	Drainage	Storm Sewer	Item includes and not limited to 200mm aggregate Sand bed and aggregatesand surrounding 200 mm of pipe crown fixing with approved slop and concrete fixing for pipe from middel end and crawn testing flexible joint rocker piece giotextile membrane surrounding including proper reinstatement with concrete or interlock or asphalt above the compacted surface in the existing route or new route etc.	Item	0	0.000	0.000
PSW25	Drainage	Storm Sewer	Storm Sewer GRP Diameter 300mm	m	315	3.150	992.250
PSW26	Drainage	Storm Sewer	Storm Sewer GRP Diameter 400mm	m	1270	2.100	2667.000
PSW27	Drainage	Storm Sewer	Storm Sewer GRP Diameter 500mm	m	345	1.575	543.375
PSW28	Drainage	Storm Sewer	Storm Sewer R.C Diameter 600mm	m	865	1.575	1362.375
PSW29	Drainage	Storm Sewer	Storm Sewer R.C Diameter 700mm	m	1090	2.100	2289.000
PSW30	Drainage	Storm Sewer	Storm Sewer R.C Diameter 800mm	m	460	2.100	966.000
PSW31	Drainage	Storm Sewer	Storm Sewer R.C Diameter 900mm	m	130	3.150	409.500



BILL NO 06 PROTECTION AND STORM WATER DRAINAGE

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
PSW32	Drainage	Storm Sewer	Storm Sewer R.C Diameter 1200mm	m	490	3.150	1543.500
PSW33	Drainage	Manholes Inlets and Chambers Note	Item includes MH double seal cover DI heavy duty with lock water proofing and as per detailed drawings Note	Item	0	0.000	0.000
PSW34	Drainage	Manholes Inlets and Chambers	R.C Manholes Chamber Ring Dia. 1200mm Type A	No	48	3.150	151.200
PSW35	Drainage	Manholes Inlets and Chambers	R.C Manholes Chamber Ring Dia. 1500mm Type A	No	21	4.200	88.200
PSW36	Drainage	Manholes Inlets and Chambers	R.C Manholes Chamber Ring Dia. 2000mm Type A	No	9	4.200	37.800
PSW37	Drainage	Manholes Inlets and Chambers	R.C Manholes Chamber Ring Dia. 1500mm Type B	No	8	4.200	33.600
PSW38	Drainage	Drainage of Structures	Gully Grating and Frame DI Heavy Duty	No	145	4.305	624.225
PSW39	Drainage	Drainage of Structures	UPVC Drainage pipe to drain gully to manhole 200mm Diameter	No	2010	4.305	8653.050
PSW40	Slope Protection and Stabilization	Riprap	Mortared stone riprap Class A including fillter membrane and fillter material 150 mm thickness	m3	15315	0.840	12864.600
PSW41	Slope Protection and Stabilization	Existing Dyke Improvement:	Remove the existing dyke use the suitable backfilling and compact in the new place in layers as per Oman specifications shift not suitable existing backfilling materials to damp yard etc.	Item	1	52.500	52.500
TOTAL PROTECTION AND STORM WATER DRAINAGE SYSTEM							265,674.675



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C1	General Works	Demolishing and Clearing the Construction Area.	Demolishing the complete buildings up to foundations and removing the debris from the Construction Site as per Engineer/Employer Instruction (including cart-away from the Project Site)	LS	1	2,000.000	2,000.000
C2	Substructure Works	Site Clearance	This shall include removing vegetation, undergrowth, bushes, hedges, trees, other temporary buildings, structures,... or the like all complete to clean the full plot.	LS	1	1,000.000	1,000.000
C3	Substructure Works	Earth work and Excavation	Bulk Excavation to receive foundations in any kind of soil including hard soil and rock, earth sport, underground, surface or running water from whatever source if any, for the new foundation building area including removal of old buildings' foundations, cleaning the site, and removing all debris (not suitable for backfilling) from the project area to the damp yard, contractor to prepare all areas to receive new foundation safely as per drawings and soil report	M3	350	0.800	280.000
C4	Substructure Works	Filling	Approved imported granular fill material compacted in layers in making up levels in the excavation area of the demolished buildings from foundation level up to levels on site plan.	M3	400	0.500	200.000
C5	Substructure Works	Filling	Approved imported fill material compacted in layers to raise the levels	M3	200	0.500	100.000
C6	Substructure Works	Filling	Approved, selected excavated material backfilled into excavations	M3	350	0.500	175.000
C7	Substructure Works	Filling	200 mm thick well compacted hardcore filling under floors	M3	35	0.500	17.500
C8	Substructure Works	Anti-termite treatment	Anti-termite treatment to surfaces of ground or filling applied strictly in accordance with the manufacturers printed instructions including digging trenches, backfilling, etc. as required by the manufacturer and the provision of guarantee valid for 10 years	M2	150	1.500	225.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C9	Substructure Works	Poured Concrete - Plain insitu concrete, poured ordinary Portland Cement (OPC), concrete grade (C15), all in accordance with Drawings and Specifications and including Formwork to give (as struck) finish - Providing and erecting formwork including all necessary staging, centering, shuttering, supports, cross bracing, de-shuttering carefully, making good the damaged surfaces wherever necessary, all complete as specified and as directed by the Engineer all in accordance with the Drawings and Specifications	Blinding upto 100 mm thickness for the full area under the boundary of foundation.	M3	17.5	45.000	787.500



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C10	Substructure Works	Reinforced insitu concrete, poured vibrated Sulphate Resistent Cement (OPC), concrete grade (C30), all in accordance with Drawings and Specifications and including Reinforcement - High yield strength deformed bars, conforming to BS 4449 (grade 460) including cutting, bending, binding, binding wire, cover blocks, tests and all necessary fixing accessories, all in accordance with the Drawings and Specifications and including Formwork to give (as struck) finish - Providing and erecting formwork including all necessary staging, centering, shuttering, supports, cross bracing, de-shuttering carefully, making good the damaged surfaces wherever necessary, all complete as specified and as directed by the Engineer all in accordance with the Drawings and Specifications	Footings	M3	45	50.000	2,250.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C11	Substructure Works	Reinforced insitu concrete, poured vibrated Sulphate Resistent Cement (OPC), concrete grade (C30), all in accordance with Drawings and Specifications and including Reinforcement - High yield strength deformed bars, conforming to BS 4449 (grade 460) including cutting, bending, binding, binding wire, cover blocks, tests and all necessary fixing accessories, all in accordance with the Drawings and Specifications and including Formwork to give (as struck) finish - Providing and erecting formwork including all necessary staging, centering, shuttering, supports, cross bracing, de-shuttering carefully, making good the damaged surfaces wherever necessary, all complete as specified and as directed by the Engineer all in accordance with the Drawings and Specifications	Plinth beams	M3	14	50.000	700.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C12	Substructure Works	Reinforced insitu concrete, poured vibrated Sulphate Resistent Cement (OPC), concrete grade (C30), all in accordance with Drawings and Specifications and including Reinforcement - High yield strength deformed bars, conforming to BS 4449 (grade 460) including cutting, bending, binding, binding wire, cover blocks, tests and all necessary fixing accessories, all in accordance with the Drawings and Specifications and including Steel fabric reinforcement, A-393 BRC mesh in two layers. All complete in accordance with the	Beds (Slabs, Grade slabs) upto 200 mm thickness	M3	30	50.000	1,500.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C13	Substructure Works	Reinforced insitu concrete, poured vibrated ordinary Portland Cement (OPC), concrete grade (C40), all in accordance with Drawings and Specifications and including Reinforcement - High yield strength deformed bars, conforming to BS 4449 (grade 460) including cutting, bending, binding, binding wire, cover blocks, tests and all necessary fixing accessories, all in accordance with the Drawings and Specifications and including Formwork to give (as struck) finish - Providing and erecting formwork including all necessary staging, centering, shuttering, supports, cross bracing, de-shuttering carefully, making good the damaged surfaces wherever necessary, all complete as specified and as directed by the Engineer all in accordance with the Drawings and Specifications	Substructure columns	M3	4	50.000	200.000
C14	Substructure Works	Concrete / Block work Protection	Polythene sheet, gauge 1200, all in accordance with Drawings and Specifications - to surfaces of structural members in contact with soil	M2	115	0.500	57.500
C15	Substructure Works	Bitumenous Sheet	Bitumenous Paint base coat and 4mm membrane to the surfaces of concrete and block work(foundation + solid block work + short columns)	M2	300	5.000	1,500.000
C16	Substructure Works	Bitumenous Paint	Bitumenous paint 3 coats to the surfaces of concrete (plinth beams)	M2	145	0.500	72.500



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C17	Substructure Works	Concrete solid block work, 10.5N/mm2 compressive strength, cement and sand mortar (1:3), with and including stiffener columns and stiffener beams, as required, all in accordance with Drawings and Specifications	200mm thick walls	M2	120	6.000	720.000
C18	Substructure Works	Block work Protection including Bitumenous Paint and Bitumenous Sheet	Protection to concrete and excavated area, masonry/block work in contact with soil, Bitumenous Paint base coat of approved bituminous paint, 4mm bituminous sheet, and including flexible board all in accordance with Drawings and Specifications - to surfaces of block work in contact with soil.up to bottom of plinth beams	M2	250	1.000	250.000
C19	Substructure Works	The Contractor should read and quote as per the supply, laying, and all works are included and required approval & commissioning as per contract standards should be under the Contractor scope of work including required charges, also including DNP scope and guarantees for material.	Important Note	Item	0	0.000	0.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C20	Substructure Works	The Contractor is advised to complete the project as per the drawing, boq and specification also need to complete if anything missing in the drawing but mentioned in the boq/specification and viceversa. Should the Tenderer fail to insert any item here, it will be deemed that this lump sum price for the tender includes all items and no subsequent claim for any additional items will be entertained	Important Note	Item	0	0.000	0.000
C21	Substructure Works	The Contractor is to detail below any additional items with quantities and rates not previously included to complete the build up of the lump sum tender price for this section of the works. Should the Tenderer fail to insert any item here, it will be deemed that this lump sum price for the tender includes all items and no subsequent claim for any additional items will be entertained	Important Note	Item	0	0.000	0.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C22	Superstructure Works Concrete Works	Poured Concrete - Reinforced insitu concrete, poured vibrated Ordinary Portland Cement (OPC), concrete grade (C30), all in accordance with the Drawings and Specifications and including Reinforcement - High yield strength deformed bars, conforming to BS 4449 (grade 460) including cutting, bending, binding, binding wire, cover blocks, tests and all necessary fixing accessories, all in accordance with the Drawings and Specifications and including Formwork to give (as struck) finish - Providing and erecting formwork including all necessary staging, centering, shuttering, supports, cross bracing, de-shuttering carefully, making good the damaged surfaces wherever necessary, all complete as specified and as directed by the Engineer all in accordance with the Drawings and Specifications	Suspended slabs, waist slabs, landings, stair etc. not exceeding 250 mm thickness	M3	30	50.000	1,500.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C23	Superstructure Works Concrete Works	Poured Concrete - Reinforced insitu concrete, poured vibrated Ordinary Portland Cement (OPC), concrete grade (C30), all in accordance with the Drawings and Specifications and including Reinforcement - High yield strength deformed bars, conforming to BS 4449 (grade 460) including cutting, bending, binding, binding wire, cover blocks, tests and all necessary fixing accessories, all in accordance with the Drawings and Specifications and including Formwork to give (as struck) finish - Providing and erecting formwork including all necessary staging, centering, shuttering, supports, cross bracing, de-shuttering carefully, making good the damaged surfaces wherever necessary, all complete as specified and as directed by the Engineer all in accordance with the Drawings and Specifications	Columns	M3	10	50.000	500.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C24	Superstructure Works Concrete Works	Poured Concrete - Reinforced Insitu concrete, poured vibrated Ordinary Portland Cement (OPC), concrete grade (C30), all in accordance with the Drawings and Specifications and including Reinforcement - High yield strength deformed bars, conforming to BS 4449 (grade 460) including cutting, bending, binding, binding wire, cover blocks, tests and all necessary fixing accessories, all in accordance with the Drawings and Specifications and including Formwork to give (as struck) finish - Providing and erecting formwork	Beams	M3	15	50.000	750.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C25	Superstructure Works Concrete Works	Poured Concrete - Reinforced insitu concrete, poured vibrated Ordinary Portland Cement (OPC), concrete grade (C30), all in accordance with the Drawings and Specifications and including Reinforcement - High yield strength deformed bars, conforming to BS 4449 (grade 460) including cutting, bending, binding, binding wire, cover blocks, tests and all necessary fixing accessories, all in accordance with the Drawings and Specifications and including Formwork to give (as struck) finish - Providing and erecting formwork including all necessary staging, centering, shuttering, supports, cross bracing, de-shuttering carefully, making good the damaged surfaces wherever necessary, all complete as specified and as directed by the Engineer all in accordance with the Drawings and Specifications	Ramp and Entrances Stairs	M3	3	45.000	135.000
C26	Superstructure Works Masonry	Internal Walls - Ordinary Portland cement concrete blocks, 7.5N/mm2 compressive strength, cement and sand mortar (1:3), with and including stiffener columns and stiffener beams, as required, all in accordance with the Drawings and Specifications	200mm thick walls	M2	260	6.000	1,560.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C27	Superstructure Works Masonry	Sunken Slab Waterproofing	Providing and applying Sunken Slab Waterproof course with bituminous paint and bituminous membrane conforming to BS:6398 in horizontal joints laid strictly in compliance with approved manufacturers printed instructions and as directed by Engineer.	M2	20	2.000	40.000
C28	Superstructure Works Thermal and Moisture Protection	Backgrounds and Finishes - Roof screed, light weight concrete screed 1000 kg/m3, minimum 50 mm thick to a maximum of 125 mm thick	50 mm (minimum) bed laid on concrete to falls and cross falls	M2	130	25.000	3,250.000
C29	Superstructure Works Thermal and Moisture Protection	4 mm thick torch applied acrylic polypropylene modified bitumen membrane with non-woven polyester reinforcement and polyethylene film waterproof membrane including primer to roofs as per the manufacturer printed instructions complete as specified. (Contractor to allow for 10 years guarantee and 24 hours flood test)	To roof decks, 4mm thick, on flat surface, laid to falls and cross falls	M2	130	1.500	195.000
C30	Superstructure Works Thermal and Moisture Protection	Skirting 300 mm girth including turning into groove	In up stands/drops and around plinths (minimum 300 mm high) including dressing over fillet grooves, sealant, tantalized batten etc. complete, to roof deck	LM	85	1.000	85.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C31	Superstructure Works Thermal and Moisture Protection	Insulation - Extruded high density polystyrene foam board insulation, with rigid closed cell structure, all in accordance with the specifications and drawings, external	to roof decks - 50 mm thick, laid on concrete, spot bonded to waterproofing	M2	130	2.000	260.000
C32	Superstructure Works Thermal and Moisture Protection	Roof Finishes	300 x 300 x 30 mm white cement tiles bedded on and including cement mortar screed to falls and cross falls, jointed in cement mortar, movements joints etc., complete - to roof	M2	130	0.500	65.000
C33	Superstructure Works Thermal and Moisture Protection	Roof Finishes	100 x 30 mm white cement skirting to upstands	LM	85	1.000	85.000
C34	Superstructure Works Thermal and Moisture Protection	Roof Sundries	Allow for Providing dressing around 110mm/83mm UPVC rainwater outlets roof duct, gargoyles, extract fan, soil and vent pipe	No	5	0.000	0.000
C35	Superstructure Works Thermal and Moisture Protection	Roof Sundries	Allow for gun applied sealant to seal the joints and groove as applicable and as specified.	Item	1	0.000	0.000
C36	Superstructure Works Metal Works	Staircase hand rail	Stainless steel handrail as shown in the Architectural drawing, shop drawings with full sections details to be approved before supply. Note : all stainless steel material shall be of 304 grade.	LM	10	15.000	150.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C37	Superstructure Works Metal Works	CAT Ladder	Supply and install a 3800mm high CAT steel Ladder as specified and detailed on the drawing, with anti-correlation epoxy pain.	No	1	100.000	100.000
C38	Superstructure Works Doors and Windows	Wood Doors - Note	1) All timber and veneers shall be well conditioned, seasoned, dried, vacuum treated and preservative treated all as specified	Item	1	0.000	0.000
C39	Superstructure Works Doors and Windows	Wood Doors - Note	2) Prepare the surface, prime and apply two under coats and two finishing coats of high gloss enamel paint of approved quality, make and shade for shutter and frame	Item	1	0.000	0.000
C40	Superstructure Works Doors and Windows	Wood Doors - Note	3) All hardwood timber shall be best quality Meranti	Item	1	0.000	0.000
C41	Superstructure Works Doors and Windows	Wood Doors - Note	4) Sizes stated are structural opening sizes	Item	1	0.000	0.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C42	Superstructure Works Doors and Windows	Wood Doors -Door comprising profiled heads, jambs, frames, subframes, architraves, beadings, mouldings, plinth block, ply linings, infill panels, mastic and other pointing, fixings, neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved; fixed to hardwood, including paint (All locks shall be under master key system) as detailed on drawing Note : all stainless steel fittings shall be of 304 grade	Type D1, double leaf, overall size 1800x2500mm high	No	1	355.000	355.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C43	Superstructure Works Doors and Windows	Wood Doors -Door comprising profiled heads, jambs, frames, subframes, architraves, beadings, mouldings, plinth block, ply linings, infill panels, mastic and other pointing, fixings, neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved; fixed to hardwood, including paint (All locks shall be under master key system) as detailed on drawing Note : all stainless steel fittings shall be of 304 grade	Type D2, single leaf, overall size 1000x2500mm high	No	1	410.000	410.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C44	Superstructure Works Doors and Windows	Wood Doors -Door comprising profiled heads, jambs, frames, subframes, architraves, beadings, mouldings, plinth block, ply linings, infill panels, mastic and other pointing, fixings, neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved; fixed to hardwood, including paint (All locks shall be under master key system) as detailed on drawing Note : all stainless steel fittings shall be of 304 grade	Type D3, single leaf, overall size 1000x2100mm high	No	4	400.000	1,600.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C45	Superstructure Works Doors and Windows	Wood Doors -Door comprising profiled heads, jambs, frames, subframes, architraves, beadings, mouldings, plinth block, ply linings, infill panels, mastic and other pointing, fixings, neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved; fixed to hardwood, including paint (All locks shall be under master key system) as detailed on drawing Note : all stainless steel fittings shall be of 304 grade	Type D4, single leaf overall size 800x2100mm high	No	2	400.000	800.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C46	Superstructure Works Doors and Windows	Wood Doors -Door comprising profiled heads, jambs, frames, subframes, architraves, beadings, mouldings, plinth block, ply linings, infill panels, mastic and other pointing, fixings, neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved; fixed to hardwood, including paint (All locks shall be under master key system) as detailed on drawing Note : all stainless steel fittings shall be of 304 grade	Type D5, single leaf overall size 1000x2100mm high	No.	1	400.000	400.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C47	Superstructure Works Doors and Windows	Wood Doors -Door comprising profiled heads, jambs, frames, subframes, architraves, beadings, mouldings, plinth block, ply linings, infill panels, mastic and other pointing, fixings, neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved; fixed to hardwood, including paint (All locks shall be under master key system) as detailed on drawing Note : all stainless steel fittings shall be of 304 grade	Type D6, single leaf overall size 1000x2400mm high	No	1	400.000	400.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C48	Superstructure Works Doors and Windows	WPC Solid Core Doors -Door comprising profiled heads, jambs, frames, subframes, architraves, beadings, moldings, plinth block, ply linings, infill panels, mastic and other pointing, fixings, neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved; fixed to hardcore, including paint and 10 years guarantee (All locks shall be under master key system) as detailed on drawing Note: all stainless steel fittings shall be of 304 grade	Type D1, double leaf, overall size 1800x2500mm high	Item	1	400.000	400.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C49	Superstructure Works Doors and Windows	WPC Solid Core Doors -Door comprising profiled heads, jambs, frames, subframes, architraves, beadings, moldings, plinth block, ply linings, infill panels, mastic and other pointing, fixings, neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved; fixed to hardcore, including paint and 10 years guarantee (All locks shall be under master key system) as detailed on drawing Note: all stainless steel fittings shall be of 304 grade	Type D2, single leaf, overall size 1000x2500mm high	Item	1	400.000	400.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C50	Superstructure Works Doors and Windows	WPC Solid Core Doors -Door comprising profiled heads, jambs, frames, subframes, architraves, beadings, moldings, plinth block, ply linings, infill panels, mastic and other pointing, fixings, neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved; fixed to hardcore, including paint and 10 years guarantee (All locks shall be under master key system) as detailed on drawing Note: all stainless steel fittings shall be of 304 grade	Type D3, single leaf, overall size 1000x2100mm high	Item	1	400.000	400.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C51	Superstructure Works Doors and Windows	WPC Solid Core Doors -Door comprising profiled heads, jambs, frames, subframes, architraves, beadings, moldings, plinth block, ply linings, infill panels, mastic and other pointing, fixings, neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved; fixed to hardcore, including paint and 10 years guarantee (All locks shall be under master key system) as detailed on drawing Note: all stainless steel fittings shall be of 304 grade	Type D4, single leaf overall size 800x2100mm high	Item	1	400.000	400.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C52	Superstructure Works Doors and Windows	WPC Solid Core Doors -Door comprising profiled heads, jambs, frames, subframes, architraves, beadings, moldings, plinth block, ply linings, infill panels, mastic and other pointing, fixings, neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved; fixed to hardcore, including paint and 10 years guarantee (All locks shall be under master key system) as detailed on drawing Note: all stainless steel fittings shall be of 304 grade	Type D5, single leaf overall size 1000x2100mm high	Item	1	400.000	400.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C53	Superstructure Works Doors and Windows	WPC Solid Core Doors -Door comprising profiled heads, jambs, frames, subframes, architraves, beadings, moldings, plinth block, ply linings, infill panels, mastic and other pointing, fixings, neoprene seal master lining and all ancillary items including fixing of ironmongery and final decoration for a complete installation all as specified and as detailed on drawing including required reinforcement cement concrete lintels and including Supply and fix ironmongery as specified in schedule and approved; fixed to hardcore, including paint and 10 years guarantee (All locks shall be under master key system) as detailed on drawing Note: all stainless steel fittings shall be of 304 grade	Type D6, single leaf overall size 1000x2400mm high	Item	1	400.000	400.000
C54	Superstructure Works Doors and Windows	Ironmongery - Supply and fix of ironmongery, with and including all necessary fixing accessories and screws to match, all in accordance with the specifications and drawings - to wood doors	Allow for grand master key and master key system	Item	1	100.000	100.000
C55	Superstructure Works Doors and Windows	UPVC windows -window sets complete with all necessary ironmongery as specified, including fixing to blockwork or concrete and mastic pointing all around, all as specified and detailed on drawing and including required reinforcement cement concrete lintels	Type W1, overall size 2000 x 1300mm high	No	13	50.000	650.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C56	Superstructure Works Doors and Windows	UPVC windows -window sets complete with all necessary ironmongery as specified, including fixing to blockwork or concrete and mastic pointing all around, all as specified and detailed on drawing and including required reinforcement cement concrete lintels	Type W2, overall size 1200 x 900mm high,	No	1	50.000	50.000
C57	Superstructure Works Doors and Windows	UPVC ventilator -ventilator sets complete with all necessary ironmongery as specified, including fixing to blockwork or concrete and mastic pointing all around, all as specified and detailed on drawing and including required reinforcement cement concrete lintels	Type V, overall size 600 x 600mm high	No	2	50.000	100.000
C58	Superstructure Works Finishes	Backgrounds - Plaster, cement and sand (1:3), internal - To walls and columns, on concrete block base, internal including stainsteel mesh, butterfly angle between the concrete column and block work.	to receive internal painting	M2	600	1.000	600.000
C59	Superstructure Works Finishes	Backgrounds - Plaster, cement and sand (1:4), external - To walls and columns, on concrete block base, external including stainsteel mesh, butterfly angle between the concrete column and block work.	to receive external painting	M2	480	1.500	720.000
C60	Superstructure Works Finishes	Allow for laying of Marble Threshold as per the specifications, drawings and to approval of the Engineer.	Internal Floor Tile	NO	1	500.000	500.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C61	Superstructure Works Finishes	Floor Tiles: FF1 Ceramic floor tiles laid on screed grouted with waterproof coloured compatible mortar to manufacturers specification/instruction; internally	600 x 600 x 8 mm Anti-Slip tiling to floor	M2	85	3.000	255.000
C62	Superstructure Works Finishes	Floor Tiles: FF2 Ceramic floor tiles laid on screed grouted with waterproof coloured compatible mortar to manufacturers specification/instruction; internally	600 x 600 x 8 mm Anti-Slip tiling to floor	M2	12	3.000	36.000
C63	Superstructure Works Finishes	Floor Tiles: FF3 Ceramic floor tiles laid on screed grouted with waterproof coloured compatible mortar to manufacturers specification/instruction; internally	600 x 200 x 8 mm Anti-Slip tiling to floor	M2	10	3.000	30.000
C64	Superstructure Works Finishes	Floor Tiles: FF4 30mm tk. Granite laid on screed grouted with waterproof coloured compatible mortar to manufacturers specification/instruction; internally	30mm thick Granite for Staircase and Steps	M2	20	4.000	80.000
C65	Superstructure Works Finishes	Floor Tiles: FF9 Granite tiles laid on screed grouted with waterproof coloured compatible mortar to manufacturers specification/instruction; internally	30mm thick Granite for Entrance floor and Staircase and Steps	M2	5	4.000	20.000
C66	Superstructure Works Finishes	Skirting Tiles: FF1 Ceramic tiles laid on screed grouted with waterproof coloured compatible mortar to manufacturers specification/instruction; internally	Ceramic Tiles 600 X 150 X 8 Anti Slip	LM	100	3.000	300.000
C67	Superstructure Works Finishes	Skirting Tiles: FF4 30mm tk. Granite laid on screed grouted with waterproof coloured compatible mortar to manufacturers specification/instruction; internally	30mm thick Granite for Staircase and Steps	LM	20	4.000	80.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C68	Superstructure Works Finishes	Allow for construction of Decorative projection, weather coat stoneshield with 10 years guarantee as per the specifications, drawings and to approval of the Engineer	External Elevation	Item	1	0.000	0.000
C69	Superstructure Works Finishes	Allow for construction of Decorative projection, weather coat stoneshield with 10 years guarantee as per the specifications, drawings and to approval of the Engineer	F1/F2 External Elevation	M2	470	5.000	2,350.000
C70	Superstructure Works Finishes	Allow for construction of Decorative projection as per the specifications, drawings and to approval of the Engineer	F3 External Elevation	Item	10	5.000	50.000
C71	Superstructure Works Finishes	Wall Finishes - FF1 Painting and decorating, Eligance marble paint finish internal	Smooth Plaster, Painting, Anti Fungal and Water Resistance	M2	300	1.000	300.000
C72	Superstructure Works Finishes	Wall Finishes - FF2 Ceramic Tiles 600 X 200 X 8 Anti Slip	Ceramic Tiles 600 X 200 X 20 Anti Slip	M2	40	3.000	120.000
C73	Superstructure Works Finishes	Wall Finishes - FF3 Ceramic Tiles 600 X 200 X 8 Anti Slip	Ceramic Tiles 600 X 200 X 20 Anti Slip	M2	65	3.000	195.000
C74	Superstructure Works Finishes	Wall Finishes - FF4 Smooth Plaster, Painting, Eligance marble paint finish Anti Fungal and Water Resistance	Smooth Plaster, Painting, Anti Fungal and Water Resistance	M2	160	1.000	160.000
C75	Superstructure Works Finishes	Ceilings Finishes - FF1 Painting and decorating, Eligance marble paint finish internal	Smooth Plaster, Painting, Anti Fungal and Water Resistance	M2	85	1.000	85.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C76	Superstructure Works Finishes	Ceilings Finishes - FF2 Smooth Plaster, Painting, Eligance marble paint finish Anti Fungal and Water Resistance	Smooth Plaster, Painting, Anti Fungal and Water Resistance	M2	12	1.000	12.000
C77	Superstructure Works Finishes	Ceilings Finishes - FF3 Smooth Plaster, Painting, Eligance marble paint finish Anti Fungal and Water Resistance	Smooth Plaster, Painting, Anti Fungal and Water Resistance	M2	10	1.000	10.000
C78	Superstructure Works Finishes	Ceilings Finishes - FF4 Smooth Plaster, Painting, Eligance marble paint finish Anti Fungal and Water Resistance	Smooth Plaster, Painting, Anti Fungal and Water Resistance	M2	20	1.000	20.000
C79	Superstructure Works Finishes	Allow for supply, fabricate and installation of Gas Cyclinder Stage as per the specifications, drawings and to approval of the Engineer.	Gas Cylinder Stage	Item	1	75.000	75.000
C80	Superstructure Works Finishes	Allow for core-cut, remove and smooth finish as per the specifications, drawings and to approval of the Engineer.	Drain Open to connect Sewage Tanker to the Holding Tank, size 550 X 400mm	Item	1	100.000	100.000
C81	Superstructure Works Finishes	Allow for supply, fabricate and installation of water point protection as per the specifications, drawings and to approval of the Engineer.	Water point protection	Item	1	50.000	50.000
C82	Superstructure Works Finishes	Allow for supply, fabricate and installation of Meter Panel protection as per the specifications, drawings and to approval of the Engineer.	Meter Panel protection	Item	1	100.000	100.000
C83	Superstructure Works Finishes	Allow for supply, fabricate and installation of Kitchen Stage including Stage Concrete, Stage Korean Top and Stage Area Ceramic Wall Tile as per the specifications, drawings and to approval of the Engineer.	Kitchen Stage Concrete, Korean Top, Ceramic Wall Tiles	Item	1	500.000	500.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C84	Superstructure Works Finishes	Allow for supply, fabricate and installation of Kitchen Hood Range including Aluminum Kitchen Cabinet above, and Aluminum Kitchen Cabinet below all as per the specifications, drawings and to approval of the Engineer.	Kitchen Hood Range, Cabinet above and below Cabinet.	Item	1	200.000	200.000
C85	Superstructure Works Finishes	The Contractor should read and quote as per the supply, laying, and all works are included and required approval & commissioning as per contract standards should be under the Contractor scope of work including required charges, also including DNP scope and guarantees for material.	Important Note	Item	0	0.000	0.000
C86	Superstructure Works Finishes	The Contractor is adviced to complete the project as per the drawing, boq and specification also need to complete if anything missing in the drawing but mentioned in the boq/specification and viceversa. Should the Tenderer fail to insert any item here, it will be deemed that this lump sum price for the tender includes all items and no subsequent claim for any additional items will be entertained	Important Note	Item	0	0.000	0.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
C87	Superstructure Works Finishes	The Contractor is to detail below any additional items with quantities and rates not previously included to complete the build up of the lump sum tender price for this section of the works. Should the Tenderer fail to insert any item here, it will be deemed that this lump sum price for the tender includes all items and no subsequent claim for any additional items will be entertained	Important Note	Item	0	0.000	0.000
EW1	External Works - General Site Works	Boundary wall	Allow for the Contractor to prepare RCC foundation, column, block work, plastering and painting as per the Architectural Drawing and as per Engineer / Employer Instruction to complete the Boundary Wall.	LM	128	100.000	12,800.000
EW2	External Works - General Site Works	Wicket Gate	Allow for the Contractor to supply, fabricate and installation of single leaf Wicket Gate as per the Architectural Drawing and follow as per Engineer / Employer Instructions, including anti corrosion epoxy paint.	Item	1	0.000	0.000
EW3	External Works - General Site Works	Car Entrance Gate	Allow for the Contractor to supply, fabricate and installation of single leaf Car Entrance Gate as per the Architectural Drawing and follow as per Engineer / Employer Instructions, including anti corrosion epoxy paint	Item	1	0.000	0.000
EW4	External Works - General Site Works	Entrance Gate	Allow for the Contractor to supply, fabricate and installation of Wicket Gate solid WPC with 10 years guarantee as per the Architectural Drawing and follow as per Engineer / Employer Instructions, including anti corrosion epoxy paint.	NO	1	1,500.000	1,500.000
EW5	External Works - General Site Works	Wicket Gate	Single leaf Wicket Gate solid WPC	Item	1	900.000	900.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
EW6	External Works - General Site Works	Car Entrance Gate	Single leaf Car Entrance Gate soild WPC	Item	1	1,200.000	1,200.000
EW7	External Works - General Site Works	Entrance Concrete Paver	Allow for the Contractor to prepare Concrete Paver as per the Architectural Drawing and place at the House Main Entrance.	No	20	44.000	880.000
EW8	External Works - General Site Works	Interlock Tile	Allow for connection Asphalt road to the site from the main drawing as per approval	M2	180	5.000	900.000
EW9	External Works - General Site Works	Curb Stone	Allow for connection Asphalt road to the site from the main drawing as per approval	LM	80	8.000	640.000
EW10	External Works - General Site Works	Design and Build Shaded Car Parking of 20 numbers with Solar Panel Canopy	Allow for the Contractor to design and build the Shaded Car Park for houses with Solar Panel Canopy, as per Engineer / Employer Instruction.	Item	1	1,300.000	1,300.000
P1	Sanitary Installation	UPVC pipes to BS 4514 1983 and BS 4660 1973 including all joints and accessories and brackets Note	UPVC drain pipes to BS 4514 1983 and BS 4660 1973 including all joints with ring seals fittings and accessories in the running length	Item	0	0.000	0.000
P2	Sanitary Installation	ditto	160mm diamater	M	40	10.000	400.000
P3	Sanitary Installation	ditto	110mm diamater	M	6	8.000	48.000
P4	Sanitary Installation	ditto	82mm diameter	M	7	8.000	56.000
P5	Sanitary Installation	ditto	50mm diameter	M	8	8.000	64.000
P6	Sanitary Installation	ditto	42mm diameter	M	8	8.000	64.000
P7	Sanitary Installation	vent cowl	Vent cowl with weathering apron 50mm diameter	No	2	8.000	16.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
P8	Sanitary Installation	Floor Drain trap	Floor Trap with 150 X 150 mm SS grating Cover	No	3	25.000	75.000
P9	Sanitary Installation	Gully Trap	300 mm and 300 mm gully trap of approximate 300 mm depth set in concrete Grade 30 Nmm joints to drain pipes complete with 300 mm and 300 mm medium duty cast iron cover and frame.	No	2	30.000	60.000
P10	Grease Trap	Grease Trap	300 mm and 300 mm grease trap of approximate 300 mm depth set in concrete Grade 30 Nmm joints to drain pipes complete with 300 mm and 300 mm medium duty cast iron cover and frame.	No	1	30.000	30.000
P11	Sanitary Installation	Inspection Chambers	Manhole size 600 and 600 mm internally upto 1.24m deep to invert	No	7	180.000	1,260.000
P12	Sanitary Installation	Manhole Cover	600 and 600 mm medium duty double seal cast iron manhole cover and frame.	No	7	110.000	770.000
P13	Sanitary Installation	Holding tank with soak pit	Reinforced concrete grade 30 N mm2 holding tank size 4000 and 2000 and 2500 mm deep internally with concrete grade 15 N mm2 and 100mm thick blinding and 250mm thick concrete base slab and 200mm thick concrete wall and roof slab and including reinforcement and formwork and rendering and step irons and 3 coats of bitumen paint and 2 layer of 1000 gauge polythene sheet and excavation and dewatering backfilling and disposal of surplus excavated materials and 600 and 600 mm heavy duty double seal ductile iron cover and frame and Precast concrete soak pit size 2000 mm diameter and 2500 mm deep internally including reinforcement and excavation and dewatering and backfilling and disposal of surplus excavated materials 600 and 600 mm heavy duty ductile iron cover and frame et as detailed on drawing.	No	1	5,000.000	5,000.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
P14	Sanitary Wares and Fittings	Semi pedestal wash basin	650 mm and 475 mm vitreous china white wash basin with semi pedestal and center tap hole and overflow and bottle trap including required complete Civil Works.	No	2	85.000	170.000
P15	Sanitary Wares and Fittings	Stainless Steel Sink	1000 mm and 550 mm stainless steel sink single bowl single drainer with drainboard to BS 1244 complete with 2 piece tubular P trap chain and plug and waste and brackets including required complete Civil Works.	No	1	120.000	120.000
P16	Sanitary Wares and Fittings	European Water Closet	400 mm and 685 mm vitreous china white concealed tank wall hung mounted EWC squatting pan built in wall toilet dual flush 3L or 6L concealed cistern and heavy duty auto closed seat and cover including required complete Civil Works.	No	2	100.000	200.000
P17	Sanitary Wares and Fittings	Faucet spray	Chromium plated approved ablution faucet with angle valve and hose and spray unit.	No	2	25.000	50.000
P18	Sanitary Wares and Fittings	Wash Basin Mixer	Single lever chrome plated wash basin mixer including pop up waste.	No	2	40.000	80.000
P19	Sanitary Wares and Fittings	Sink Mixer	Single lever chrome plated Sink mixer.	No	1	40.000	40.000
P20	Sanitary Wares and Fittings	Toilet tissue holder	Recessed type stainless steel Toilet tissue dispenser or holder with stainless steel hood.	No	2	15.000	30.000
P21	Sanitary Wares and Fittings	Towel rail	610 and 75 and 75 mm towel rail	No	2	15.000	30.000
P22	Sanitary Wares and Fittings	Mirror	450 and 600 mm mirror 6 mm thick and bevel edged and plywood backing fixed with chromium plated dome headed screws	No	2	15.000	30.000
P23	Sanitary Wares and Fittings	Bath shower	Single lever dual control bath shower mixer	No	2	40.000	80.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
P24	Sanitary Wares and Fittings	Bip tap	For internal and external.	No	2	15.000	30.000
P25	Sanitary Installation	Note	HPUPVC pipes and fittings to BS 3505 Class E including all joints and connections and fittings.	Item	0	0.000	0.000
P26	Sanitary Installation	Hpupvc pipe	25 mm diameter pipe for air conditioner drainage pipe to ac drain pit.	M	24	12.000	288.000
P27	Water Supply installation	Polypropylene random copolymer pipe Note	Polypropylene random copolymer pipes and fittings and cold and hot water connections to international standard ISO EN ISO 15874 2003 and DIN 80777 8078 including up stand and brackets exposed insulation as per Specification in running length and 25mm thick rigid performed sectional fiber glass insulation with aluminum foil and fiber glass reinforced adhesive and canvas Cora cloth with 2 coats of foster paint one coat of water proof emulsion glossy white paint and vapour barrier coating as described.	Item	0	0.000	0.000
P28	Water Supply installation	Cold and Hot water PPR C pipes with insulation	15 mm diameter	M	28	10.000	280.000
P29	Water Supply installation	Cold and Hot water PPR C pipes with insulation	20 mm diameter	M	10	15.000	150.000
P30	Water Supply installation	Cold and Hot water PPR C pipes with insulation	25 mm diameter	M	4	20.000	80.000
P31	Water Supply installation	Cold and Hot water PPR C pipes with insulation	32 mm diameter	M	30	25.000	750.000
P32	Water Supply installation	Cold and Hot water PPR C pipes with insulation	40 mm diameter	M	29	30.000	870.000
P33	Water Supply installation	Cold and Hot water - Valves Note	Supply and install the following Isolating valves to BS 5154 series B bronze and wedge gate pattern and screwed joints with adaptor to pipes etc wherever shown in drawings and or specified and as approved by the Engineer.	Item	0	0.000	0.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
P34	Water Supply installation	Cold and Hot water Valves	15 mm diameter	No	10	25.000	250.000
P35	Water Supply installation	Cold and Hot water Valves	20 mm diameter	No	8	25.000	200.000
P36	Water Supply installation	Cold and Hot water Valves	32 mm diameter	No	4	35.000	140.000
P37	Water Supply installation	Cold and Hot water Valves	32 mm diameter isolating value	No	2	35.000	70.000
P38	Water Supply installation	Cold and Hot water Valves	40 mm diameter	No	2	40.000	80.000
P39	Water Supply installation	Equipment and Accessories Note	Equipment and accessories as specified including all connections and fittings	Item	0	0.000	0.000
P40	Water Supply installation	Water Tank	600 US gallon capacity GRP type water storage tank with foundation epoxy coated frame ball valve overflows etc to approval	No	1	2,500.000	2,500.000
P41	Water Supply installation	Water Heater	50 liter capacity horizontal type copper tank high level wall mounted electrical water heater including all connections and fixing.	No	2	150.000	300.000
P42	Water Supply installation	Booster pump	Cold water pressurised booster pump set 1No Working pump and 1No standby pump for domestic water supply delivering 2 l per sec at 2.5 bar with Gate valve and Non return valve and float switch and pressue guage and pressure vessel 30 to 50 lit PN10 and water low level cut off relay etc with pump room all complete as detailed in the drawing to approval.	No	1	1,500.000	1,500.000
P43	Rain Water Installation	Rain Water UPVC Pipes Note	UPVC pipes to BS 4514 or 1983 including all joints and fittings and accessories and connections and brackets	Item	0	0.000	0.000
P44	Rain Water Installation	Rain Water UPVC Pipes	110mm diamater	M	24	25.000	600.000
P45	Rain Water Installation	Rain water Outlet	110 mm diameter root terminal socket tail rain water outlet.	No	4	25.000	100.000
P46	Plumbing and Drainage System	Sundries	Allow for working drawings and as built drawings.	Item	1	0.000	0.000




BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
P47	Plumbing and Drainage System	Sundries	Allow for all supports plinths and dog houses and necessary builder s work after obtaining approval through shop drawings including setting out and marking holes and chases cut outs etc and making good.	Item	1	0.000	0.000
P48	Plumbing and Drainage System	Sundries	Allow for all protective and decorative painting.	Item	1	0.000	0.000
P49	Plumbing and Drainage System	Sundries	Allow for providing Test Certificates	Item	1	0.000	0.000
P50	Plumbing and Drainage System	Sundries	Allow for co ordination with other Engineering Installations.	Item	1	0.000	0.000
P51	Plumbing and Drainage System	Sundries	Allow for testing and commissioning of underground cable prior to and after backfilling.	Item	1	500.000	500.000
P52	Plumbing and Drainage System	Sundries	Allow for OandM Manual	Item	1	0.000	0.000
P53	Plumbing and Drainage System	Sundries	Allow for sterilization of all pipes and over head tanks etc.	Item	1	0.000	0.000
P54	Plumbing and Drainage System	Sundries	Allow for spare parts for three years as per manufacturers recommendation.	Item	1	0.000	0.000
P55	Plumbing and Drainage System	Sundries	Allow for training OandM staff.	Item	1	0.000	0.000
P56	Plumbing and Drainage System	Sundries	Allow for any other activity not listed above.	Item	1	0.000	0.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
F1	Fire Fighting Installation	Note	Supply and install a complete fire fighting system to the approval of the Civil Defence Authorities and complete with association and fitting as shown in drawings or specified in accordance with BS 530 Part 1 1976 and Part 3 1985 and to approval of the Engineer.	Item	0	0.000	0.000
F2	Fire Fighting Installation	Fire Extinguisher	2 Kg carbon dioxide fire extinguisher	No	1	10.000	10.000
F3	Fire Fighting Installation	Fire Extinguisher	180 and 180 mm fire blanket	No	1	15.000	15.000
F4	Fire Fighting Installation	Fire alarm cable and conduits and panel and accessories installation	Automatic Multi detector point	No	1	15.000	15.000
G1	Gas supply line	Gas line	Supply and fix 18 mm diameter MS schedule 40 gas pipeline including pickup points and connection to Gas Stove	M	10	50.000	500.000
M1	Air Conditioning and Ventilation Installation	High level Wall mounted Split AC with DX unit	12000 BTU HR capacity high level wall mounted split type air conditioner including connection to electrical outlet and concrete base foundation.	No	1	450.000	450.000
M2	Air Conditioning and Ventilation Installation	High level Wall mounted Split AC with DX unit	18000 BTU HR capacity high level wall mounted split type air conditioner including connection to electrical outlet and concrete base foundation.	No	4	600.000	2,400.000
M3	Mechanical installation	Sundries	Allow for builders works in connection with sanitary and water services including holes and chases and sleeves and pipe brackets painted casing to exposed pipes and access panels and weather proof flashing to vent pipes passing through roof etc.	Item	1	0.000	0.000
M4	Mechanical installation	Sundries	Allow for incidental works such as co ordination with other engineering installations	Item	1	0.000	0.000
M5	Mechanical installation	Sundries	Allow for protective covering and painting to all exposed water supply and ventilation pipe work.	Item	1	0.000	0.000
M6	Mechanical installation	Sundries	Allow for identification labels and color coding etc.	Item	1	0.000	0.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
M7	Mechanical installation	Sundries	Allow for testing and commissioning.	Item	1	0.000	0.000
M8	Mechanical installation	Sundries	Allow for chlorination of water storage tanks and pipe work	Item	1	0.000	0.000
M9	Mechanical installation	Sundries	Allow for document As installed drawings and Operation ad Maintenance Manuals	Item	1	0.000	0.000
E1	SUB MAIN DISTRIBUTION BOARD	Sub Main Distribution Board	Sub Main Distribution panel board in weather GRP enclosure IP 65 including 1nos 200A MCCB and 3 NOS 63A,63A,45A MCCB Outgoing Breakers and supports and Busbar and earthing and cable glands and Ammeters and Voltmeters and internal wiring interconnection 1PH 3PH KWH series meters and labels as per approved MHEW drawings	No	1	600.000	600.000
E2	Grease Trap	Note	XLPE PVC SWA PVC copper cable with PVC copper earth continuity conductor including necessary conduit and trunking and cable tray and termination	Item	0	0.000	0.000
E3	Electrical Engineering Installation	Cable	4C and 70 mm ² + 1C x 50 mm ² ECC from MDB to SMDB1	Item	1	0.000	0.000
E4	Electrical Engineering Installation	Distribution Board Note	Distribution board including isolator and ELCB in separate enclosure and MCB RCD MCB as specified along with necessary supports earthing cable glands and internal wiring and interconnection and labels	Item	0	0.000	0.000
E5	Electrical Engineering Installation	Distribution Board	63A TPN 10 way DBs	No	1	50.000	50.000
E6	Electrical Engineering Installation	Distribution Board	63A TPN 10 way DBs	No	1	50.000	50.000
E7	Electrical Engineering Installation	Distribution Board	45A TPN 6way DBs	No	1	45.000	45.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
E8	Electrical Engineering Installation	Cable Note	XLPE PVC SWA PVC copper cable with PVC and copper earth continuity conductor including necessary conduit and trunking and cable tray and termination	Item	0	0.000	0.000
E9	Electrical Engineering Installation	Cable	4C and 35 mm ² + 1C and 25 mm ² ECC from SMDBs to DB1	M	25	15.000	375.000
E10	Electrical Engineering Installation	Cable	4C and 35 mm ² + 1C and 25 mm ² ECC from SMDBs to DB2	M	30	15.000	450.000
E11	Electrical Engineering Installation	Cable	4C and 25 mm ² + 1C and 16 mm ² ECC from SMDB to DB3	M	35	10.000	350.000
E12	Electrical Engineering Installation	Earthing Installation	Earthing system including 16 mm dia. high conductivity solid copper rod electrodes with drive head assemblies and Earthing clamps for earth pits Earthing of exposed pipe work sanitary fittings and equipment all as required including 300 and 300 and 400 mm deep internally earth pit and earth wires as per specification and drawings complete with 300 mm and 300 mm medium duty double seal cast iron cover and frame.	No	1	0.000	0.000
E13	Electrical Engineering Installation	Sundries	Allow for builders work in connection with electrical installation including holes chases sleeves ducts cable tray trucking panel backboards or formwork supports access panels cover plates etc.	Item	1	0.000	0.000
E14	Electrical Engineering Installation	Sundries	Allow for incidental works such as co ordination with other engineering installations.	Item	1	0.000	0.000
E15	Electrical Engineering Installation	Sundries	Allow to identification labels and charts etc.	Item	1	0.000	0.000
E16	Electrical Engineering Installation	Sundries	Allow for testing and commissioning of complete electrical installation.	Item	1	0.000	0.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
E17	Electrical Engineering Installation	Sundries	Allow for documents As installed drawings Operation and Maintenance manuals.	Item	1	0.000	0.000
E18	Electrical Engineering Installation	Small Power Accessories and cable and Conduits Installation Note	Supply and installd and connect test and commissioning of the following wiring devices including SS cover plate connect test of the conduits and cables and back box and junction box form distribution board from the following as required as shown on drawing and specification	Item	0	0.000	0.000
E19	Electrical Engineering Installation	Small Power Accessories and cable and Conduits Installation	13A DP twin switched socket outlet	No	21	6.000	126.000
E20	Electrical Engineering Installation	Small Power Accessories and cable and Conduits Installation	30A cooker socket	No	1	6.000	6.000
E21	Electrical Engineering Installation	Small Power Accessories and cable and Conduits Installation	20A DP flux outlet for AC	No	5	6.000	30.000
E22	Electrical Engineering Installation	Small Power Accessories and cable and Conduits Installation	20A weatherproof DP flux outlet for WH	No	2	6.000	12.000
E23	Electrical Engineering Installation	Small Power Accessories and cable and Conduits Installation	13 A unswitched fused spur unit outlet for EF	No	3	6.000	18.000
E24	Electrical Engineering Installation	Small Power Accessories and cable and Conduits Installation	20A Dp switch for WH and AC	No	7	6.000	42.000
E25	Electrical Engineering Installation	Small Power Accessories and cable and Conduits Installation	20A weatherproof TPN isolator for Booster pump	No	1	12.000	12.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
E26	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation Note	Supply and install and connect test of the conduits and cables form distribution board from the following .Supply and install connect test and commissioning of the following wiring devices including SS cover plate connect test of the conduits and cables and back box and junction box form distribution board from the following as required as shown on drawing and specification.	Item	0	0.000	0.000
E27	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	Lighting switch 10A Double pole one way one gang	No	3	6.000	18.000
E28	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	Ditto one way two gang	No	3	6.000	18.000
E29	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	Ditto one way three gang	No	11	6.000	66.000
E30	Electrical Engineering Installation	Lighting Fixture Note	Supply and install and connect test and commissioning of the following lighting fixtures and including lamps and electronic ballasts and control gear and wires and cables and all necessary accessories complete as specified and as shown on the drawings.	Item	0	0.000	0.000
E31	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	40w fluorescent fitting light fixture	No	10	12.000	120.000
E32	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	40w fluorescent light fixture for toilet	No	2	12.000	24.000
E33	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	40w led downlight	No	7	12.000	84.000
E34	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	25w led wall mounted light fixture	No	2	12.000	24.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
E35	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	25w led wall mounted light fixture	No	3	12.000	36.000
E36	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	25w led wall mounted light fixture whether proof IP66	No	11	12.000	132.000
E37	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	7w led mirror light	No	2	12.000	24.000
E38	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	20w compound wall light with whether proof IP65	No	13	12.000	156.000
E39	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	Ceiling fan	No	5	15.000	75.000
E40	Electrical Engineering Installation	Lighting Accessories and cable and conduits installation	Wall mounted exhaust fan	No	3	10.000	30.000
GN1	TV System Installation	TV System Installation	Cable and conduit to TV point in concealed installation from satellite	No	4	25.000	100.000
GN2	TV System Installation	Outlet	Flush mounted TV Satellite outlet	No	1	25.000	25.000
GN3	TV System Installation	TV System Installation	Allow for co axial cable in concealed conduit from dish antenna to satellite switcher with all necessary accessories and trunking and conduits and trays and supports etc.	Item	1	100.000	100.000
GN4	Telephone System	TV System Installation	Cable and conduits to telephone outlet points in concealed installation from telephone junction box to IP phone expansion module for reception	No	4	50.000	200.000
GN5	Telephone System	Outlet	Cat 6E telephone outlet	No	4	10.000	40.000
GN6	Telephone System	Junction box	Telephone junction box	No	1	50.000	50.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
GN7	Telephone System	Excavation	Supply and laying 80 pair telephone cable including trench excavation and backfilling and ducts and bedding caution tape etc all as per site conditions	Item	1	75.000	75.000
GN8	Telephone System	Cables	80 pair external grade telephone cable from mantel terminal box to main telephone junction box at main building Electrical room.	Item	1	50.000	50.000
GN9	Telephone System	Draw Pits	450 and 450 and 500 mm deep internal size telephone draw pit RCC wall and rendering internally and 75 mm PCC at bottom with 450 and 450 mm medium duty ductile iron cover and frame.	Item	1	50.000	50.000
GN10	Structured Cabling system	Accessories	Wi Fi access units including all accessories and fittings	item	1	100.000	100.000
GN11	Structured Cabling system	Accessories	Any other works not specifically enumerated under the works above with implementation cost	Item	1	0.000	0.000
GN12	Structured Cabling system	Cable	Cableconduits and accessories to RJ 45 Category 6A dual socket outlet	No	4	10.000	40.000
GN13	Structured Cabling system	Cable	Drop lead 3m long Category 6A	No	2	50.000	100.000
GN14	Structured Cabling system	Cable	Drop lead 6m long Category 6A	No	2	75.000	150.000
GN15	Structured Cabling system	patch panel	16 Port Cat 6A Patch panel	No	1	100.000	100.000
GN16	Structured Cabling system	Structured Cabling system	500mm single mode fiber LC SC Patch cords	No	1	50.000	50.000



BILL NO 07 3 NO. HOUSING UNITS

Item Code	Item Name	Item Details	Additional Information	UOM	Quantity	Unit Price In Figure	Total Price In Figure
GN17	Structured Cabling system	Accessories	Accessories and stacking kits and cable management and cable organizer and cable channels and supports all types of cords and pig tail connectors including termination etc complete	Item	1	0.000	0.000
GN18	Telephone and Structured Cabling and CCTV System	Sundries	Allow for builders work in connection with electrical installation including holes and chases and sleeves and ducts and cable tray trucking and panel backboards or formwork support and access panels and cover plates etc.	Item	1	0.000	0.000
GN19	Telephone and Structured Cabling and CCTV System	Sundries	Allow for incidental works such as co ordination with other engineering installations.	Item	1	0.000	0.000
GN20	Telephone and Structured Cabling and CCTV System	Sundries	Allow to identification labels charts etc.	Item	1	0.000	0.000
GN21	Telephone and Structured Cabling and CCTV System	Sundries	Allow for testing and commissioning of complete electrical installation.	Item	1	0.000	0.000
GN22	Telephone and Structured Cabling and CCTV System	Sundries	Allow for documents As Installed drawings Operation and Maintenance manuals.	Item	1	0.000	0.000
TOTAL 1 NOS HOUSING UNITS							79,997.000
TOTAL 3 NOS HOUSING UNITS							239,991.000



**CONSTRUCTION, COMPLETION AND MAINTENANCE OF PROPOSED (20NOS) HOUSING
UNITS AND MAINTENANCE WORKS FOR THE EXISTING (32) HOUSES FOR THE
MINISTRY**

GRAND SUMMARY

Priced Bill of Quantities

Transfer the Contract Summary of Contract Value to the Form of Tender

SI No.	Description	R.O WITHOUT VAT 5%
1.	BILL NO 01 PRELIMINARIES	227,580.000
2.	BILL NO 02 DAY WORKS	88,252.500
3.	BILL NO 00 PROVISIONAL SUMS	200,000.000
4.	BILL NO 03 NEW HOUSING UNITS 20 NOS	1,965,370.940
5.	BILL NO 04 EXTERNAL WORKS AND EXTERNAL SERVICES	28,455.000
6.	BILL NO 05 MAINTENANCE WORKS FOR THE EXISTING HOUSING UNITS - 29 NO.	1,436,308.650
7.	BILL NO 06 PROTECTION AND STORM WATER DRAINAGE	265,674.675
8.	BILL NO 07 3 NO. HOUSING UNITS	239,991.000
9.	CONTINGENCIES 10% (Bill No 03 +Bill No 04 + Bill No 05 + Bill No 06 + Bill No 07)	393,580.027
Total Contract Value		4,845,212.792

